NIT No.: Date:

STANDARD BIDDING DOCUMENT FOR PROCUREMENT OF WORKS

Divyang Friendly Park at Gandhi Garden, Firozpur Cantt, Punjab
Under AMRUT 2.0 Scheme

Volume -3

Project Value: Capital Cost: Part-A Percentage Rate Rs. 40.13 Lakh
O&M Cost Part-B Percentage Rate Rs. 11.03 Lakh.

Price Bid

September, 2024

NIT No.:	**Date:**				
Name of Work: Divyang Friendly Park at Gandhi Garden, Firozpur Cantt, Punjab Under AMRUT 2.0 Scheme					
	Name of Bidder:				
	General Summary				
S.No	**Particulars**				**Total Amount (Rs)**
	Capital Works: Percentage Rate				
1	**Estimate Amount (Part A) (In Rs):**	**4,012,650.56**	**Entre Rate below** without (+), (-) and (%) symbols For "**At Par**" Rate, Enter Zero.		
2	**5 years' O& M (PART-B)**	**1,103,271.00**			
	Estimate Amount (Part A and B) (In Rs):	**5,115,921.56**			
	Percentage Above/Below/At Par	**Select**	0.00	**%**	
	Amount as per percentage quoted, Percentage Rate (Part A, B & C) (Amount in Rs)				**-**
Amount In Words		**No Rupees and No Paise**			
Provisional Sum (Not part of bidding) Rs in Lakh				=	2.01

NIT No.:		Date:					
Name of Work: Development of Green Spaces/Park at Focal Point, Rajpura, District Patiala, Punjab Under AMRUT 2.0 Scheme							
S.no.	**CSR Ref.**	**Description**	**Unit**	**Qty**	**Rate (Rs)**	**Rate (Rs. In Words)**	**Amount (Rs)**
		Capital Works CSR Items (Part - A)- CIVIL					
		Development of Parks					
		Turfing of Lawn :					
	32.9	Fine grassing including uprooting rank vegetation and weeds by digging the area to a depth of 30 cm, removing all weeds and other growth with roots by forking repeatedly, breaking clods, rough dressing, flooding with water, uprooting fresh growth after 10 to 15 days,mixing fertilizer and then fine dressing for planting new grass, including disposal of all rubbish with all leads and lifts, watering,weeding and maintenance for 30 days or till thick lawn is formed.					
1	a	Planting Selection no. 1 grass roots in rows 5.0 cm apart in both directions.	Sqm	1400.00	69.00	Sixty Nine Rupees and No Paise	96,600.00
2	32.1	Supplying and stacking at site of work well decayed farm yard manure from approved site of decayed farm yard manure from approved site of work including screening through sieve of I.S.designation 16 mm with 5 km lead	Cum	8.40	625.00	Six Hundred Twenty Five Rupees and No Paise	5,250.00
		Supplying and Planting Permanent Trees:					
3	32.13	Digging of pits in all kinds of soil & refilling the same, with the excavated earth mixed with well decayed farm yard manure @ 30% of pit volume and insecticide for termite control.	cum	17.72	388.00	Three Hundred Eighty Eight Rupees and No Paise	6,875.00
4	32.14	Supplying and planting permanent trees in prepared pits and watering.	Each	42.00	170.00	One Hundred Seventy Rupees and No Paise	7,140.00
		Planting Permanent Shrubs :					
5	32.13	Digging of pits in all kinds of soil & refilling the same, with the excavated earth mixed with well decayed farm yard manure @ 30% of pit volume and insecticide for termite control.	Cum	63.72	388.00	Three Hundred Eighty Eight Rupees and No Paise	24,724.00
6	32.18	Supplying & Planting permanent shrubs in prepared pits and watering.		295.00	66.00	Sixty Six Rupees and No Paise	19,470.00
		Planting permanent hedges :					
7	32.34	Planting hedge including digging of trench 60 cm wide to 15 cm depth and mixing FYM fertilizerand insecticides, planting of sapling at 30cm distance from plant to plant in two rows.		430.00	165.00	One Hundred Sixty Five Rupees and No Paise	70,950.00
8	32.26	Planting ground covers (ordinary) including digging of beds to 15 cm depth and mixing FYM, Fertilizer, insecticides, planting of saplings at 25 cm distance from plant to plant and row to row	Sqm	120.00	277	Two Hundred Seventy Seven Rupees and No Paise	33,240.00
		Supply and Laying of soil -Good earth					
9	5.2 (i)	Earth,Surkhi, Sand, Earth, Fly Ash, Bajri, Ballast, Stone Boulders, Kankar and Building Rubbish, Earth.	Cum	90.00	195.17	One Hundred Ninety Five Rupees and Seventeen Paise	17,566.00
	4.1 (A)	Stone(building or pitching) Sand, Earth, FlyAsh, Bajri, Shingle, Spalls, Brick Bats, Brick Ballast and Stone Metal					

S.no.	CSR Ref.	Description	Unit	Qty	Rate (Rs)	Rate (Rs. In Words)	Amount (Rs)
10		Rate for loading into wagon trucks or boats withiin 15 metres lead	Cum	90.00	19.48	Nineteen Rupees and Forty Eight Paise	1,754.00
11	6.4	Extra for Compansation & royality for ordinary earth /ordinary clay taken from private land	Cum	90.00	60.22	Sixty Rupees and Twenty Two Paise	5,420.00
12	32.51 (L.R)	**Preparation of mounds** of various size and shapes including supply of good earth & Sand filling, in layers not exceeding 20 cm in depth, breaking of clods, watering each layer, dressing etc. lead up to 50 m and lift upto 1.5 m complete as per direction.	Cum	90.00	320.00	Three Hundred Twenty Rupees and No Paise	28,800.00
		Planting Rose beds :					
13	32.30	Planting rose beds including digging of beds to 15 cm depth and mixing FYM, fertilizer and insecticides,triangular planting of sapling at 60 cm distance from plant to plant and row to row.	Sqm	38.40	174	One Hundred Seventy Four Rupees and No Paise	6,682.00
		Planting Seasonal Flowers :					
14	32.22 (a)	Planting seedlings including digging of beds to 15 cm depth and mixing FYM, fertilizer and insecticides, planting of seedlings at 20cm distance from plant to plant and row to row.	Sqm	38.40	259	Two Hundred Fifty Nine Rupees and No Paise	9,946.00
		Brick Lining					
15	32.54 (d)	Edging of paths/ beds with bricks/tiles laid dry, including required excavation, refilling, consolidating with hand and spreading surplus.**Brick inclined at 60 deg to horizontal**	Mtr	151.20	60	Sixty Rupees and No Paise	9,072.00
	24.46	Informatory sign board 800x600mm rectangular as per IRC 67- 2012 with high intensity Microprismatic grade retro reflective Sheeting as per ASTM D 4956 – 09 and as per IRC 67 – 2012. fixed over 4mm thick aluminium Composite material (ACM) sheeting having aluminium skin thickness of 0.4 to 0.5 mm on both sided and fixing the same with suitable size aluminium alloy rivets @ 200 mm c/c to back support frame of 25x25x3mm angle iron supported on a square hollow steel section post 60x60x3.2mm conforming to IS 4923 without cost of definition plate firmly fixed to ground in foundation concrete M-25 of size 0.45x0.45x0.60m for vertical post complete as per clause 801 of MORT&H specifications. Supplier shall provide a warranty as per clause 6.9 of IRC 67-2012 for retro reflective sheeting & a certified copy of test reports from an independent test laboratory conforming to clause 6.7 of IRC 67-2012 .					
16	b(i)	Using high intensity Microprismatic grade retro reflective Sheeting Type IV as per ASTM D 4956 09 and as per IRC 67 2012	Each	3.00	3496.00	Three Thousand Four Hundred Ninety Six Rupees and No Paise	10,488.00

S.no.	CSR Ref.	Description	Unit	Qty	Rate (Rs)	Rate (Rs. In Words)	Amount (Rs)
17	32.57 (a)	**Supply and Installation of Garden Bench:** Chair type garden bench with L-shaped sides made of reinfoced concrete (M-30), thicknes 100 mm, overall height 1000 mm, base width 620 mm. Back and seat shall consist of 5 no. reiforced cocrete planks 1500 mm x 100 mm x50 mm one pank 1500 mmx 200 mm x50 mm. seating height of the benchshal be 450 mm. The bench shal be fixedwith nuts on concrete mount, at holes sealed after assembly and installation	Each	12.00	5299.00	Five Thousand Two Hundred Ninety Nine Rupees and No Paise	63,588.00
18	32.75	Providing and Fixing pair of **plastic dustbins** 100 litre volume each, of two different colour, for dry and wet waste, made of virgin plastic to be mounted on ms rectangular hollow section50x25x3 mm frames pivoted on 3 Ms Square hollow section verticals, 1 m above ground, one 35 cm RHS welded to each vertical member at base and grouted in 180 x 40x 30 cm 1:2:4 cement concrete.	Each	5.00	12753.00	Twelve Thousand Seven Hundred Fifty Three Rupees and No Paise	63,765.00
		Difference in Rates of materials :					
19		Bricks :	1000 nos	1285	149.99	One Hundred Forty Nine Rupees and Ninety Nine Paise	193.00
		Ferozpur					
		Specially Abled/Divyang Friendly Zone Flooring & Sitting Plateform					
20	14.116	Providing and Laying Tactile Flooring full body vitrified , low water absorption below 5%, having excellent slip resistance , very dense, durable and abrasion resistant, solid through colour, fade proof, highly chemical and stain resistance unglazed finish porcelain tile of size 300mm x 300mm x 10mm + 5mm thick, approved profile design, Tec-button/Tec-liner laid in ordinary grey cement and on 20mm thick bed of cement mortar 1:3 filling neat cement slurry between joints with White Cement containing pigment to match the shade complete in all respect. (Tile design and pattern will be as per guidelines issued for persons with disability)	Sqm	35.00	1810.00	One Thousand Eight Hundred Ten Rupees and No Paise	63,350.00
		Construction of Sitting Platform					
21	6.6	Earth work in excavation in foundations trenches etc. in all kinds of soil where Pick-Jumper work is not involved and not exceeding 2.0 metres depth including dressing of bottom and sides of trenches, stacking the excavated soil clear from the edge of excavation and subsequent filling around masonry in 15 cm, layers with compaction including disposal of all surplus soil as directed within lead of 30 metres.	Cum	11.18	182.00	One Hundred Eighty Two Rupees and No Paise	2,035.00
		Cement Concrete 1:8:16					

S.no.	CSR Ref.	Description	Unit	Qty	Rate (Rs)	Rate (Rs. In Words)	Amount (Rs)
22	10.6 (b) ii	Cement Concrete 1:8:16 With Stone Aggregate 40 mm gauge Mixing by mechanical means using concrete mixer volumetric type	Cum	2.49	3127.00	Three Thousand One Hundred Twenty Seven Rupees and No Paise	7,787.00
23	11.5	First class burnt brick work laid in cement sand mortar 1:5 in foundation and plinth	Cum	5.13	5013.00	Five Thousand Thirteen Rupees and No Paise	25,717.00
24		**Deduct 10% labour rate as per Notes-ii of chapter**	Cum	5.13	-132.70	One Hundred Thirty Two Rupees and Seventy Paise	-681.00
25	10.27	Damp proof course 4cm thick of cement concrete 1:2:4 with water proofing compound as per manufactures guidelines	**Sqm**	12.7	244	Two Hundred Forty Four Rupees and No Paise	3,099.00
26	11.6	First class burnt brick work laid in cement sand mortar 1:5 in first storey upto 4 metres above plinth level.	Cum	5.72	5151.00	Five Thousand One Hundred Fifty One Rupees and No Paise	29,464.00
27		**Deduct 10% labour rate as per Notes-ii of chapter**	Cum	5.72	-146.40	One Hundred Forty Six Rupees and Forty Paise	-838.00
28	15.9	12.5 mm thick cement plaster 1:4	sqm	49.68	189.00	One Hundred Eighty Nine Rupees and No Paise	9,390.00
29	16.59	Finishing walls with acrylic smooth exterior paint of required shade with two or more coats applied @ 1.67 litre/10Sqm over and including base coat of water proofing Cement Paint applied @ 2.20 Kg/10 Sqm	sqm	49.68	120.00	One Hundred Twenty Rupees and No Paise	5,962.00
30	9.8	Centrring and shuttering for flat surfaces such as suspended floors roofs, landings, chajjas, shelves etc.	Sqm	15.46	532.00	Five Hundred Thirty Two Rupees and No Paise	8,223.00
31	10.20	Reinforced cement concrete M-20 mechanically batch mixed using batch type concrete mixer as per IS:1791 and vibrated by needle vibrator but excluding steel reinforcement centring and shuttering in superstructure.	Cum	2.48	5902.00	Five Thousand Nine Hundred Two Rupees and No Paise	14,661.00
32	18.18	Cold twisted detormed (Ribbed/ Tor steel) Bars (Fe 500 grade as per IS 1786-2008) , for R.C.C works, where not including in the complete rate of RCC including bending and binding placing in position complete	Qtl	1.99	6497.00	Six Thousand Four Hundred Ninety Seven Rupees and No Paise	12,911.00
33		Add as per AC slip-4	Qtl	1.99	933.24	Nine Hundred Thirty Three Rupees and Twenty Four Paise	1,855.00
		Difference in Rates of materials :					
34		Stone Metal 40mm gauge	Cum	2.49	-222.53	Two Hundred Twenty Two Rupees and Fifty Three Paise	-555.00
		Mirthal					
35		Coarse Aggregate 11.2mm	Cum	1.54	-227.99	Two Hundred Twenty Seven Rupees and Ninety Nine Paise	-352.00
		Haryaal					
36		Coarse Sand	Cum	1.92	-143.92	One Hundred Forty Three Rupees and Ninety Two Paise	-276.00
		Lohand Khad					

S.no.	CSR Ref.	Description	Unit	Qty	Rate (Rs)	Rate (Rs. In Words)	Amount (Rs)
37		Bricks :	1000 nos	5208	149.99	One Hundred Forty Nine Rupees and Ninety Nine Paise	782.00
		Ferozpur					
38		Coarse Aggregate 20/25mm	Cum	1.027	-260.66	Two Hundred Sixty Rupees and Sixty Six Paise	-268.00
		Pathankoat					
		Carriage of materials :					
	5.2 (i)	Earth,Surkhi,Sand,earth,Fly Ash,Bajri,Ballast,Stone Boulders,Kankar and Building Rubbish,Earth					
39		Stone Metal 40mm gauge	Cum	2.49	706.66	Seven Hundred Six Rupees and Sixty Six Paise	1,760.00
		Mirthal					
40		Coarse Aggregate 11.2mm	Cum	1.54	742.02	Seven Hundred Forty Two Rupees and Two Paise	1,144.00
		Haryaal					
41		Coarse Sand	Cum	1.92	721.13	Seven Hundred Twenty One Rupees and Thirteen Paise	1,383.00
		Lohand Khad					
42		Coarse Aggregate 20/25mm	Cum	1.03	719.52	Seven Hundred Nineteen Rupees and Fifty Two Paise	740.00
		Pathankoat					
43		Fine sand	Cum	4.75	266.64	Two Hundred Sixty Six Rupees and Sixty Four Paise	1,268.00
		35km					
		Katcha & Paved Pathway					
44	6.2 (a)	Earth work excavation in ordinary soil, exclusive of compensation of earth:-Kassi work undressed involving an average horizontal throw up to 2.0 metres and an average vertical lift up to 0.5 metres including breaking of clods.	Cum	253.90	77.00	Seventy Seven Rupees and No Paise	19,551.00
	24.4	Compaction of Earth work					
45	(c)	Compaction of earth work & Preparation of sub grade including loosening, leveling of earth 225mm thick top layer, rough dressing of soil, final dressing of earth to give level, camber, watering, rolling with road roller, compacting the bed to achieve minimum dry density as given in the Table 300-2 as per Technical clause 305 of MORT&H specifications. (In case of link roads earth work to be done by villagers)	Sqm	804.50	6.00	Six Rupees and No Paise	4,827.00
	10.6	**Cement Concrete 1:8:16**					
46	10.6 (b) ii	Cement Concrete 1:8:16 With Stone Aggregate 40 mm gauge Mixing by mechanical means using concrete mixer volumetric type	Cum	51.20	3127.00	Three Thousand One Hundred Twenty Seven Rupees and No Paise	160,103.00

S.no.	CSR Ref.	Description	Unit	Qty	Rate (Rs)	Rate (Rs. In Words)	Amount (Rs)
47	14.136	Providing and laying 50mm thick factory made cement concrete inter locking paver block of M-30 grade machine made rubber moulded smooth finishwith strong vibratory process or with vibrohydraulic compaction machine and of approved size and design / shape laid in ordinary grey and pattern over and including 40 mm thick compacted bed of coarse sand, filling the joints with fine sand etc.all completeas per directions of Engineer -in -charge IS code- 15658(2006)	Sqm	469.40	602.00	Six Hundred Two Rupees and No Paise	282,579.00
48	14.141	Extra Cost for using darker fast shade for interlocking pavers Tiles of any shape & thickness instead of grey colours.	Sqm	102.40	65.00	Sixty Five Rupees and No Paise	6,656.00
49	14.59	Precast chequred tiles of 20mm minimum thickness in ordinary grey cement without chips laid on 20mm thick bed of cement mortar 1:3 with neat cement slurry between joints and over the base for floors, treads of steps and landings	sqm	465.00	788.00	Seven Hundred Eighty Eight Rupees and No Paise	366,420.00
		Difference in Rates of materials :					
50		Coarse sand :	Cum	30.56	-143.92	One Hundred Forty Three Rupees and Ninety Two Paise	-4,398.00
		Lohand Khad					
51		Stone Metal 40 mm	Cum	51.20	-222.53	Two Hundred Twenty Two Rupees and Fifty Three Paise	-11,394.00
		Mirthal					
		Carriage of materials :					
	5.2 (i)	Earth,Surkhi,Sand,earth,Fly Ash,Bajri,Ballast,Stone Boulders,Kankar and Building Rubbish,Earth					
52		Coarse sand :	Cum	30.56	721.13	Seven Hundred Twenty One Rupees and Thirteen Paise	22,035.00
		Lohand Khad					
53		Stone Metal 40 mm	Cum	51.20	706.66	Seven Hundred Six Rupees and Sixty Six Paise	36,181.00
		Mirthal					
54		Fine sand	Cum	38.79	266.64	Two Hundred Sixty Six Rupees and Sixty Four Paise	10,343.00
		35km					
		Devolpment of Parking					
		Cement Concrete 1:8:16					
55	10.6 (b) ii	Cement Concrete 1:8:16 With Stone Aggregate 40 mm gauge Mixing by mechanical means using concrete mixer volumetric type	Cum	95.50	3127.00	Three Thousand One Hundred Twenty Seven Rupees and No Paise	298,629.00

S.no.	CSR Ref.	Description	Unit	Qty	Rate (Rs)	Rate (Rs. In Words)	Amount (Rs)
56	14.139	Providing and laying 80 mm thick factory made cement concrete interlocking Paving blocks of M- 40 grade manufactured by block making machine equipped with steel mould clamped to a strong vibratory table with hydraulic pressure for compaction of concrete as per IRC SP 63 -2014 and of approved size and design / shape laid in Ordinary Grey Colour and pattern over and including 40 mm thick compacted bed of coarse sand, filling the joints with fine sand etc, all complete as per directions of Engineer-in-Charge.	Sqm	918.71	805.00	Eight Hundred Five Rupees and No Paise	739,562.00
		Cement Concrete 1:2:4					
57	10.13 (a) ii	Cement Concrete 1:2:4 With stone ballast or shingle Mixing by mechanical means using concrete mixer volumetric type	cum	3.27	4670.00	Four Thousand Six Hundred Seventy Rupees and No Paise	15,253.00
58	14.141	Extra cost for using darker fast shade for interlocking pavers tiles of any shape & thickness instead of grey colours	Sqm	183.74	65.00	Sixty Five Rupees and No Paise	11,944.00
59	24.41 (a)	Providing and laying factory made rubber moulded smooth finish cement concrete Kerb M-20 grade 250mm high with bottom width 165mm and top width 115mm made over strong vibratory table and fixing with cement mortar 1:2 as per MORT&H specifications	Mtr	50.00	357.56	Three Hundred Fifty Seven Rupees and Fifty Six Paise	17,878.00
		Difference in Rates of materials :					
60		Coarse sand :	Cum	38.22	-143.92	One Hundred Forty Three Rupees and Ninety Two Paise	-5,501.00
		Lohand Khad					
61		Stone Metal 40 mm	Cum	95.50	-222.53	Two Hundred Twenty Two Rupees and Fifty Three Paise	-21,252.00
		Mirthal					
62		Coarse Aggregate 11.2mm	Cum	1.76	-227.99	Two Hundred Twenty Seven Rupees and Ninety Nine Paise	-403.00
		Haryaal					
63		Coarse Aggregate 20/25mm	Cum	1.18	-260.66	Two Hundred Sixty Rupees and Sixty Six Paise	-307.00
		Pathankoat					
		Carriage of materials :					
	5.2 (i)	Earth,Surkhi,Sand,earth,Fly Ash,Bajri,Ballast,Stone Boulders,Kankar and Building Rubbish,Earth					
64		Coarse sand :	Cum	38.22	721.13	Seven Hundred Twenty One Rupees and Thirteen Paise	27,561.00
		Lohand Khad					
65		Stone Metal 40 mm	Cum	95.50	706.66	Seven Hundred Six Rupees and Sixty Six Paise	67,487.00
		Mirthal					
66		Coarse Aggregate 11.2mm	Cum	1.76	742.02	Seven Hundred Forty Two Rupees and Two Paise	1,309.00
		Haryaal					
67		Coarse Aggregate 20/25mm	Cum	1.18	719.52	Seven Hundred Nineteen Rupees and Fifty Two Paise	847.00

S.no.	CSR Ref.	Description	Unit	Qty	Rate (Rs)	Rate (Rs. In Words)	Amount (Rs)
		Pathankoat					
68		Fine sand	Cum	50.51	266.64	Two Hundred Sixty Six Rupees and Sixty Four Paise	13,467.00
		35km					
		Construction of Badminton Court					
	32.54 (a)	Edging of paths/bed with bricks/tiles laid dry including required excavation, refilling, consolidating with hand and spreading surplus.Bricks laid length wise with half brick depth					
69			Mtr	78.4	37.00	Thirty Seven Rupees and No Paise	2,900.80
70	6.2 (a)	Earth work excavation in ordinary soil, exclusive of compensation of earth:- Kassi work undressed involving an average horizontal throw up to 2.0 metres and an average vertical lift up to 0.5 metres including breaking of clods.	cum	24.92	77.00	Seventy Seven Rupees and No Paise	1,918.92
		Cement Concrete 1:8:16					
71	10.6 (b) ii	Cement Concrete 1:8:16 With Stone Aggregate 40 mm gauge Mixing by mechanical means using concrete mixer volumetric type	Cum	0.04	3127.00	Three Thousand One Hundred Twenty Seven Rupees and No Paise	112.58
		Cement Concrete 1:2:4					
72	10.13 (a) ii	Cement Concrete 1:2:4 With stone ballast or shingle Mixing by mechanical means using concrete mixer volumetric type	Cum	0.16	4670.00	Four Thousand Six Hundred Seventy Rupees and No Paise	756.54
73	18.53	Steel work in built up tubular pipes (round, square or rectangular hollow tubes etc. ISI Marked) for flat shed (ie.Where no truss work is involved) including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.	Qtl	0.2136	9490.00	Nine Thousand Four Hundred Ninety Rupees and No Paise	2,027.07
74		Add as per AC slip-4 for Hollow Section	Qtl	0.2136	373.30	Three Hundred Seventy Three Rupees and Thirty Paise	79.74
		Difference in Rates of materials :					
75		Stone Metal 40mm gauge	Cum	0.04	-222.53	Two Hundred Twenty Two Rupees and Fifty Three Paise	-8.02
		Mirthal					
76		Coarse Aggregate 11.2mm	Cum	0.09	-227.99	Two Hundred Twenty Seven Rupees and Ninety Eight Paise	-19.95
		Haryaal					
77		Coarse Sand	Cum	0.07	-143.92	One Hundred Forty Three Rupees and Ninety Two Paise	-10.50
		Lohand Khad					
78		Bricks :	Cum	0.392	149.99	One Hundred Forty Nine Rupees and Ninety Eight Paise	58.80
		Ferozpur					
79		Coarse Aggregate 20/25mm	Cum	0.06	-233.92	Two Hundred Thirty Three Rupees and Ninety Two Paise	-13.65
		Pathankoat					
		Carriage of materials :					

S.no.	CSR Ref.	Description	Unit	Qty	Rate (Rs)	Rate (Rs. In Words)	Amount (Rs)
	5.2 (i)	Earth,Surkhi,Sand,earth,Fly Ash,Bajri,Ballast,Stone Boulders,Kankar and Building Rubbish,Earth					
80		Stone Metal 40mm gauge	Cum	0.04	706.66	Seven Hundred Six Rupees and Sixty Six Paise	25.44
		Haryaal					
81		Coarse Aggregate 11.2mm	Cum	0.09	742.02	Seven Hundred Forty Two Rupees and Two Paise	64.92
		Haryaal					
82		Coarse Sand	Cum	0.07	721.13	Seven Hundred Twenty One Rupees and Twelve Paise	52.58
		Lohand Khad					
83		Coarse Aggregate 20/25mm	Cum	0.06	719.52	Seven Hundred Nineteen Rupees and Fifty Two Paise	41.97
		Pathankoat					
84		Fine Sand	Cum	0.02	266.64	Two Hundred Sixty Six Rupees and Sixty Four Paise	4.80
		35km					
		Construction of Pergola					
85	6.6	Earth work in excavation in foundations trenches etc. in all kinds of soil where Pick-Jumper work is not involved and not exceeding 2.0 metres depth including dressing of bottom and sides of trenches, stacking the excavated soil clear from the edge of excavation and subsequent filling around masonry in 15 cm, layers with compaction including disposal of all surplus soil as directed within lead of 30 metres.	cum	0.98	182.00	One Hundred Eighty Two Rupees and No Paise	179.00
		Cement Concrete 1:8:16					
86	10.6 (b) ii	Cement Concrete 1:8:16 With Stone Aggregate 40 mm gauge Mixing by mechanical means using concrete mixer volumetric type	cum	0.33	3127.00	Three Thousand One Hundred Twenty Seven Rupees and No Paise	1,032.00
		Cement Concrete 1:2:4					
87	10.13 (a) ii	Cement Concrete 1:2:4 With stone ballast or shingle Mixing by mechanical means using concrete mixer volumetric type	cum	0.13	4670.00	Four Thousand Six Hundred Seventy Rupees and No Paise	608.00
88	18.53	Steel work in built up tubular pipes (round, square or rectangular hollow tubes etc. ISI Marked) for flat shed (ie.Where no truss work is involved) including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.	qtl	25.32	9490.00	Nine Thousand Four Hundred Ninety Rupees and No Paise	240,332.00
89		Add as per AC slip-4 **for Hollow Section**	qtl	25.32	373.30	Three Hundred Seventy Three Rupees and Thirty Paise	9,454.00
		Painting for Steel Works :					
90	16.17	Painting two or more coats excluding priming coat with synthetic enamel paint f in all shades on wood work, metallic or plastered concrete surface to give an even shade .	Sqm	112.68	66.00	Sixty Six Rupees and No Paise	7,437.00

S.no.	CSR Ref.	Description	Unit	Qty	Rate (Rs)	Rate (Rs. In Words)	Amount (Rs)
91	18.31	Providing & Fixing of 10 gauge welded mesh of 25mm x 25mm size fixed on existing MS Hollow pipe / steel glazing with MS flat 20mm x 6mm beeding complete in all respect including painting two coats with Synthetic Enamel Paint and Priming Coat	Sqm	33.31	655.00	Six Hundred Fifty Five Rupees and No Paise	21,816.00
		Difference in Rates of materials :					
92		Stone Metal 40mm gauge	Cum	0.33	-222.53	Two Hundred Twenty Two Rupees and Fifty Three Paise	-74.00
		Mirthal					
93		Coarse Aggregate 11.2mm	Cum	0.07	-227.99	Two Hundred Twenty Seven Rupees and Ninety Nine Paise	-17.00
		Haryaal					
94		Coarse Sand	Cum	0.06	-143.92	One Hundred Forty Three Rupees and Ninety Two Paise	-9.00
		Lohand Khad					
95		Coarse Aggregate 20/25mm	Cum	0.05	-260.66	Two Hundred Sixty Rupees and Sixty Six Paise	-13.00
		Pathankoat					
		Carriage of materials :					
	5.2 (i)	Earth,Surkhi,Sand,earth,Fly Ash,Bajri,Ballast,Stone Boulders,Kankar and Building Rubbish,Earth					
96		Stone Metal 40mm gauge	Cum	0.33	706.66	Seven Hundred Six Rupees and Sixty Six Paise	234.00
		Mirthal					
97		Coarse Aggregate 11.2mm	Cum	0.07	742.02	Seven Hundred Forty Two Rupees and Two Paise	53.00
		Haryaal					
98		Coarse Sand	Cum	0.06	721.13	Seven Hundred Twenty One Rupees and Thirteen Paise	43.00
		Lohand Khad					
99		Fine Sand	Cum	0.17	266.64	Two Hundred Sixty Six Rupees and Sixty Four Paise	44.00
		35km					
100		Coarse Aggregate 20/25mm	Cum	0.05	719.52	Seven Hundred Nineteen Rupees and Fifty Two Paise	34.00
		Pathankoat					
		Repair Works					
		Existing Pathway					
101	8.43	Taking out existing CC interlocking paver blocks from footpath/ central verge/pavement, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in- Charge.	Sqm	209.60	107.00	One Hundred Seven Rupees and No Paise	22,428.00

S.no.	CSR Ref.	Description	Unit	Qty	Rate (Rs)	Rate (Rs. In Words)	Amount (Rs)
102	14.136	Providing and laying 50mm thick factory made cement concrete inter locking paver block of M-30 grade machine made rubber moulded smooth finishwith strong vibratory process or with vibrohydraulic compaction machine and of approved size and design / shape laid in ordinary grey and pattern over and including 40 mm thick compacted bed of coarse sand, filling the joints with fine sand etc.all completeas per directions of Engineer -in -charge IS code- 15658(2006)	Sqm	209.60	602.00	Six Hundred Two Rupees and No Paise	126,180.00
		Existing Fountain & Gazebo					
103	8.35	Dismantling glazed tiles (to be carefully removed).	Sqm	60.50	107.00	One Hundred Seven Rupees and No Paise	6,474.00
104	14.127	Providing and fixing 1st quality ceramic glazed wall tiles Matt/Semi Matt/Glosy/Highly Gloss finish/Highlighter/emboss conforming to IS : 15622 (thickness to be specified by the manufacture of approved make in all colours, shades except burgundy, bottle green, black of size 450 x 310 mm as approved by Engineer-in- Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:4 (1 cement: 4 fine sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	Sqm	60.50	795.00	Seven Hundred Ninety Five Rupees and No Paise	48,098.00
		Existing Entry Gate & Boundary Wall					
	8.31	**Scraping**					
105	c	Cement plaster	Sqm	25.00	36.00	Thirty Six Rupees and No Paise	900.00
106	15.9	12.5 mm thick cement plaster 1:4	Sqm	25.00	189.00	One Hundred Eighty Nine Rupees and No Paise	4,725.00
107	16.14	Finishing walls with cement based water soluble paint exterior such as snowecem, robbiacem etc. on old work one coat to give an even shade	Sqm	1375.00	39.00	Thirty Nine Rupees and No Paise	53,625.00
108	16.17	Painting two or more coats excluding priming coat with synthetic enamel paint in all shades on wood work, metallic or plastered, concrete surface to give an even shade.	Sqm	1475.00	66.00	Sixty Six Rupees and No Paise	97,350.00
109	14.89 a	Providing and laying flamed finish Granite stone 18mm thick in flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge : Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	Sqm	45.00	2104.00	Two Thousand One Hundred Four Rupees and No Paise	94,680.00
		Existing Toilet Block					

S.no.	CSR Ref.	Description	Unit	Qty	Rate (Rs)	Rate (Rs. In Words)	Amount (Rs)
110	30.32 (v)	Providing and fixing in position vitreous chinaware white lavatory suites of approved make (to the approval of Engineer-in-charge) consisting of C.P. brass waste 32mm dia with one C.P. brass pillar tap including Rack Bolt Screw Pair 115mm long complete in all respect. Size 560mm x 430mm x 820mm	Each	1.00	3917.00	Three Thousand Nine Hundred Seventeen Rupees and No Paise	3,917.00
111	30.43 (i)	Providing and fixing vitreous chinaware pedestal of approved make (to the approval of Engineer-in-charge) for wash hand basin complete in all respect. (i) Vitreous chinaware standard white pedestal for wash hand basin.	Each	1.00	2010.00	Two Thousand Ten Rupees and No Paise	2,010.00
112	16.14	Finishing walls with cement based water soluble paint exterior such as snowecem, robbiacem etc. on old work one coat to give an even shade	Sqm	105.00	39.00	Thirty Nine Rupees and No Paise	4,095.00
113	14.127	Providing and fixing 1st quality ceramic glazed wall tiles Matt/Semi Matt/Glosy/Highly Gloss finish/Highlighter/emboss conforming to IS : 15622 (thickness to be specified by the manufacture of approved make in all colours, shades except burgundy, bottle green, black of size 450 x 310 mm as approved by Engineer-in- Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:4 (1 cement: 4 fine sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	Sqm	32.50	795.00	Seven Hundred Ninety Five Rupees and No Paise	25,838.00
114	8.31	Scraping: Cement Plaster	Sqm	32.50	36.00	Thirty Six Rupees and No Paise	1,170.00
115	17.60	Providing and fixing of 25mm thick PVC flush door shutters (without chowkhat) upto 737mm width of colour and shade as approved by Engineer-in-charge made out of a one piece Multi chamber extruded PVC Plug section of the size of 762mm X 25mm or less as per requirement with an average wall thickness of 1mm ± 0.3mm. PVC Plug foam end cap of size 23x10mm are provided on both vertical edges to ensure the overall thickness of 25mm. An MS tube having dimensions 19mm x 19mm is inserted along the hinge side of the door. Core of the door shutter should be filled with High Density Polyurethane Code Description Unit Quantity Rate Amount foam. The Top & Bottom edges of the shutter are covered with an end-cap of the size 25mm X 11mm. Door shutter shall be reinforced with special polymeric reinforcements as per manufactures' specification and drawing to take up necessary hardware and fixtures. Stickers indicating the locations of hardware will be pasted at appropriate places	Sqm	5.49	3425.00	Three Thousand Four Hundred Twenty Five Rupees and No Paise	18,804.00
		Difference in Rates of materials :					
116		Coarse sand :	Cum	8.38	-143.92	One Hundred Forty Three Rupees and Ninety Two Paise	-1,207.00

S.no.	CSR Ref.	Description	Unit	Qty	Rate (Rs)	Rate (Rs. In Words)	Amount (Rs)
		Lohand Khad					
		Carriage of materials :					
	5.2 (i)	Earth,Surkhi,Sand,earth,Fly Ash,Bajri,Ballast,Stone Boulders,Kankar and Building Rubbish,Earth					
117		Coarse sand :	Cum	8.38	721.13	Seven Hundred Twenty One Rupees and Thirteen Paise	6,046.00
		Lohand Khad					
118		Fine sand	Cum	3.41	266.64	Two Hundred Sixty Six Rupees and Sixty Four Paise	910.00
		35km					
						Capital Works ' CSR based Civil Items (In Rs)	3,534,649.04
		Add 5.35% on CSR-Punjab-2022 items on account of change in GST rates for work contracts approved under Agenda item no.1 in the meeting of direction committee of Chief Engineers on dates 28-02-2023 and is issued vide memo No.2433-2452 /CSR dated 02-03-2023		5.35%			189,103.72
						Total Capital Works Amount after adding 5.35% (In Rs)	3,723,752.76
		Capital Works Non CSR Items (Part - A)- Civil					
119	NS	Providing and Fixing EPDM Flooring 25 mm thick (19mm-14 mm SBR+6 mm color EPDPM complete in all respect and as per direction & satisfaction of Engineer-in-charge.	Sqm	140.00	383.87	Three Hundred Eighty Three Rupees and Eighty Seven Paise	53,741.80
120	NS	Platform Merry Go round: Providing, fixing and commissioning of merri Go round (Revolving platform) size: 8 feet in diameter. Platform 3 mm thickness non skid CRC steel (cold rolled coil steel sheet) finished with PU polyurethene paint 60-100 mm microns) base member of 25mm x 5mm and 40 x 5 mm MS angle finished with powder-coated 60-70 microns. Vertical MS pipe dia 76 mm and thickness of pipe 3.5 mm finished with PU paint 60-100 microns. Connecting member cosist of 42 mm dia. 3m thickness, finished with PU paint 60-100 microns.	Each	1.00	89442.00	Eighty Nine Thousand Four Hundred Forty Two Rupees and No Paise	89,442.00
121	NS	Out door Muzi Chime: Providing and Fixing of Out door Muzi Chime having product zone 1.0m x 0.9 m x1.5 m and play Zone 2.0 m x1.9 m x2.3 m capable for kids all abilities complete in all respect to the satisfaction of Engineer -in -charge Note:- Rate includes GST,CP,Freight Charges & Instalation.	Each	1.00	50723.00	Fifty Thousand Seven Hundred Twenty Three Rupees and No Paise	50,723.00
122	NS	Musical Drum: Providing and Fixing of musical drum having product zone 1.5m x1.5 m and play Zone 2.0 m x2.5 m capable for 3 kids all abilities at a time complete in all respect to the satisfaction of Engineer -in -charge Note:- Rate includes GST,CP,Freight Charges & Instalation.	Each	1.00	89232.00	Eighty Nine Thousand Two Hundred Thirty Two Rupees and No Paise	89,232.00

S.no.	CSR Ref.	Description	Unit	Qty	Rate (Rs)	Rate (Rs. In Words)	Amount (Rs)
123	NS	Providing and fixing badminton nylon net mesh Size: 20mm & badmintn net size 6 x 0.76m & made of thick twisted and knotted polyethylene cord. Head bond stitched with 1.5" wide heavy weight canvas. Sides and bottom made of 0.75" polyseter fabric	Each	2.000	2879.06	Two Thousand Eight Hundred Seventy Nine Rupees and Six Paise	5,759.00
						Capital Works ' Non CSR based Civil Items (In Rs)	**288,897.80**
		Capital Works (Part - A) " Civil "					
		CSR based amount after adding 5.35% (In Rs)					**3,723,752.76**
		Non - CSR based amount (In Rs)					**288,897.80**
		Total : Part - A (CIVIL) CSR + Non CSR Amount : (Rs)					**4,012,650.56**
		5 Years' Operation & Maintenance Cost (PART-B)					
124	NS	1st Year.	Per month	12	12394.00	Fourteen Thousand Thirty Three Rupees and Sixteen Paise	148,728.00
125	NS	2nd Year.	Per month	12	17783.73	Twenty Thousand Thirty Eight Rupees and Sixteen Paise	213,405.00
126	NS	3rd Year.	Per month	12	19117.50	Twenty One Thousand Five Hundred Forty One Rupees and No Paise	229,410.00
127	NS	4th Year.	Per month	12	20551.32	Twenty Three Thousand One Hundred Fifty Six Rupees and Fifty Eight Paise	246,616.00
128	NS	5th Year.	Per month	12	22092.67	Twenty Four Thousand Eight Hundred Ninety Three Rupees and Thirty Three Paise	265,112.00
		5 Years' Operation & Maintenance Cost (Part - C)					**1,103,271.00**

Provisional Sum				
S.no.	**Description**	**Unit**	**Qty**	**Amt.(Rs.lakh)**
	Provisional Sum			
	Contingencies = 5 % of Capital Cost			2.01
	Total : Provisional Sum (A+B)			**2.01**

Signature Not Verified
Digitally signed by SATISH KUMAR
Date: 2024.12.03 10:14:19 IST
Location: Punjab-PB