MILITARY ENGINEER SERVICES

NAME OF WORK **REPAIR/ MAINT OF LT DISTRIBUTION SYSTEM AND REPAIR MAINT OF PIPE LINE AT AF STN BKT**

INDEX SHEET

Ser No	Contents	Pages	
		From	To
1.	Content page	01	01
2.	Forwarding letters including instructions to tenderer	02	06
3.	Item rate tender & contract IAFW-1779 (A) (Revised 1955)	07	33
4.	*General Conditions of contracts IAFW-2249 (1989 print English & Hindi version) including errata and amendments to IAFW-2249	34	87
5.	*Schedule of Minimum Wages	88	88
6.	Special Conditions	89	98
7.	Particular Specification	99	115
8.	Notice of tender (IAFW-2162) including appx 'A' to Notice of Tender	115	122
9.	Corrigendum to tender document		
10.	Relevant correspondence		
11.	Acceptance letter		
	Total Pages No		
	Drawing _NIL_ No		

* These documents are not enclosed with the tender documents and can be seen in this office on any working days.

(SIGNATURE OF CONTRACTOR)

AGE (Contracts)
For Garrison Engineer (AF)

Tele (Civ): 05212-298007

REGISTERED/AD
Garrison Engineers (AF)
Military Engineer Services
PIN-901108 C/o 56 APO
Bakshi-ka-talab, Lucknow

8769 / BKT / /E-8 Aug 2025

M/S _____

_____

REPAIR/ MAINT OF LT DISTRIBUTION SYSTEM AND REPAIR MAINT OF PIPE LINE AT AF STN BKT

Dear Sir(s),

1. Tender documents in respect of above work are uploaded on the site www.defproc.gov.in. The tender is on single stage two cover/two stage two cover/three cover e-tendering system. The contents of Cover I and Cover II are specified in NOTICE OF TENDER.

2. Bids will be received online by ACCEPTING OFFICER upto the date and time mentioned in the NOTICE INVITING TENDER (NIT). No tender/bid will be received in physical form and any tender/bid received in such manner will be treated as non bonafide tender/bid.

3. Bid will be opened on due date and time fixed for opening in the presence of tenderers/bidders or their authorised representatives, who have uploaded their quotation bid and who wish to be present at the time of opening the bids.

4. Your attention is also drawn to instruction on filling and submission of tender attached herewith. You may forward your points on tender documents and/or depute your technical representative for discussion on tender/drawings and to clarify doubts, if any, on or before **____Aug 2025**. You are requested not to write piece meal points and forward your points duly consolidated before due date viz **____Aug 2025**.

5. Unenlisted contractors are required to submit the scanned copies (in pdf file) of documents required as per eligibility criteria mentioned in instructions for filling the tender documents and Appendix 'A' to NIT alongwith EARNEST MONEY DEPOSIT (EMD) and tender fee on e-procurement portal and submit the physical documents in the office of GE (AF) BKT within time limit specified in NIT. Inadequacy/deficiency of documents shall make the bid liable for rejection resulting in disqualification for opening of financial bid.

6. (a) Contractor having not executed standing security bond and standing security deposit in any MES formation shall upload scanned copy of EARNEST MONEY DEPOSIT (EMD) mentioned in Notice of tender and shall ensure receipt of hard copy of EMD in the office of tender issuing authority before date and time fixed for this purpose. In case of failure to abide by any of these two requirements, the finance bid will not be opened.

(b) Contractor having not executed standing security bond and standing security deposit in any MES formation would be required to deposit individual security deposit on acceptance of tender which will be calculated with reference to the tendered cost

as per scales laid down by MES for calculation of “earnest money” enhanced by 25% subject to maximum of Rs 18,75,000/- (Rupees eighteen lakhs seventy-five thousand only).

7. Enlisted contractor of MES shall submit the scanned copies (pdf file) of enlistment letter, tender fee and such other documents as mentioned in Appx ‘A’ to NIT on e procurement portal and submit physical documents in the office of GE (AF) BKT within five days of bid submission end date.

8. The contractor must ensure that the tender/bid on the proper form is uploaded in time as the Accepting Officer will take no cognizance of any quotations/offer received in any other electronic or physical form like email/fax/by hand/through post from tenderer/bidder even if they are received in time.

9. In view of delays due to system failure or other communication related failures, it is suggested that the tender/bid be uploaded, if necessary, sufficiently in advance of the last due date and time fixed.

10. Keeping in view the applicability of Goods & Service Tax (GST) on all contracts, it is mandatory for the contractors to upload their GST registration number alongwith the ‘T’ bid. This will be one of the criteria for qualifying in ‘T’ bid. Contractor, who does not upload GST registration number shall be disqualified in the ‘T’ bid evaluation and his finance bid shall not be opened.

11. General Conditions of Contracts (IAFW-2249) (1989 Print) and errata and amendments thereto, Schedule of minimum fair wages and MES SSR (Part-I and Part-II) are not enclosed with these documents. These are available for perusal in the Office of GE concerned and this office.

12. ANY TENDERER, WHICH PROPOSES ALTERATIONS TO ANY OF THE CONDITION, SPECIFICATIONS LAID DOWN IN THE TENDER DOCUMENTS OR ANY NEW CONDITION, WHATSOEVER, IS LIABLE TO BE REJECTED.

Yours faithfully,

.

AGE (Contracts)
for Accepting Officer.

Encls: - Tender documents

Signature of Contractor

INSTRUCTIONS ON FILLING AND SUBMISSION OF TENDERS

1. EARNEST MONEY DEPOSIT (EMD)

Contractor(s) who are not enlisted with MES/who are enlisted but have not executed the Standing Security Bond shall submit Earnest Money deposit as detailed in Notice of Tender in one of the following forms alongwith their tender/bid:-

(a) Deposit at Call Receipt from a Scheduled Bank in favour of GE concerned.

(b) Receipted Treasury challan, the amount being credited to the Revenue Deposit of GE concerned.

It is advisable that Earnest Money is deposited in the form of deposit call receipt from an approved Scheduled Bank for easy refund. In case the tenderer/bidder wants to lodge 'EARNEST MONEY DEPOSIT' in any other form allowed by MES, a confirmation about its acceptability will be obtained from the Accepting Officer well in advance of the bid submission end date and time. Earnest Money Deposit shall be submitted in the name of GE concerned.

NOTES:- Earnest Money Deposit (EMD) in the form of cheque/Bank Guarantee etc will not be accepted. NON SUBMISSION OF EARNEST MONEY DEPOSIT (EMD) (Scanned copy alongwith Technical Bid and Hard copy before the date and time fixed for opening of BOQ) WILL RENDER THE BID DISQUALIFIED FOR OPENING OF COVER II (FINANCE BID).

NON-SUBMISSION OF EARNEST MONEY WILL RENDER AS NON- BONAFIDE AND CONSEQUENTLY LIABLE TO BE IGNORED

2. SECURITY DEPOSIT

In case the tender/bid submitted by such contractor who is not enlisted with MES is accepted, the contractor will be required to lodge with the Controller of Defence Accounts INDIVIDUAL SECURITY DEPOSIT calculated with reference to Tendered Cost as notified by the Accepting Officer subject to a maximum of Rs 18,75,000/-. The amount is required to be lodged within 30 (Thirty) days of the receipt by the contractor of notification of acceptance of tender/bid, failing which the sum shall be recovered from the 1st RAR payment or from the Final bill (See condition 22 of GCC IAFW-2249).

3. CONTRACTORS ENLISTED UNDER CHIEF ENGINEER CENTRAL COMMAND AND WHO HAVE EXECUTED SECURITY BOND AND DEPOSITED STANDING SECURITY DEPOSIT BUT OF A LOWER CLASS

In case the tender/bid is accepted, the amount of 'Additional Security Deposit' will be as notified by the Accepting Officer. This amount will be the difference between the 'Individual Security Deposit' calculated with reference to the 'TENDERED COST' and the 'STANDING SECURITY DEPOSIT' lodged. The amount is required to be lodged within 30 (thirty) days of the receipt by the contractor of notification of acceptance of tender/bid, failing which the sum shall be recovered from the 1st RAR payment or from the Final bill (Refer condition 22 of GCC IAFW-2249)

4. CONTRACTORS ENLISTED IN MES FORMATIONS OTHER THAN CENTRAL COMMAND

Contractors whose names are on the approved list of any MES formation i.e other than CE Central Command and who have deposited Standing Security and have executed Standing Security Bond may tender/bid without depositing Earnest Money with the bid and if the Accepting Officer decides to accept the tender/bid, such tenderers will be required to lodge Security Deposit as notified by the Accepting Officer. The amount is required to be lodged within 30 (thirty) days of the receipt by the contractor of notification of acceptance of tender/bid, failing which the sum shall be recovered from the 1st RAR payment or from the Final bill.

INSTRUCTIONS ON FILLING AND SUBMISSION OF TENDERS

5. GENERAL INSTRUCTIONS FOR COMPLIANCE

5.1 The bids received only in the electronic form will be considered. All bids shall be submitted on 'eprocuremes.gov.in' portal. Documents should be scanned and forwarded in 'pdf' form and 'xls' form as indicated.

5.2 Bids shall be uploaded on 'eprocuremes.gov.in' portal on or before the bid closing date mentioned in the tender. No tender/bid in any other electronic or physical form like email/fax/by hand/through post will be considered.

5.3 Bid should be DIGITALLY signed using valid DSC. All pages of tender documents, corrections/alterations shall be signed/initialed by the lowest bidder after acceptance.

5.4 Drawings, if issued in physical form, must be returned duly initialed by the tenderer/bidder in separate envelope indicating his name and address.

5.5 The tender shall be signed, dated and witnessed at all places provided for in the documents after acceptance. All corrections shall be initialed. The contractor shall initial every page of tender and shall sign all drawings forming part of the tender. Any tender/bid which proposes alterations to any of the conditions whatsoever, is liable to be rejected.

5.6 In the technical bid, a scanned copy of Power of Attorney in favour of the person uploading the bid using his/her DSC shall be uploaded. In case the digital signatory himself is the sole proprietor, scanned copy of an affidavit on stamp paper of appropriate value to this effect stating that he has authority to bind the firm in all matters pertaining to contract including the Arbitration Clause, shall be attached in 'pdf' form. In case of partnership concern or a limited company, digital signatory of the bid/tender shall ensure that he is competent to bind the contractor (through partnership deed, general power of attorney or Memorandum and Articles of Association of the Company) in all the matters pertaining to the contracts with Union of India including arbitration clause. A scanned copy of the documents confirming of such authority shall be attached with the tender/bid in 'pdf' form, if not submitted earlier. The person uploading the bid on behalf of another partner(s) or on behalf of a firm or company using his DSC shall upload with the tender/bid a scanned copy (in 'pdf' form) of Power of Attorney duly executed in his favour by such other or all of the Partner(s) or in accordance with constitution of the company in case of company, stating that he has authority to bind such other person of the firm or the Company, as the case may be in all matters pertaining to the contract including the Arbitration Clause.

5.7 Even in case of Firms or Companies which have already given Power of Attorney to an individual authorizing him to sign tender in pursuance of which bids are being uploaded by such person as a routine, fresh power of Attorney duly executed in his favour stating specifically that the said person has authority to bind such partners of the Firm or the Company as the case may be including the condition relating to Arbitration Clause, should be uploaded in 'pdf' form with the tender/bid unless such authority has already been given to him by the firm or the Company. It shall be ensured that power of attorney shall be executed in accordance with the constitution of the company as laid down in its Memorandum & Article of Association.

5.8 Hard copies of all above documents should be sent by the contractor to the Tender issuing authority well in advance to be received before the date and time fixed for the same.

5.9 Bid (Cover 1 & 2) shall be uploaded well in time.

5.10 The contractor shall employ Indian Nationals after verifying their antecedents and loyalty. Attention is also drawn to special condition No.3 referred hereinafter and also conditions 24 and 25 of IAFW-2249 (General conditions of contract).

5.11 Tenderers/bidders who uploaded their priced tenders/bids and are desirous of being present at the time of opening of the tenders/bids, may do so at the appointed time.

INSTRUCTIONS ON FILLING AND SUBMISSION OF TENDERS

5.12 The tenderer/bidder shall quote his rate on the BOQ file only. No alteration to the format will be accepted, else the bid will be disqualified and summarily rejected.

5.13 In case the tenderer/bidder has to revise / modify the rates quoted in the BOQ (excel sheet) he can do so only in the BOQ, through eprocuremes.gov.in site only before the bid closing time and date.

6. REVOCATION/REVISION OF OFFER UPWARD/OFFERING VOLUNTARY REDUCTION, AFTER CLOSING OF BID SUBMISSION DATE & TIME

In the event of lowest tenderer/bidder revoking his offer or revising his rates upward/offering voluntary reduction, after closing of bid submission date and time, his offer will be treated as revoked and the Earnest Money deposited by him shall be forfeited. In case of MES enlisted contractors the amount equal to the Earnest Money stipulated in the Notice of tender, shall be notified to the tenderer/bidder for depositing the amount through MRO. Bids of such contractors/bidders shall not be opened till the aforesaid amount equal to the earnest money is deposited by him in Govt Treasury. In addition, bids of such tenderer/bidder and his related firm shall not be opened in second call or subsequent calls. Reduction offered by the tenderer/bidder on the freak high rates referred for review shall not be treated as voluntary reduction.

7. C P M (Critical Path method)

7.1 The project planning for work covered in the scope of tender is based on CPM.

7.2 The tenderer/bidder is expected to be fully conversant with the CPM technique and employ technical staff who can use the technique in sufficient details. Sufficient books and other literature on the subject are widely available in the market which the tenderer/bidder may make use of.

7.3 The tenderer's/bidder's attention is drawn to special condition of the tender regarding preparation of the detailed network analysis and time schedule for the work and his liability for employing sufficient resources to adhere to this schedule. Any inability on the part of the tenderer/bidder in using the technique will be taken as his technical inefficiency and will affect his class of enlistment and future prospect/invitation to tenders for future works.

7.4 Department may issue amendments/errata in form of CORRIGENDUM to tender/revised BOQ to the tender documents. The tenderer/bidder is requested to read the tender documents in conjunction with all the errata/amendments/corrigendum, if any, issued by the department.

8. These instructions shall form part of the contract documents.

Signature of Contractor
Date:

AGE (Contracts)
for Accepting Officer

(IN LIEU OF IAFW-1779-A (REVISED-1955)

MILITARY ENGINEER SERVICES

(To be used in conjunction with General Conditions of contracts IAFW-2249, 1989 Print)

Tele (Civil): 05212-298007

Garrison Engineer (AF)
Military Engineer Service
PIN-901108, C/O 56 APO
Bakshi-ka-talab, Lucknow

8769/ BKT / /E-8 Aug 2025

REPAIR/ MAINT OF LT DISTRIBUTION SYSTEM AND REPAIR MAINT OF PIPE LINE AT AF STN BKT

Dear Sir (s),

1. **M/S** _____ **of**_____

is/are is/are authorized to tender for above work. The bidder is to upload the quoted bid on the

http://defproc.gov.in" site before _____ **2025** upto 1800 hrs.

2. Any correspondence concerning this tender should be addressed quoting the reference to GE (AF) Bakshi Ka Talab Lucknow and marked as "CA NO: GE (AF)/BKT/ / of 2025-26.

"THE PRESIDENT OF INDIA DOES NOT BIND HIMSELF TO ACCEPT THE LOWEST OR ANY TENDER"

(SIGNATURE OF CONTRACTOR)

AGE (Contracts)
For Garrison Engineer (AF)
Issuing Officer

SCHEDULE `A' NOTES

NAME OF WORK: - REPAIR/ MAINT OF LT DISTRIBUTION SYSTEM AND REPAIR MAINT OF PIPE LINE AT AF STN BKT

1. The scope of work covered under this contract are given in Schedule 'A' (BOQ) in a separate Excel sheet.

2. The quantities shown in Col 3 of the BOQ are approximate and are inserted as guide line only. These shall however not be varied beyond the limits laid down in condition 7 of IAFW-2249 (General Conditions of contracts).

3. Tenderers are required to insert unit rates in figures under Col 6 of the BOQ against each item of schedule `A'.

4. The rate quoted for each items under Col 5 of Sch `A' (BOQ) shall include for all necessary works required for the entire completion all as specified and shown on drawings.

5. PERIOD OF COMPLETION: The entire work under this contract shall run for a period of **270 days** from the date of handing over of site/commencement as per work order No-01.

6. The unit rate quoted by the tenderer under Col 5 of Sch `A' (BOQ) shall be deemed to include for labour and materials complete unless specifically stated otherwise in these tender documents. The unit rate shall also include for cost of drilling, cutting, forming holes etc, in concrete in bricks etc, as may be required and making good to match the adjoining surfaces.

7. Unit rate quoted by the tenderers against various items of Schedule `A' shall interalia, be deemed to include minor details of construction which are obviously and fairly intended but which may not have been specifically stated in tender documents but are essential for execution and completion of work. In case of any difference of opinion between the contractor and the GE as to whether or not any items of work constitutes "minor construction details" which is deemed to have been included in the contractor's quoted prices, the decision of the Accepting Officer shall be final, conclusive and binding.

8. Contract sum shall be arrived at after deducting amount of schedule of credit from the total quoted amount.

9. TAXES:- The rates quoted by the tenderer shall be deemed to be inclusive of all taxes (including GST as per GST Act, Labour welfare cess etc.) and other levies payable under the respective statutes and nothing extra shall be paid/ re-imbursed by the department on this account.

10. Total amount in Column 55 of BOQ is not firm.

11. TESTING OF MATERIALS

11.1 Refer condition 11 of IAFW-2249.

11.2 The cost of material, labour to be consumed in testing, transportation charges, testing charges shall be born by the contractor.

SCHEDULE `A' NOTES (CONTD…..)

12. Specification in MES Schedule part I (2009) and preamble to items given in MES Schedule part II rates (2010) under respective trade section shall be applicable. If any provision in the description of items of Schedule 'A' and particular specifications is at variance with the provisions given in specification in MES Schedule part I (2009) and preambles to MES Schedule part II rates (2010), provision in particular specifications shall take precedence there over.

13. Uploading of copy of provident fund code number in addition to other document required. The contractor not in possession of this Number shall be disqualified in "T" bid evaluation and his finance bid shall not be opened.

14. It is an express condition of this contract that if the Cat. Part No. or Make of any item has been given in Schedule 'A' (BOQ) and makes for these items are also available in Particular Specifications. In such cases, Cat. Part No. or Make as given in Schedule 'A' (BOQ) shall prevail and the same shall be provided by the Contractor. However, in case due to non-availability of none of the Cat. Part No. or make as given in Schedule 'A' (BOQ), Makes as given in Particular Specifications may be provided subject to written approval of GE after submission of non-availability certificate of all makes as mentioned in Schedule 'A' (BOQ).

15. **PERFORMANCE SECURITY**

15.1 Within 28 days of receipt of the letter of acceptance, contractor shall deliver to the Accepting Officer a Performance Security in any of the forms given below for an amount equivalent to 5% of the contract sum.

(a) A Bank Guarantee in the prescribed form.

(b) Government Securities, FDR or any other Government Instruments stipulated by the Accepting Officer.

15.2 If the performance security is provided by the contractor in the form of a Bank Guarantee, it shall be issued by Nationalized /Scheduled Indian Bank but its confirmation shall be done only from the Head Office of the Bank.

15.3 Failure of the contractor to comply with the requirements of sub clause 15 .1 shall constitute sufficient grounds for cancellation of the award of work and forfeiture of the Earnest Money. In case of MES enlisted contractor, amount equal to the earnest Money stipulated in the Notice Inviting Tender, shall be notified to the tenderer for depositing the amount through MRO. Issue of tender to such tenderers shall remain suspended till the aforesaid amount equal to the Earnest Money is deposited in Government Treasury.

15.4 All compensation or other sums of money payable by the contractor to the Government under the terms of this contract or under any other contract with Government may be deducted from, or paid by the sale of sufficient part of the Performance Security or from the interest arising there from or from any sums which may be due or become due to the contractor by the Government on any account whatsoever and in the event of his Performance security being reduced by reason of any such deduction, or sale as aforesaid, the contractor shall within ten days thereafter make good in cash or securities, endorsed as aforesaid, any sum or sums which may have been deducted from or realized by the sale of his Performance Securities or any pat thereof.

Government shall not be responsible for any loss of securities or any depreciation in the value of securities while in their charge nor for loss of interest thereon.

SCHEDULE `A' NOTES (CONTD…..)

15.5 In the event of contract being cancelled, under Condition 52,53&54 of General Conditions of Contract, the Performance Security shall be forfeited in full and shall be credited into consolidated fund of India.

15.6 The Performance Security shall be in favour of Accepting Officer and shall be in any of the forms mentioned above. Work Order No 1 shall be placed only after submission of Performance Security of adequate value by the contractor. In case a fixed deposit receipt of any Bank is furnished by the contractor to the Government as part of the Performance Guarantee and the Bank is unable to make payment against the said fixed deposit receipt, the loss caused thereby shall fall on the contractor and the contractor shall forthwith on demand furnish additional security to the Government to make good the deficit.

15.7 **PERIOD OF VALIDITY OF PERFORMANCE SECURITY**: - The period of validity of the Bank Guarantee Bond or any other instruments as mentioned above against Performance Security shall be initially valid up to the stipulated date of expiry of Defects Liability Period plus minimum 60 days beyond that. In case final bill is not paid during this period, the contractor shall get the validity of Performance Guarantee extended to cover such enlarged time required for payment of final bill.

15.8 Bank Guarantee Bond in lieu of Performance Security is due for discharge on expiry of Defect Liability Period provided always that the contractor has been paid the final bill and contractor has rendered the No demand Certificate (IAFW-451).

15.9 If any recovery is outstanding against the contractor, release of Bank Guarantee will be subject to recovery /withholding the due amount as stipulated in condition 67 (as amended) of General Conditions of Contracts (IAFW-2249).

16. **APPROVAL OF STAR RATES**:- In case of any deviation, mode of pricing shall be decided by Accepting Officer I terms of Condition 62 of IAFW-2249.

16.1 In the event of a deviation order involving fixation of Special (Star) rate, Draft Rate shall be prepared by GE (within a maximum period of 30 days) while initiating the proposal for deviation seeking approval of Accepting Officer and notified to contractor. While notifying the Draft Rate, it will be clearly stipulated that the same is merely an estimated rate and firm rate shall be fixed based on actual and receipt of supporting documents from contractor such as vouchers/literatures of product/test certificate etc (as applicable) on completion of the work involving Star Rate. Any objection to method of fixing Star Rate will be dealt as per condition 7 of IAFW-2249.

16.2 Draft Star Rate shall be made based on market enquiry through telephonic enquiry/quotations/e-mails/rate lists/internet based sources, material & labour constants available in various civil engg books and record available in respect of Star Rates approved in the past for similar items of work etc. Contractor may also assist GEs office in preparation of draft Star Rate.

16.3 The Draft Star Rate shall be purely a draft rate and shall not be used for claiming final payment during execution of work. However, GE shall allow part payment to the tune of 80% during execution to avoid any financial hardship to contractor.

16.4 After completion of the item of work involving Star Rate, contractor shall submit the vouchers/literature of product /test certificates (as applicable, decision of GE being final in case of any disagreement) for finalization of Star Rate. The Star Rate shall be technically checked by AGE (Contracts)/Director (Contracts) depending upon the financial effect & approved by competent authority within a period of one month from submission of the relevant documents by contractor as mentioned above.

SCHEDULE `A' NOTES (CONTD….)

16.5 Star Rate as approved by competent authority after technical check by AGE (Contracts)/Director (Contracts) depending upon financial effect shall be referred as "the rate decided by GE" under Para 62(G) of IAFW-2249.

17. **Defect Liability period** shall be **twelve calendar months** from the date of actual completion of work.

18. As per amendment to Payment of Wages Act, 1936 Act, issued in the Gazette Notification dated 15 Feb 2017 "All wages shall be paid in current coin or currency notes or by cheque or by crediting the wages in the bank account of the employee for this contract, the Payment shall be made into Aadhaar linked bank account of the employee by the contractor.

19. Submission of proof of crediting the wages in the Aadhaar linked bank account payment made to the employees by the contractor, shall be a pre-requisite to enable the contract executing authority to release subsequent payments to contractors. The registered contractor shall also provide the details of individual's EPF and ESI account number to claim the payment and the contract executing authority will ensure verification of the same from time to time.

20. No payments to the contractors / firms will be made unless proof of payment of wages through Aadhaar linked bank accounts is submitted by the contractors / firms. In case payments are made in current coin or currency notes, certificate will be submitted by the contractors / firms along with undertaking by the concerned workmen asking for the payment other than by cheque or by crediting in the bank account of the employee / workman.

21. **Dress/ Uniform**. The contractor shall be provided Yellow Colour Jacket with Silver colour reflector strip/ tape to the labours and shall be wore them while working otherwise penalty of Rs 100/- per day per person will be recovered from payment due to contractor.

22. **Police Verification**. Contractor shall provide confirmation of police verification for all the labours working in the premises of AF Stn BKT to Engr-in-Charge under intimation to this office before completion of work.

Signature of Contractor
Date:

AGE (Contracts)
for Accepting Officer

SCHEDULE 'B'
ISSUE OF MATERIALS ETC TO THE CONTRACTOR
(See Condition 10 of IAFW-2249)

Ser No	Description of items	Rate at which materials etc will be issued to the contractor		Place of issue of Schedule 'B'	Remarks
		Unit	Rate		
1	2	3	4	5	6

NIL

SCHEDULE 'C'
ISSUE OF TOOLS AND PLANTS (OTHER THAN TRANSPORT), WHICH WILL BE HIRED BY THE CONTRACTOR
(See Condition 15, 34 & 35 of IAFW-2249)

Ser No	Quantity and particulars	Details of MES crew supplied	Hire charges per unit per working day	Stand by charges per unit per off day	Place of issue by name	Remarks

NIL

SCHEDULE 'D'
TRANSPORT TO BE HIRED BY THE CONTRACTOR
(See Condition 15, 16 & 35 of IAFW-2249)

Ser No	Quantity	Particulars	Rate per unit per working day	Place of issue by name	Remarks

NIL

(Signature of the contractor)

AGE (Contracts)
For Garrison Engineer (AF)

TENDER

To
The President of India,

Having examined and perused the following documents: -

1. Specifications signed by AGE Contract.

2. Drawing detailed in the list of drawings.

3. Schedule 'A', 'B', 'C', & 'D' attached hereto

4. MES standard schedule of rates 2009 (Part-I specification) and SSR 2020 (Part-II rates) (here in after referred to as MES standard schedule) together with amendment No 1 to 03 for SSR 2009 Part I and amendments 1 to 122 for SSR 2020 Part II as applicable.

5. General condition of contracts IAFW-2249 (1989 Print) together with errata No 1 to 20 and amendments 1 to 49.

6. Water Conditions 31 of contracts IAFW-2249 General conditions of contracts
Water will be supplied by the MES from unmetered sources and shall be paid by the contractor at the rate of Rs 3.75 per Rs 1000/- (Rupees one thousand only) worth of work done priced at contract rates.

7. Should this tender be accepted?
I/We agree: -
*(a) That the sum of Rs _____(Rupees _____Only) forwarded as earnest money shall be retained as part of performance security deposit or be refunded by the Government on receipt of appropriate amount of Performance security deposit all as per condition 19 of IAFW-2249.
(b) To execute all the works referred to in the said documents upon the terms and conditions contained or referred to therein or at the item rates contained in the aforesaid sch 'A' and such rates may be fixed under provisions of condition 62 of IAFW-2249 and to carry out such deviations as may be ordered vide condition 7 of IAFW-2249 up to a maximum of 1**0% (ten percent)** and further agree to refer all disputes as required by condition 70 of IAFW-2249 to the sole arbitrator of a serving officer having degree in Engineering or equivalent or having passed final/direct final examination of Sub division-II of Indian Institute of Surveyors (India) recognized by Govt of India to be appointed by Chief Engineer (AF) Allahabad or in his absence Officer, Officiating as Chief Engineer (AF) Allahabad whose decision shall be final, conclusive and bindings.

*To be deleted where not applicable.

Tender (Contd...)

Signature_____in the capacity of _____

Duly authorized to sign the tender for and on behalf of M/s _____
(Name in capital letter)

Postal Address_____

_____

Telephone _____

Sign of Witness _____

Address _____

_____

Telephone _____

ACCEPTANCE

_____Alterations have been made in this document as evidence that those alterations were made before the execution of contract agreement and they have been initialed by the Contractor and AGE (Contracts) of GE (AF) Bakshi-ka-talab, Lucknow.

The said officer is hereby authorized to sign and initial on my behalf the documents forming part of this Contract Agreement. The above tender is/was accepted by me on behalf of the President of India at the item rates contained in Sch 'A' attached hereto on the____day of _____ 2025

Dated: This_____ day of _____2025

(Yogesh S Meshram)
Appointment: EE
Garrison Engineer (AF)
Bakshi-ka-talab, Lucknow
Accepting Officer
For and on behalf of President of India

GENERAL CONDITION OF CONTRACTS (IAFW-2249) 1989 PRINT

MEASUREMENT CONTRACTS IAFW-1779 & 1779A & LUMP SUM

CONTRACT BASED ON IAFW-2159

1. It is hereby agreed by me/us that the General Conditions of contract including condition 70 pertaining to settlement of disputes by Arbitration (IAFW-2249, 1989 Print) containing 33 pages Serial Page No 33 to 65 with errata No 1 to 20 containing one page Ser Page No 66 and amendment No 1 to 48 containing 20 Pages Srl Page No 67 to 86 through not enclosed with the tender documents, form part of the tender.

2. The tender submitted by me/us is subject to the aforesaid General conditions of contracts, i.e. IAFW – 2249, a copy of which has been supplied to *me/us and is in" my/our possession and which* I/We have read and under stood before submission of tender.

3. My/Our signature hereunder is deemed to be "my/our having signed the aforesaid General Conditions of Contract together with errata amendments (IAFW – 2249 – 1989 Print) forming Part of this tender.

* To be deleted whichever is not applicable.

Signature of contractor

Dated: _____

AGE (Contract)
For Accepting Officer

SCHEDULE OF MINIMUM WAGES

It is hereby agreed that the “Schedule of minimum wages” as published vide Govt of India in its latest notification (as applicable on the due date of receipt of tender which specified minimum rates of wages for various categories forms part of these tender documents and is my/our in possession. I/We have read and understood the provisions contained in this notification before submission of tender.

My/our signature here under amounts to my/our having signed the aforesaid documents forming part of the tender documents.

Signature of contractor

Dated: _____

AGE (Contract)
For Accepting Officer

SPECIAL CONDITIONS

1 GENERAL:

1.1 The following special conditions shall be read in conjunction with General Conditions of contracts IAFW-2249 (1989 Print), including errata/amendments thereto. If there are any provisions in these special conditions, which are at variance with the provisions in the above-mentioned documents; the provisions in these special conditions shall be deemed to take precedence.

1.2 General Rules, preambles, special conditions, method of measurements etc. specified in MES Standard Schedule of Rates shall be applicable unless specific provisions to the contrary are made in these tender documents.

2.0 VISIT TO SITE (S) OF WORK

The tenderers are advised to visit the site(s) of work with prior permission of GE and make themselves familiar with the local working conditions, accessibility to sites(s), availability of material and other relevant conditions which effect their pricing, workman like execution and entire completion of work. The tenderer shall be deemed to have visited the site(s) before tendering whether they actually visit or not.

3.0 CONDITIONS FOR WORKING IN RESTRICTED AREA

(a) The work lies in **RESTRICTED AREA.**

(b) The contractor shall apply in writing well in advance of the commencement of work for the issue of security passes and shall submit list of person(s) concerned and shall satisfy Garrison Engineer who shall at his discretion issue passes or may get them issued through the security officer of the unit concerned for controlling admission of the contractor, his agents, his Engineers, Overseers, Work-mistries and his workmen. The cost for procuring the passes shall be borne by the contractor. Passes thus issued shall be returned at any time or on demand by the issuing officer and in any case shall be surrendered to the issuing officer immediately on completion of work.

(c) The contractor and his people on the work site(s) shall observe all security rules promulgated from time to time by the authorities controlling the area where the work is to be carried out e.g. prohibition of smoking and lighting in certain zones, search of persons at entry and exit and keeping to specified routes etc. Any person(s) found violating the security rules laid down by the authorities in the area is/are liable to be expelled from that area without assigning any reasons whatsoever and the contractor shall have no claim on this account.

(d) The contractor may not be allowed to take his vehicles for carriage of materials up to the point of structure and the materials may have to be unloaded at the points as directed by Engineer-in-Charge. More over all vehicles are subject to search at entry point and contractor shall have no claim on this account.

(e) The site(s) of work are undulating and the contractor shall have to take permission to stack the materials at different places. The contractor shall take into consideration these factors while quoting his rates.

SPECIAL CONDITIONS (Contd…)

4.0 CONTRACTOR'S REPRESENTATIVES/AGENTS AND WORKERS

4.1 The contractor shall employ only Indian Nationals and verify their antecedents and loyalty before employing them on the work. He shall ensure that no person of doubtful antecedents and nationality is in any way associated with the work. If for reasons of technical collaboration or other consideration the employment of any foreign national is unavoidable, the tenderers shall furnish full particulars of such persons to the Accepting Officer at the time of submission of tender. As a proof that he has employed only Indian Nationals, the contractor shall render a certificate to this effect to GE within one month from the date of commencement of work.

4.2 The GE shall have full power, and without giving any reasons to order the contractor immediately to cease to employ in connection with this contract any representatives, agent, servants and workmen or employees whose continued employment in his (GE's) opinion is undesirable. The contractor shall not be allowed any compensation on this account.

4.3 Tenderer's attention is also drawn to condition 25 of IAFW-2249 in this connection.

5.0 HOURS OF WORKING

The working hours shall be as notified by the authority controlling the area, which will be normally from 0800hours to 1700 hours. If, however, contractor wants to work beyond these normal hours he can do so if permitted by the GE in writing. Similarly, no work will be allowed to be carried out on Sunday and gazetted holidays unless specifically permitted by the GE in writing.

6.0 LAND FOR STORAGE OF MATERIALS, WORKSHOP, OFFICE AND ACCOMODATION FOR LABOURERS

6.1 The contractor shall be permitted to store materials including erecting temporary sheds, temporary workshop and the site office at the area(s) of land marked on the site plan(s) or as decided by the GE if the area(s) are not marked on the site plans. The contractor shall pay license fee of **Re 1.00 (Rupee one only)** per year or part thereof in respect of each and every separate area(s) of land allotted to him.

6.2 The contractor shall be permitted to erect labour camp on Ministry of Defence land for labour coming from outside the J&K State only. Site for labour camp shall be as shown on the site plan(s) or as decided by GE and contractor shall have no claim what-so-ever on this account.

7 CONTRACTOR'S PLANT/ EQUIPMENT AT SITE

7.1 The contractor shall furnish the Engineer-in-Charge every morning a distribution return of the plant and/or equipment on the site of work, stating the following particulars:-

(i) Particulars of plant/or equipment, its make, year of manufacture, Model No. if any Registration No., if any, capacity, year of purchase etc.
(ii) Total Nos. (quantity) on site of works.
(iii) Location indicating Nos. (quantity) at each location on the site of works.
(iv) Purchase value on the date of purchase. For the purpose of this condition plant and/or equipment shall include vehicle i.e., lorries but neither the workmen's tools nor any manually operated tools/equipment.

7.2 The Engineer-in-charge shall record the particulars of plant/equipment supplied by the contractor in the works diary and send the return to the GE for record in his office

SPECIAL CONDITIONS (Contd…)

8.0 LOSS OR DAMAGE ON ACCOUNT OF ENEMY ACTION

If as a result of enemy action the contractor suffers any loss or damage, the Govt., shall reimburse to the contractor such loss or damage, to the extent and in the manner here-in-after provided:-

(i) The loss suffered by him on account of any damage or destruction of his plant and or equipment (as defined in special condition 7 above) or materials or any part or parts thereof. (The amount of loss assessed by the Accepting Officer of the contract or CWE in the case of contract accepted by GE, shall be final and binding).

(ii) The compensation paid by him under any law for the time being in force to any workman employed by him for any injury caused to him or to the Workmen's legal successors for loss of the workman's life.

(iii) Payment of compensation for loss or damage to any work or part of work carried out. The amount of compensation shall be determined in accordance with condition 48 of General Conditions of Contracts (IAFW-2249).

No reimbursement shall be made nor any compensation be payable under the above provision unless the contractor has taken air defence/precautions ordered in writing by the GE concerned or in the absence of such reasonable precautions. Neither reimbursement shall be payable nor any compensation shall be payable for any plant and/ or equipment or material not lying at site of work at the time of enemy action.

9.0 USE OF EXISTING BUILDINGS ETC.

The contractor shall not use the existing latrines, baths and other existing buildings if any for use by his work people or for storage of his materials or for any other purpose unless permitted to do so in writing by Garrison Engineer.

10. 0 WATER SUPPLY:

10.1 Refer condition 31 of General condition of Contract IAFW-2249, clause 4.13 of MES Schedule, Part-I and Srl 6 on Tender Page.

10.2 Water will be supplied by the department at point as decided by the GE. Water will be charged at the rate of Rs 3.75 per one thousand worth of work done priced at contract rates or at Rs 5.39 per 1000 Ltrs of water (in case of metered supply). The contractor shall make his own arrangement for conveyance and storage of water required for the work, labour/workmen, etc. In the event of breakdown of MES supply of water in the event of the said supply of MES water becoming intermittent, the contractor shall not be allowed any compensation, whatsoever, on this account.

10.3 The contractor, if he so desires, will be allowed to augment the departmental water supply by boring wells at his own cost at site (s) approved by the GE. On completion of the work the contractor shall remove pipes etc. installed and make good the site as directed by the Engineer-in-Charge without any extra cost to Govt. The contractor shall be given no rebate for augmentation of water supply and charges for water shall be recovered at the rate mentioned herein before.

SPECIAL CONDITIONS (Contd…)

11.0 ELECTRICITY

11.1 In case the contractor desires to buy electricity from MES, it will be supplied at point up to 3 Km away for site of work shown on site plan/or as decided by the GE.

11.2 Electric supply shall be 415/230 volts, 50 cycles, three phase AC supply upto 25 KW.

11.3 The contractor shall be charged for the electric energy consumed at Rupees 8.44 per unit (KWH) for lighting and power.

11.4 The above rate is all in cost rate. Duties and /or taxes if any, levied by State Govt. and/or any electricity under taking and the like on the electricity charged will be borne by the department.

11.5 Main switches and KWH meter to register the power supplied shall be provided and installed by MES. All other fittings, cable switch, connection etc for distribution and supply of electricity form main switch to work site shall be arranged by the contractor at his own according to Indian Electricity Rules and along with the routes approved by the GE. The GE shall have free access to inspect all installations, connections, devices for consuming the electricity and if these are not found satisfactory the GE shall have the power to get these disconnected.

11.6 Supply of electricity shall be during the hours as decided by the GE. However MES does not constituted any guarantee for the continuity of supply and no compensation shall accrue to the contractor for the supply becoming intermittent or if there is any breakdown for any reason.

12.0 DAMAGE TO EXISTING BUILDINGS, ROADS AND DRAINS ETC,

The contractor shall be responsible to reinstate and make good at his own expense, the damage if any caused by his workmen etc. to existing buildings, roads, drains, cables etc., while carrying out the work under this contract. Rectification, reinstatement, replacement, making good and touching up, etc, shall conform to the standard of workmanship and materials, originally used and the same shall be done to the entire satisfaction of Engineer-in-charge.

13.0 QUARRIES AND ROYALTY

Reference condition 14 of IAFW-2249 General Conditions of contracts. Delete this condition in toto and substitute as under: -

"Neither quarries are available nor the quarrying shall be permitted on the defence land".

14.0 MINIMUM WAGES PAYABLE TO LABOUR

14.1 Refer condition 58 of IAFW-2249. The contractor shall not pay wages lower than minimum wages for labour as fixed by the Govt. of India/State Govt. whichever is higher.

14.2 The fair wage referred to in condition 58 of IAFW-2249 will be deemed to be the same as the minimum wages as referred to above.

SPECIAL CONDITIONS (Contd…)

14.3 The contractor shall have no claim whatsoever if on account of any local regulation or otherwise he is required to pay wages in excess of minimum wages as described above during the execution of work.

14.4 The contractor shall ensure that the workers deployed by him directly or indirectly are enrolled as members of Provident Fund and shall be given Universal Account Number (UAN).

14.5 The contractor shall submit a certificate to the Engineer-in-Charge at the time of submission of RAR / Final bill to the effect that all workers employed directly or indirectly by him are registered for EPF and the due contributions have been credited into their account.

15.0 CO-OPERATION WITH OTHER AGENCIES

The contractor shall permit free access and afford reasonable facilities to other Agencies or departmental workmen engaged by Govt. to carry out other work services (whether or not in connection with the work under the scope of this contract) on the site, simultaneously. The contractor shall not be allowed any extra payment on this account.

16.0 SECURITY OF CLASSIFIED DOCUMENTS

16.1 Tenderers special attention is drawn to condition 2A & 3 of General Conditions of Contracts(IAFW-2249) for compliance. The contractor shall not communicate any classified information regarding the work either to sub contractor(s) or to any other person(s) without prior written approval of the Engineer-in-Charge. The contractor shall also not make copies of the design and drawings and other documents furnished to him in respect of works and he shall return all documents to the department on completion of the work or earlier determination and/or termination of the contract.

16.2 The contractor shall attach with final bill the receipt from Engineer-in-Charge to the effect that the contractor has returned the classified documents as per condition 3 of General Conditions of Contracts(IAFW-2249) .

17. **RECORD OF CONSUMPTION OF CEMENT**

17.1 For the purpose of keeping a record of cement procured/received and consumed in work, the contractor shall maintain a properly bound register in the form approved by the Engineer-in-Charge showing the daily receipt of cement, quantity used in works and balance at the end of each day and such other information as is required to control the consumption and procured /receipt of cement. This register shall be signed daily by the contractor's representative in token of correctness of the entries made and it shall be signed in token of check by MES representative as follows:-
(i) Daily by JE in charge of supervision of works.
(ii)Once in a week by the Engineer-in-Charge.

17.2 The register shall be kept at site of work in the safe custody of the contractor during progress of work and on demand he shall produce the same for verification of Inspecting Officer. The register shall be returned to MES on completion of work.

17.3 The aforesaid provisions will however not absolve the contractor to use required quantity of cement in work

18.0 CLEANING DOWN

The contractor shall clean all floors, joinery, glass panes etc. and remove drops of cement/lime paint etc. and touch up all painter's work and carry out other items of work as are necessary to make and leave the premises clean and tidy before handing over the buildings and/or works. The contractor shall not be allowed any extra payment on this account.

SPECIAL CONDITIONS (Contd…)

19.0 VALIDITY OF TENDER

The tender shall remain open for acceptance for a period of 90 days (Ninety days) from the date on which the same is due to be submitted.

15.0 RECORD OF MATERIALS

15.1 The quantity of materials such as paints, water proofing compounds, chemicals for anti-termite treatment etc., and the like as directed by the Engineer-in-Charge (The quantity of which cannot be checked after incorporated in the Works) shall be recorded in measurement book and signed by the contractor and the Engineer-in-Charge as a check to ensure that the required quantity has been brought to site for incorporation in the work.

15.2 Material brought to site shall be stored as directed by the Engineer-in-Charge and those already recorded in Measurement Book shall be suitably marked for identification.

15.3 The contractor shall on demand, produce to the AGE, original receipted paid vouchers in respect of the supplies. The paid vouchers so produced shall be verified, defaced and stamped by Engineer-in-Charge including contract number, name of work under his dated signature. The contractor shall ensure that the materials are brought to site in original sealed containers/packing, bearing manufacturer's making except in the case of the requirement of materials(s) being less than smallest packing.

15.4 Contractor shall produce paid vouchers from the manufacturers and/or their authorised agents for the full quantity of following materials as applicable and as a prerequisite before submitting claims for payment for advance on account of the work done and /or materials collected in accordance with conditions 64 of General Conditions of Contracts IAFW-2249 :-

(a) Oil bound distemper
(b) Cement base paint
(c) Enamel paint
(d) Acrylic emulsion paint
(e) Cement
(f) Any other materials as decided by the GE

15.5 Payment for the above materials shall neither be made in the RARs nor shall these be allowed for incorporation in the work unless the purchase vouchers invoices as stated above are produced by the contractor and are verified by the Engineer-in-Charge regarding their correctness and genuineness and are defaced by him against the contract.

21.0 **REFER SPECIAL CONDITIONS 6 & 9**

(i) The contractor shall maintain site/area of land/buildings in a clean and tidy conditions at his own expenses and shall deliver up the same on/or before the date of completion of the works, or on termination of the contract, or in the event of the said areas or land/buildings required by the GE within one month of an order to that effect, in a clean and tidy state complete in every particular and to the satisfaction of Engineer-in-Charge.

SPECIAL CONDITIONS (Contd…)

(ii) In addition to completion of all other stipulations under condition 49 of IAFW-2249, the completion certificate under condition 49 of IAFW-2249 shall be issued only after vacation of site/area of land/building allotted to the contractor. However, the contractor may be permitted by the GE in writing to retain such areas of land/building which is in the opinion of GE may be required for storage of materials required for rectification of defects (decision of the GE shall be final and binding in this regard). Soon after the rectification of defects such area of land/building shall be vacated and delivered to the Engineer-in-Charge in a neat state. Payment of final bill shall be made to the contractor only after such areas of land/building are vacated by the contractor.

22. **OFFICIAL SECRET ACT:** The contractor shall be bound by the Indian official Secret Act 1923 particularly Section 5 thereof, all as per condition 2A of IAFW-2249.

23 **BLANK**

24. **RE-IMBURSEMENT/REFUND ON VARIATION IN "TAXES DIRECTLY RELATED TO CONTRACT VALUE"** :-

(a) The rates quoted by the Contractor shall be deemed to be inclusive of all taxes (including Goods & service Tax (GST) on materials and services, Turnover Tax, Labour Welfare cess/tax etc.), duties, Royalties, Octroi & other levies payable under the respective states as applicable. No reimbursement/refund for variation in rates of taxes, GST duties, Royalties, Octroi & other levies, and/or imposition/abolition of any new/existing taxes, duties, Royalties, Octroi & other levies shall be made except as provided in sub para (b) here-in-below.

(i) The taxes which are levied by Govt at certain percentage rates of Contract Sum/Amount shall be termed as "taxes directly related to Contract value" such as GST on Works Contracts, Turnover Tax, Labour Welfare Cess/tax and like but excluding Income Tax. The tendered rates shall be deemed to be inclusive of all "taxes directly related to Contract Value" with existing percentage rates as prevailing on last bid closing date and time. Any increase in percentage rates of "taxes directly related to Contract value" with reference to prevailing rates on last due date for receipt of tenders shall be reimbursed to the Contractor and any decease in percentage rates of "taxes directly related to Contract value" with reference to prevailing rates on last due date for receipt of tenders shall be refunded by the Contractor to the Govt/deducted by the Govt from any payments due to the Contractor. Similarly, imposition of any new "taxes directly related to Contract value" after the last bid closing date shall be reimbursed to the Contractor and abolition of any "taxes directly related to Contract value" prevailing on last due date of bid closing shall be refunded by the Contractor to the Govt/deducted by the Govt from the payments due to the Contractor.

(ii) The contractor shall, within a reasonable time of his becoming aware of variation in percentage rates and/or imposition of any further "taxes directly related to Contract value", give written notice thereof to the GE stating that the same is given pursuant to this Special Condition, together with all information relating thereto which he may be in a position to supply. The Contractors shall submit the other documentary proof/ informations as the GE may require.

(iii) The Contractor shall, for the purpose of this condition keep such books of account and other documents as are necessary and shall allow inspection of the same by a duly authorized representative of Govt, and shall further, at the request of the GE furnish, verified in such a manner as the GE may require, any documents so kept and such other informations as the GE may require.

SPECIAL CONDITIONS (Contd…)

(iv) Reimbursement for increase in percentage rates/imposition of “taxes directly related to Contract value” shall be made only if the Contractor necessarily & properly pays additional “taxes directly related to Contract value” to the Govt, without getting the same adjusted against any other tax liability or without getting the same refunded from the concerned Govt Authority and submits documentary proof for the same as the GE may require.

Signature of the Contractor

AGE (Contracts)
For Garrison Engineer (AF)

Dated: _____

APPENDIX 'A' TO SPECIAL CONDITIONS

LIST OF CERTIFIED PRODUCTS TO BE INCORPORATED IN WORKS

Sl No	Material
1.	Concrete
	(a) Internal water proofing compounds(IS : 2645)
	(b) Plywood for concrete shuttering work(IS-4990)
2.	Joinery
	Wooden Flush Door Shutters, solid core type(IS-2202)
3.	Builders Hardware
	(a) Steel shutter hinges(IS:1341)
	(b) Non-ferrous Butt Hinges(IS : 205)
	(c) Ferrous Tower Bolts (IS:204)
	(d) Non-ferrous Tower Bolts (IS: 204)
	(e) Door Handles (non-ferrous)(IS:208)
	(f) Parliament Hinges(Ferrous)(IS:362)
	(g) Hydraulically Operated Door Closures(IS:3564)
	h) Continuous Piano Hinges(IS:3818)
	(j) Non-ferrous Metal sliding door Bolts (IS:2681)
	(k) Tee and Strap Hinges (IS:206)
	(l) Mild steel sliding door Bolts (IS:281)
4.	Steel And Iron Work
	(a) Steel doors, windows and ventilators(IS: 1038)
5.	Roof Covering
	Bitumen Felts for water proofing and damp proofing (IS-1322)
6.	Ceiling and Lining
	(a) Plywood for General Purposes(IS- 303) (Second revision)
	(b) Block boards(IS : 1659)
	(c)Veneered decorative plywood(IS : 1328) (Second revision)
	(d) Marine plywood (IS : 710)
	(e) Fiber Hard board(IS : 1658)
7	Flooring
	(a) White Portland cement(IS : 8042)
	(b) Cement concrete flooring(IS : 1237)
	WATER SUPPLY, PLUMBING, DRAINS AND SANITARY APPLIANCES
8	
	(a) Concrete pipes with or without reinforcement (IS: 458)
	(b) Salt glazed stoneware pipes and fittings (IS: 651)
	(c) Flushing cisterns for water closets and urinals other than plastic (IS: 774)
	(d) Cast copper alloys screw down bib taps and stop valves (IS: 781)
	(e) Galvanised mild steel tubes (IS: 1239)
	(f) Galvanised mild steel tube fittings (IS: 1239)
	(g) Sand cast irons spigot and socket soil waste and ventilating pipes and fittings (IS: 1729)
	(h) Ball valves (Horizontal plunger type) including floats for water supply purposes (IS: 1703)
	(j) Cast iron manhole covers and frames (IS: 1726)
	(k) AC presser pipes (IS: 1592)
	(l) Automatic flushing cisterns (IS: 2326)
	(m) Vitreous china sanitary appliances
	(i) Wash down water closets (IS: 2556 Part II)
	(ii) Squatting pans (IS: 2556 Part III)
	(iii) Wash basins (IS: 2556 Part IV)
	(iv) Laboratory Sinks (IS: 2556 Part V)
	(v) Urinals Bowl type (IS: 2556 Part VI Section I)
	(vi) Half Round Channels (IS: 2556 Part VII)
	(vii) Syphonic wash down water closets (IS: 2556 Part VIII)
	(viii) Foot rests (IS: 2556 Part X)

APPENDIX 'A' TO SPECIAL CONDITIONS

(n) Plastic WC seats and covers (IS: 2546)
(o) Vertically cast iron pressure pipes for water and sewage (IS: 1531)
(q) Centrifugally cast (Spun) iron pressure pipes for water gas and sewage (IS: 1536)
(r) Centrifugally cast (CI spigot and socket soil waste and ventilating pipes, fittings and accessories)(IS: 3989)
(s) Rubber sealing rings for gas main water mains and sewers (IS: 5382)
(t) Cast iron fittings for pressure pipes for water mains and sewers (IS: 1538)

9. Electrical Works
(a) Ceiling Rose (IS:371)
(b)Tumbler switches (IS:3854)
c) Socket outlet 3 pin plug and socket (IS:1293)
(d) Switch fuses (main & switch) (IS:1064 Part-I&II)
(e) Rigid steel conduit (IS:1063)
(f) Rigid Non-Metallic conduit (IS:2509)
(g) Single core cable polyethylene insulated and PVC sheathed cable(IS:1596)
(h) Starter for tube light (IS:2215)
(i) Fluorescent lamps (IS: 2418 Part I&II)
(j) Aluminium stranded conductor (IS: 398 Part I & II)
(k) Switchgears (IS:2208)
(l) HRC cartridge fuse links upto 650 volts (IS:9224 Part II)
(m) Porcelain Insulators for overhead power lines (IS:731)
(n) MCB (IS:8828)

_____
Signature OF Contractor
Dated

AGE (Contracts)
for Accepting Officer

PARTICULAR SPECIFICATIONS

1. **GENERAL**

1.1 The work under this contract shall be carried out in accordance with BOQ, Particular specifications, drawings, general specifications and other provision in the MES Standard Schedule of Rates 2009 part-I for specification and 2010 Part-II for rates and these shall be read in conjunction of each other.

1.2 The General specifications referred to in Para 1.1 here-in- before as well as referred to in IAFW-2249 (General Conditions of Contracts shall mean the specification contained in MES standard Schedule of Rates, ISS any other standard Engg Book.

1.3 Particulars specifications given here-in-after are in brief and only to particularize, amend and emphasize the specifications given in MES Schedule of Rates which are not repeated here-in-after.

1.4 Particulars specifications given here-in-after are in brief. Specifications of materials and workmanship shall be as described in MES schedule expect specifically mentioned otherwise in this document. General RULES, preambles to various sections/Rates, Special Conditions, method of measurement etc given in the MES Schedule shall also apply to this contract unless otherwise mentioned in the tender documents.

1.5 All the materials required to be incorporated in this work shall conform to relevant IS and shall be ISI marked materials which are being manufactured without IS certification and ISI embossing shall conform to IS provisions.

1.6 The copy all purchase vouchers and test certificate (duly certificate) shall be kept in the office of E-I-C and will be produced as and when asked for the same. The RAR for payment of related items will be initiated only after receipt of genuine PV &T/C by the E- I-C.

1.7 In case of any class of work for which there in no specifications in the tender documents including SSR, such work shall be carried out in accordance with Indian Standard Specification and where Indian Standard Specifications do not cover same the work should be carried out as per Standard Engineering practice subject to the approval of the GE.

1.8 No claim whatsoever will be tenable for any misunderstanding or for not having ascertained requisite information/completion of the entire work to require ins satisfactory completion of the entire work to requirement as pre contract agreement.

1.9 In below Particular Specification, which in not, applicable to this particular work shall be treated as “Blank”.

2. **DISMANTLING / DEMOLITION**.

2.1 Dismantling/demolition of the material shall be carried out as per clause given in Section 21 of SSR Part-I (2009).

2.2 Precautions prior to dismantling/demolition and during dismantling/demolition shall be carried out as per clause 21.5 and 21.6 of SSR Part –I (2009).

2.3 Removing of dismantled material shall be carried out as per 21.7 of SSR Part – I (2009)

2.4 All precautions should be taken by the contractor and making good to disturb portion without any extra cost.

2.5 The Contractor without any extra cost to Govt, shall make good any damage becoming due to dismantling/demolition. The unserviceable materials, debris and rubbish shall be disposed off out side of the premises as directed by the Engineer-in-Charge.

2.6 Dismantling/demolition of the material shal be carried out as per clause 21.1and 21.3 of SSR Part I (2009). Precautions prior to dismantling/demolition and during dismantling/demolition shall be carried out as per clause 21.5 and 21.6 of SSR Part I (2009). Removal of dismantled materials shall be carried out as per clause 21.7 of SSR Part I (2009)

PARTICULAR SPECIFICATIONS

3. **GENERAL**

3.1 Specifications of materials and workmanship shall be all as described in MES Schedule except where specifically mentioned otherwise in these documents. General rules, preambles to various sections, rates, special conditions, methods of measurements etc. given I MES schedule shall apply to this contract unless otherwise mentioned in this tender document. The location and distribution of various items in the drawings are tentative. Alterations can be made by the GE as per site requirements and there shall be n price adjustment on this account. The lump sum quoted by the contractor against Schedule 'A' shall be deemed to include expenditure on account of all extras which are not specifically shown drawings or given in particular specifications but are essential to the execution or work. In case of difference of opinion in this respect between the contractor and GE/CWE, the decision of the Accepting Officer shall be final, conclusive and binding.

3.2 On completion of entire work, the Contractor shall submit in triplicate to the Engineer-in- Charge layout plan showing actual position of poles, overhead lines, routes, cable run and all other information that will be necessary for maintenance and operation.

4. **SAMPLES AND MATERIALS** :

(a) All materials to be incorporated in this work shall be highest standard and unless otherwise specified hereinafter, shall be ISI marked and in case materials which do not have IS certification and ISI embossing shall strictly comply with the relevant ISS (or BSS for which no ISS has been issued). The makes/brands of the materials shall be as given in Appendix 'A' hereinafter.

(b) Samples of all the material shall be supplied by the contractor to the GE for approval within 30 days from the date of issue of work order.

(c) The materials and equipment to be supplied and installed under this Contract shall be indigenous make. In case tenderers offer any imported materials, they may do so out of his existing stock. No assistance/foreign exchange shall be shall be given by the department for importing any components.

(d) The contractor after obtaining written approval of samples by the GE shall obtain materials and equipment from the approved firms or through their authorized agents only. As a proof that a particular material has been obtained from the firm or through their authorized agents, the contractor shall produce such evidence to the satisfaction of GE when asked for, with regard to quality and quantity. The materials shall be brought to the site with maker's original packing with seal intact.

5. PURCHASE VOUCHERS:- Original machine numbered purchase vouchers for the main items like earthing materials to be incorporated in work shall be given by the contractor to the Engineer-in-Charge before incorporating in the work. The E-I-C will be ensuring that no payment will forward without getting PV's. These items shall be purchased from the manufacturer or their authorized dealers

6. **WORKNAMSHIP**

The specification and general rules as laid down in MES standard schedule of rates (2009) Part I and 2020 part II shall be applicable to the whole work. These will be applied in conjunction with relevant IS. The work carried out shall be of the highest standard conforming to modern engineering practice both as regards to design and execution. The work shall be executed to entire satisfaction of the GE. The contractor shall employ qualified supervisor and skilled tradesman during the entire period of execution of the contract. He shall on demand by the Engineer-in-Charge produce evidence of qualification of his superior tradesman at the time of commencement of work or at any time during the execution of the contract. All work shall be executed as per the code of practice as listed in the IS, all electric work shall be governed by IE Act/Rule with latest amendments. The code of practice for electric wiring installations as per IS-732 of 1989 with amendments will be strictly followed.

7. **GUARANTEE**

The contractor shall be responsible for provision of the guarantee for all items supplied by him as per the period of guarantee given by the manufacturers. In addition, he shall be responsible for 2 years maintenance including replacement of all items damaged/unserviceable during the defects liability period of the same specifications, standard and manufacturer as the items being replaced.

PARTICULAR SPECIFICATIONS

8. **TEST AND TRIALS**

8.1 The manufacturer's test certificate duly signed by the authorized testing authority of the manufacturer, or the test certified obtaining form a recognized government test house, shall be accepted as an evidence of the equipments and cables, accessories conforming to relevant IS. The test certificate should bear the statement that the items under test confirming to the relevant IS(number to be quoted). The contractor shall carry out insulation resistance test, the continuity test etc. The earth resistance of the earth electrode shall be measured and contractor shall submit a record of measurements do obtain. The contractor shall submit in writing record sheet of all tests carried out at site.

8.2 The contractor shall at his own expense provide all facilities, testing equipment's skilled/unskilled labour and supervisory staff and carry out the test as specified. The cost of testing is deemed to be inclusive in the unit rates quoted by the contractor against respective items.

9. **KNOWLEDGE OF REQUIREMENT**

The contractor shall be deemed to have a good working knowledge of the exact requirement of the job. In case of any doubt, clarification can be obtained from Accepting Officer before the tender is submitted. No claim, whatsoever, against Government shall be accepted or any plea by the contractor of incomplete knowledge of the work involved.

10. **ALTERNATIVES**

Normally, the equipment and material as specified in these documents will only be accepted. However, the tenderer may offer in addition to that specified in these documents alternatives equipments with their item wise costs which conform to the specifications for consideration by the Accepting Officer.

11. **AMENDMENTS TO THE PROJECT SCHEME**

The Accepting Officer reserves the right to omit or add to or modify any items considered necessary. The consequent price adjustments or deviation shall be carried

12. **PATENT RIGHTS**

The Government will have no liability in any dispute arising out of the infringement of patent right by the tendered. General Conditions of Contract also refer in this connection.

13. **INSPECTION**

The contractor is required to afford all facilities for inspection and examination of all materials used and workmanship in terms assembled or manufactured by them or their sub-contractors. The inspection of the works shall be carried out at all reasonable times and defects pointed out shall be rectified by the contractor without any extra cost.

14. **EXCAVATION AND EARTH WORK**:

The Contractor shall excavate to the authorized width and depths as indicated in SSR and as directed by the Engineer-in-Charge. Excavation made to depths more than their required levels shall be made good by the contractor at his own expenses with approved earth ramming, watering, in 150 mm layers. No extra payment shall be made for extra depth excavated and filled by the Contractor. The Contractor shall familiarize himself with the site and the cost of any shoring, strutting and dewatering required shall be deemed to be included in the quoted rate and no extra payment shall be made.

15. **CONCRETE, BRICKS, AGGREGATE, SAND ETC**:

Concrete work shall be carried out all as per respective item and as per relevant IS provisions and for other general specifications such as bricks, cement, aggregate and sand etc. refer relevant items in BOQ and clauses in SSR Part-I.

16. **CABLES**:

16.1 (a) House wiring cables shall conform to IS 692 of 1973 and laying shall generally be as described in MES Schedule Part-I.

(b) LT cables shall conform to IS 1554 Part I of 1976 and laying shall be done as described in MES Schedule Part I and all as directed at site.

(c) Cable shall be brought in standard drum length (normally of 500RM single lenths). In the normal situation straight through joints shall not be used. However, straight through joints will be permitted at exceptional circumstances when the reason for the same is on account of balance left form the cables originally brought for this particular work, such joint shall be epoxy cable joints. Satisfactory IR test for all underground cable shall be conducted after physical completion. The test shall recorded and signed by the Contractor and Engineer-in-Charge. The cable shall be laid as per Clause 19.73 to 19.95 of MES Schedule part I.

PARTICULAR SPECIFICATIONS

17. **CABLE PROTECTION**

17.1 (a) Cable shall be protected in trenches by providing sand cushioning and cable covers all as described BOQ items.

(b) On poles/walls, cables shall be protected by GI protection pipes all as specified in items of Schedule 'A'/BOQ.

18. **CABLE END BOX**

Cable end box be epoxy cold resin filled type suitable for relay voltage grade as described and jointed as per relevant IS/manufacturers instruction.

19. **CABLE GLANDS**

Cable glands shall be of brass chromium plated of appropriate size as per IE rules.

20. **TESTING EQUIPMENT**

All tests shall be carried out by the contractor using his own instruments without any extra payment. All tests shall be recorded and signed by the Contractor and Engineer-in-Charge.

21. **TESTING OF CABLES**

Testing of cables shall be carried out as detailed in clauses No 19.93.1 of SSR Part-I except that no NV test shall be made. The cable record shall be maintained all as per clause19.95 of SSR Part-I.

22. **TEST CERTIFICATE**

Manufacturer's test certificates shall be furnished by the contractor in respect of equipments as demanded by the department. If deemed necessary, initial test may be conducted at the manufacturers work site in presence of the GE's representative. All tests shall be carried out in accordance with relevant Indian Standards (or British Standards where Indian Standard do not exist).

23. **TAKING OVER OF EQUIPMENTS/INSTALLATIONS**

If the test of equipments/installations as described here in before do not show satisfactory results, the contractor shall at his own expense rectify/replace the defective installations or any part thereof as directed by the Garrison Engineer within one month. The decision of the GE shall be final and binding in this regard. The installation shall be re-tested after rectification/replacement of the defective components. The installation/equipments shall be finally taken over after the Contractor has given satisfactory test results as certified by the GE.

24. **SCOPE OF WORK**

24.1 The scope of work under this contract includes execution of work as described in BOQ and as specified here-in during the entire contract period.

24.2 The rates quoted in Schedule 'A'/BOQ shall be deemed to provide any minor accessories which are obviously and fairly intended for proper running of the plants form his own resources for which no payment shall be admissible to the contractor.

25. **LOSSES DUE TO INADEQUACY**

25.1 The contractor shall be responsible for making good damage occurred due to inadequate experience of staff deployed by him and the negligence in workmanship. The decision of the Accepting Officer shall be final and binding.

26 **STANDARD OF QUALITY AND WORKMANSHIP**

26.1 Electric Supply and installation of all electrical equipments and accessories shall strictly comply with provision contained in the latest edition of Indian Electricity Act and Rules framed there-under as applicable except where regulation and rules are modified by these specifications and relevant code of practice for Internal Electrification (IS-732) Para 19.2 of SSR 2009 Part I will be referred to for general requirement.

26.2 Items of works in this schedule shall be deemed to cover inter-alia all allied minor detail/work as to make the electrical installations in each buildings or part thereof complete and fit for switching on electric supply and taking into use the installations.

PARTICULAR SPECIFICATIONS

26.3 Refer condition 25 of General conditions of contracts (IAFW-2249). All electrical works shall be carried out by properly skilled and licensed electrician under the supervision of qualified electrician supervisors. The contractor shall on demand by Engineer-in-Charge produce such evidence of qualification of his workmen and supervisor either at commencement of work at any time thereafter during the currency of contract. Record of license of electrician and supervisor shall be endorsed in works diary by Engineer-in-Charge in token of check made by him. The entire work shall be high class with best workmanship and to the entire satisfaction of Engineer-in-Charge.

26.4 All equipments and materials incorporated in this work shall be of standard make and shall strictly comply with current appropriate Indian Standard Specifications.

26.5 Samples of all electrical fittings shall be first got approved by the GE in writing before incorporation in the work and shall confirm to the relevant IS or make and catalogue number as specified. Utility light fittings shall be of the best quality available and confirm to the sample kept in GE's office duly approved by him.

26.6 The terminal points for light and power switch socket combination, switches fan regulators, fittings outlet etc, shall terminate in recessed mild steel boxes fixed flush to the walls and covered with laminated sheet 3 mm uniform thickness to match the colour of the walls as directed by GE.

26.7 Cutting and forming chases in crick work/concrete where directed shall be done as per direction of Engineer-in-Charge, Gaps/voids of all cut/formed chases including recessed formed for terminal boxes for housing power plugs, switches sockets shall be carried out with cement concrete (1:3:6) type C-1 or in cement mortar (1:6) mix after fixation of pipes/boxes etc without any extra cost to the Govt.

26.8 Clause 19.101 to 19.112 and 19.114 of SSR Part I will be referred to for workmanship. Special attention is drawn to clause 19.111 of SSR Part I for method of passing conductor through walls and floors.

26.9 All material incorporated in the work shall be ISI marked. In case ISI marked material /equipment is not available in the market due to not being manufactured, the same shall be conforming to BIS specifications.

27. MATERIALS: - The materials shall be as specified in SSR (Part-I) given below: -

Sl No	Materials	Reference t Para of SSR (Part I)
(a)	Cables cords and earthing leads	19.24
(b)	Cables for internal Wiring for light power & submain	19.25
(c)	Wooden battens Blocks and boards	19.28
(d)	Conduit and conduit Fittings	19.29
(e)	Plug/gut ties	19.30
(f)	Screw and Fastenings, link clips	19.31
(g)	Ceiling rose	19.32
(h)	Shades	19.33
(j)	Bulkhead fittings	19.34
(k)	Socket outlets	19.40
(l)	Lamp holders	19.41
(m)	Main switch	19.45
(n)	Switch boards Distribution fuse Board	19.44
(o)	Miniature circuit breaker	19.46

PARTICULAR SPECIFICATIONS

28. **INSPECTION**

The contractor is required to afford all facilities for inspection and examination of all materials used and workmanship in items assembled for manufactured by them or their sub contractors. The inspection will be made of the works at all responsible items and the contractor shall rectify defects pointed out without any extra cost to the Government.

29. **POSITION OF SWITCH SOCKET COMBINATION**

All switch socket combination will be placed 1.20 meters above finished floor level.

30. **FLEXIBLE CORDS**.

Flexible cords 23/0.0076 shall conform to IS No. 434.

31. **LAYOUT**

The exact position of various light fittings/fans/socket outlet and others shall be approved by the GE in writing before the contractor shall take the work in hand without any price adjustment.

32. **TYPE OF ELECTRIC SUPPLY**:

Type of electric supply will be 4 wire, 50 cycles, 415/230V

33. **EARTHING**

33.1 The earthing shall be in accordance with section 19 clauses 19.137 of MES Schedule and as specified in BOQ and the work shall be executed in the presence of MES representative. Excavation for earth pit may be in any type of soil, excavation shall be passed by Engineer-in-Charge before filling in, Surplus soil if any shall be removed to a distance not exceeding 50 meters and the site left clean and tidy. Concrete in earth pit shall be 1:3:6 type C1 using 20 mm graded stone aggregate.

33.2. The maximum continuity resistance from any point of the installation including the earth continuity conductor and earth lead to the earth pit shall not exceed 0.12 Ohm. All metal works associated with wiring system other than current carrying parts including the cable sheathed and armoured conduit, ducts and box shall be connected to the earth continuity conductor as required under Indian Electricity Rules 1965 and IEE wiring regulations. The earth terminal of socket outlet etc, shall be connected to the earth continuity conductor. The size of all the earth continuity shall be as specified in respective Schedule A` items. Testing of earthing shall be carried out as per clause No 19.146 of MES Schedule Part I.

34. **TESTS**.

The following tests shall be carried out to the entire satisfaction of the Engineer-in-Charge before the work is finally handed over by the contractor and completion certificate is issued.

(a) Polarity Test : Test result shall not be lower than the minimum specified in Indian Electricity rule.

(b) Insulation resistant test.

(c) Continuity test sectional and over all

(d) Earth resistance test : This is not to exceed 1 Ohms.

34.1. Clause 19.146 of SSR (Part I) is applicable

35. **RECORD DRAWINGS**

On completion of wiring of the building the contractor shall submit three copies of line plan of the building (Scale :100) indicating position of controls and fittings and actual runs of all mains and sub circuit and such other information which the Engineer-in- Charge may require. Phase/neutral wires shall e shown in red and black colour respectively.

36. **MAKES OF MATERIALS**

Makes of materials shall be one of the makes as given as Appx ‘A’ to PS and approved by GE. All the materials shall be approved by GE in writing.

37. **COLOUR CODE IN CONDUIT SYSTEM OF WIRING**

Red/Yellow/blue wires for phases, black wire for neutral and green wire for earth shall be in wiring in conduit as specified in clause 19.25 on serial page 438 of SSR part-I- 2009.

PARTICULAR SPECIFICATIONS

38. CEMENT

39 GENERAL

40 Type of cement for the subject work shall be Ordinary Portland cement of Grade 43 (Forty three) in accordance with IS-8112 of 1989 or Portland Pozzolana cement (IS:1489 – 1991) Mixing of OPC and PCC shall not be allowed in the work and also use of OPC and PPC shall not be permitted in the same building except for plaster and mortar. While using the PCC, following requirements shall be met with by the contractor:-

41 (a) PCC shall meet the strength criteria of 43 Grade OPC as laid down in IS 8112 – 1989.

(b) The minimum period before striking form work given n clause 11.3.1 of IS : 456 – 2000anf period of curing shall be suitably increased at site by the GE The contractor shall not claim anything extra on this account.

(c) The contractor shall be submit the following certificate from the manufacturer of the cement for every batch of cement.

(i) The quality of fly as is strictly as per IS 1489 (Part-I) -1991.

(ii) Fly ash is inter- ground with clinker and not mixed with clinker.

(iii) Dry flash is transported in closed containers ans stored in silors. Only pneumatic pumping has been used.

(iv) The fly ash is received from thermal power plant using high temperature combustion above 1000° C has only been used.

42 PROCUREMENT AND TESTING OF CEMENT:-

4.2.1 All cement required for completion of this contract shall be procured by the contractor, under his own arrangement direct from the manufacturers.

(i) ACC
(ii) Birla Corporation Ltd (Cement division)
(iii) Jay Pee Rewa Cement
(iv) Manglam Cement
(v) Ambuja Cement Ltd
(vi) Century Cements
(vii) Grasim Industries Ltd
(viii) The India Cement
(ix) Ultra Tech Cement
(x) JK Cement
(xi) Binani Cement
(xii) Orient Cement
(xiii) Madras Cement Ltd
(xiv) Dalmia Cement (Bharat) Ltd
(xv) Andhra Cement
(xvi) Shree Cement t
(xvi) J K Lakshmi Cement
(xvii) Lafarge Cement
(xviii) Saurashtra Cement
(xix) Dhuruv Cement

Particulars of the manufacturer of cement along with date of manufacture shall be furnished by the Contractor to GE for every consignment of cement separately.

42.2 In case estimated requirement of cement is less than 1200 bags, contractor can procure cement form the authorized distributors/dealers of the approved firms. However, contractor shall have to submit test certified for the batch issued by the firm. Independent testing of cement shall have to submit test certificate for the batch issued by the firm. Independent testing of cement shall be a the option /distretion of the Garrison Engineer, if any factory test certificates are produced by the contractor. In case the contractor does not produce the factory test certificate, the testing of cement by Garrison Engineer shall be mandatory. However the testing shall be restricted to IS-4031 (method of physical test for hydraulic cement) only. The GE shall ensure that cement accepted should not be more than two months old. The week/date of manufacturing of cement is always printed at the bottom end of the cement bag. The marking of manufacturing date o cement bag is of peculiar nature and all concerned officials are required to clearly understand the method of marking.

42.3 The contractor shall furnish the particulars of the manufacturer of cement alongwith the date of manufacturer to the Garrison Engineer for every lot of cement separately. The cement so brought shall be fresh and in no case older than 60 days from date of manufacture. The GE shall verify the documents in support of the purchase of cement. Before placing order for supply of cement by the contractor he shall obtain written approval from GE regarding name of manufacture, quantity of cement etc. Cement shall be procured for minimum requirement of one month and not exceeding the requirements of the same for more than two months at a time.The cement shall be consumed in the work within three months after receipt. Cement shall conform to the requirement of IS specification and each bag of cement shall bear relevant ISI mark. The weight of each consignment shall be verified by the Engineer-in-Charge and recorded.The content of cement shall be checked at random to verify the actual weight of cement per bag. However, the content per bag shall be checked at random to verify the actual weight of cement per bag. However, the content per bag shall be 50 Kg only subject to tolerance given in clause 9.2.1.1 and Annexure ‘B’ of IS- 8112 of 1989.

PARTICULAR SPECIFICATIONS

42.4 TESTING :

42.4.1 The manufacturer is required to carry out inspections and testing of cement in accordance with the relevant BIS provisions. The contractor shall submit the Manufacturer's Test Certificate in original along with the test sheet giving the result of each physical test as applicable and chemical composition of the cement or authenticated copy thereof duly signed by the manufacturer, with each consignment. The Engineer-in-Charge shall record these details in the cement Acceptance/Rejection Register as appended here in below after due verification.

42.4.2 The GE may organise independent testing as per IS-3535 (method of sampling hydraulic cement) and IS-4031-1995 (Method of Physical test for hydraulic cement) and IS-4032-1985 (Methods of chemical analysis of hydraulic cements) of random sample of cement drawn from each lot of the consignment from the National Test House, SEMT Wing, CME, Regional Research Laboratories, Govt Engineering collage ,IS approved laboratories and Zonal lab etc.

42.4.3 The contractor shall make available required quantity of cement and other facilities for testing of cement by GE as specified here-in-before and shall bear the cost of cement and testing thereto irrespective of whether sample passes or fails. GE shall make payment to the testing house lab and direct the contractor to deposit the amount in Govt. treasury in favour of GE concerned and submit the treasury challan to the GE within 10 days of the letter issued by the GE for payment of cost of testing of cement. If contractor fails to do so, the testing charges shall be recovered from the dues of the contractor.

40.2.4.4 The required quantity of samples of the cement shall be taken in two polythene bags and sealed by the Engineer-in-Charge in the presence of representative of the contractor. The seal shall be authenticated both by the Engineer-in-Charge and representative of the contractor. Out of two samples, one sample shall be sent for testing and other retained by GE in his office. Record of these samples shall be kept by Engineer-in-Charge in the register and copy of the same shall be sent to GE/CWE/CE by him for record.

42.4.5 Cement brought by the contractor shall be allowed to be incorporated in the work after satisfactory test results of sample sent for testing. GE shall inform the contractor, about the test results and permission to incorporate in the work, in writing. GE shall ensure that word "pass" is embossed on both side of the cement bags of lot which has been found as per specification as per test result. The cost of embossing as indicated herein above shall be borne by contractor.

42.4.6 In case the sample got tested by the GE from the institutions/laboratories, mentioned here in before , fails, the concerned lot of cement shall stand rejected. The GE shall emboss a mark 'X' on both sides of each bag of the rejected lot. The GE will inform the contractor in writing about the test result and direct him to remove the rejected cement from the site of works within two days of the order by the GE. Contractor shall have no claim whatsoever on account of rejection and removal of cement.

42.4.7 It shall be the responsibility of the contractor to arrange cement well in advance, to facilitate its testing before use in the work. The contractor shall submit the programme of procurement of cement to the GE before the date of commencement of the work indicating date of procurement and quantity.

43 STORING :

43.1 The contractor shall store the cement at site in a covered leak proof godown with locking arrangement, over a dunnage at least 20 cm high, in such a manner as to prevent deterioration due to moisture or intrusion of foreign matter. The stack of cement stores shall be at least 60cm away from the walls. The cement so stored shall be inspected by the (JE Civil) and the rep of the contractor once in a day to ensure that cement is not affected by moisture or by any other means. Engineer-in-Charge shall make such inspections once in a month. In addition to the inspection the Engineer-in-Charge shall attach a certificate with every RAR that cement is stored as per the above provisions and is safe. The tested and untested cement shall be segregated and stored separately with distinct identification.

43.2 The cement godown shall be provided with two locks on each door. One lock by the GE and other lock by the contractor shall be provided. The keys of the lock provided by the GE at each door shall remain with Engineer-in-Charge or his representative and that of the other lock with the contractor's authorised agent at site of work so that cement is removed from the godown only according to the daily requirement with the knowledge of both the parties.

43.3 Procurement of cement shall be made in phased manner to avoid storage for long duration.

44 DOCUMENTATION

44.1 The contractor shall submit original vouchers, test certificates and test sheets from the manufacturer/producers for the total quantity of cement supplied under each consignment to be incorporated in the work. The GE alongwith the relevant documents before sample is taken for the testing shall inspect all consignments received at the work site. The original vouchers and test certificates(original/authenticated) shall be defaced by the Engineer-in-Charge and kept on record in the office of the GE duly authenticated and with cross reference to the control number recorded in the cement acceptance/rejection register. The cement acceptance/rejection register shall be signed by (JE Civil), Engineer-in-Charge, GE and the Contractor. The Accepting Officer may order a Board of Officers for verification of connected documents produced by the contractor. The entire quantity of cement shall also be recorded in the measurement book(not to be abstracted) for record purpose before incorporation in the work and shall be signed by the Engineer-in-Charge and the contractor.

44.2 Record of cement brought by the contractor shall be maintained on the following format :-

PARTICULAR SPECIFICATIONS

CEMENT SUPPLY & ACCEPTANCE REGISTER (Appx A)

1. CA No & Name of work :
2. Control No :
3. Name of manufacturer/Brand Name/Gde of cement (A) Manufacture _____(b) Brand_____(c) Grade
4. Qty of cement & Lot No/Week No (in Bags): (Qty_____(b) Lot No /week No_____
5. Manufacturer's test certificates No_____
6. Random Test Details (a) Physical test report from vide their letter No_____
(Name of approved Lab/Engg College)
(b) Chemical test report from _____vide their letter No
(Name of approved Lab/Engg College)
7. Details of Physical & Chemical properties :

	Physical Requirements (As per IS 4031)										Chemical Requirements (As per IS - 4032)							
	Specific Surface M^2 /Kg	Soundness by Le Chateliar	Soundness by Auto Clave	Initial Setting Time (Minutes)	final setting time (minutes)	Compressive Strengths			Temp during testing °C	Standard Consistency (%)	Lime Saturation Factor (Ratio)	Alumina iron Ratio (Ratio)	Insoluble Residue (%)	Magnesia (%)	Sulphuric Anhydride (%) Ignition	Loss of ignition (%)	Alkalies (%)	Chlorides (%)
						03 days (MPa)	07 days (Mpa)	28 days (Mpa)										
As per relevant IS																		
As per manufacturer's test certificate																		
As per random test certificate																		

Remarks with signature Accepted/Rejected

Contractor Junior Engineer Engineer-in-Charge Garrison Engineer

Remarks of BOO/Inspecting Officer/CWE

*To be allotted serially by GE consignment wise

PARTICULAR SPECIFICATIONS

45 REQUIREMENT OF CEMENT :

45.1 Requirement of cement to be incorporated in the works under this contract (except for design mixes) shall be calculated on the basis of the cement constants as circulated by Engineer-in-Chief's Branch, Army HQ, New Delhi which can be seen in CE's office, CWE's office and GE's office. The quantity of cement required shall be checked jointly by the Engineer-in-Charge and the rep of the contractor at different stages of work and recorded in the cement register which shall be checked at the time of payment of RAR.

45.2 Lime shall be conforming to approved samples kept in GE's GE office.

45.3 Fine aggregate (sand) for concrete work shall conform to materials specifications and grading with the limits of grading Zone I to II as specified in Clause 4.4.1 to 4.4.6 and 4.4.7(2) of MES Schedule Part I and shall conform to approve sample kept in the office of GE. Mixing of sand for obtaining specified grading rom two different sources shall not be permitted.

45.4 (a) Coarse aggregate (stone aggregate) for all cement concrete work such as PCC/RCC shall be of approved quality all as specified in clause 4.4.1 to 4.4.7(1) of MES Schedule part I.

(b) Coarse aggregate (stone aggregate) 20mm and below shall be machine crushed and above 20 mm may be hand broken.

(c) Grading of coarse aggregate (stone aggregate) unless specified otherwise otherwise in the specifications hereinafter in various locations/work i.e PCC/RCC shall be as specified in MES Schedule Pari I.

(d) Coarse aggregate for lime concrete shall however be brick aggregate as specified in clause 4.5 of MES Schedule part I.

45 Before commencement of excavation, the contractor shall mark the layout of the proposed pipe routes on ground alongwith the alignment as directed by the Engineer-in-Charge.

46 The Engineer-in-Charge and the contractor shall jointly take ground levels alongwith the pipe alignment marked on ground at intervals as decided by GE. From these levels the Engineer-in-Charge shall draw longitudinal section. These will also show proposed invert levels of pipes, levels books shall be signed by the contractor and the Engineer-in-Charge and earth work computed with the application of primordial/trapezoidal formula for the purpose of payment.

47 Authorized width of trenches shall be as given in special condition 3.2 of MES Schedule Part II. Authorized width or those actually excavated whichever is less shall only be paid. The Authorized width and depth of trench for GI pipes and cable shall be as per Clause No 18.50.1 of MES Schedule Part-I.

48 Refilling of excavated trenches after laying and testing of pipe lines shall be done with the earth obtained from excavation which shall be free from grass, stone etc. The filling specified above shall be brought to level and 75mm above ground level in a crown shape.

49 The Contractor shall excavate to the specified depths only as indicated on the drawings and as directed y the Engineer-in-Charge. Excavation made to depths more than their required levels shall be made good by the contractor at his own expenses with approved earth ramming, watering, in 150 mm layers. No extra payment shall be made for extra depth excavated and filled by the Contractor. The Contractor shall familiarize himself with the site and the cost of any shoring, strutting and dewatering required shall be deemed included in the lump sum and no extra payment shall be made.

50 RETURN, FILLING IN TRENCHES AND DISPOSAL

(a) After excavation is carried out to required depth, the bottom of trenches shall be evenly dressed and well rammed before pipes area laid down. Unless otherwise specified, all trenches shall be filled back with spoil obtained from excavation, watered, rammed and consolidated to the satisfaction of Engineer-in-Charge and shall be laid in regular layer not exceeding 150mm thick. The returning filling specified above shall be done upto height of 80mm above ground level. Settlement of earth in trenches which may take place during the execution of work or during the maintenance period shall be made up by the contractor at his own cost.

b) Joints of pipe shall be kept open and no filling over the joints shall be done till pipe is tested. In case these are filled up or get filled up during the course of time, these shall again be opened before commencing the testing of the pipe line and afterward the trenches shall be properly filled.

(c) Pipes shall not be laid directly over rock (where rock excavation is done) but 150mm cushion of approved earth, well rammed shall be provided below the pipes.

(d) All surplus spoil obtained from excavation shall be removed to a distance specified in BOQ and spread and leveled at places as directed by Engineer-in-Charge without any extra cost of Govt.

PARTICULAR SPECIFICATIONS

51.0 APPENDIX TO PARTICULAR SPECIFICATIONS: -

51.1 The make of all items as per Appx 'B' to PS attached here in after and any difference in between BOQ and Appx 'A', the BOQ shall take precedence in overall.

51.2 To ascertain the quality of any material to be incorporated in the CA, The GE/AGE may order for independent testing from any approved Lab and testing charges shall be born by the Contractor.

51.3 All items should be ISI Marked as available in the market, otherwise conforming to IS Specifications.

52 ***EARTHING***

52.1 Refer clause 19.137 to 19.146 on page 481 to 484 MES Schedule2009 (Part-I) and plate No 3 at srl page No 497 of SSR (Part-I).

*52.*2 The contractor shall execute installation of earth plate in the presence of Engr-in-Charge. Charcoal dust and salt and returning filling shall be done in layers not exceeding 20cm depth, properly watered and rammed. Surplus spoil shall be carried away and the site left clean and tidy.

53.0 **EXTERNAL WATER SUPPLY**

53.1 (a) Work shall be carried out by Skilled plumbers / pipe fitters.
(b) Layout of pipe shall be generally as directed by engineer in charge.
(c)The holes through walls, floors etc, around the pipes shall be made good with cement and sand mortar (1:4) for full thickness & finished as per surrounding surface.

53.2 The location and distribution of various items are tentative. Alteration can be made by GE as per the site requirements and there shall be no price adjustment on this account. The rates quoted by the contractor against each item of Schedule 'A' shall be deemed to include expenditure on account of all extras which are not specially shown on drawings or given in particulars specifications but are essential for the execution of work. In case of difference of opinion in this respect between the contractor and the GE, the decision of the accepting Officer shall be final, conclusive and binding.

54.0 **DI PIPES**: - All DI pipes shall conform to IS-8329-2000 and shall be grade K-7. All fittings shall conform to IS-9523-2000 and Hydraulic testing will be carried out as given in IS-12288. Manufacturers Test Certificate shall be produced. DI pies shall be all as specified in clause 18.94 to 18.94.2 of SSR Part I

55.0 FLANGED JOINTS: - Joint material used between flanges of pipes/fittings shall be of thickness 3.00mm and samples shall be got approved from the GE before procurement of bulk. Flanges shall conform to IS-6392 "Specification for steel pipe flanges" shall be welded or screwed (at the option of contractor without any price adjustment on the [pipe/fittings as per IS requirement. The numbers and positions of holes on the flanges shall be as per IS requirement. Nuts, bolts and washers shall be of MS as per IS.

56.0 **GI PIPE AND FITTINGS**: -
(a) GI pipes and fitting shall be medium grade, conforming to IS 1239 (Part I) and IS -1239 (Part II) respectively with tolerance as specified in clause 18.42 of SSR Part I.

(b) GI pipes and fitting shall be laid at a depth not less than 225mm and not more than 450mm below ground level all as specified in Clause 18.50 of SSR Part I. (c) Jointing of GI pipes and fittings shall be done as specified in Clause 18.50 of SSR Part I.

PARTICULAR SPECIFICATIONS

57.0 JOINTING OF DI / GI PIPES AND FITTINGS: -

(a) No flanges or spigot and socket joint shall be buried in the masonry of the valve chambers.

(b) Cast iron fittings and specials such as bends, tapers, tees, connecting pieces etc. shall be carefully and accurately aligned and jointed to pipes as directed under relevant clauses of IS 3114 of 1985 as amended. While laying pipes in trenches care shall be taken that no earth etc gets inside pipe. The work when completed shall be tested as per IS requirements.

(c) While laying pipes in trenches care shall be taken that no earth etc gets inside pipe. The work when completed shall be tested as per IS requirements.

(d) (i) In run leads joints for pipes, fitting and specials, molten lead and spun yarn will be used. The spun yarn shall be handled with care in order to pavement contamination and shall be dry when put into place in the joints. The yarn shall be free of oil, fat or greasy substances.

(ii) When a single strand of yarn is used, it shall have an overlap at the top not more than 5 cms. When more than single strand is required for a joint each strand shall be cut to sufficient length so that the ends of pipe will meet without causing overlap. The end of strand shall meet on opposite side of the pipes and not on the top of the bottom. Successive stand of yarning material shall be driven home separately.

(iii) The lead for caulking purposes shall conform to IS 782-1978. The quantity of lead and spun yarn required for difference sizes of pipes shall be as specified in clause 18.48.24 of MES Schedule Part I

(g) Laying and Jointing of DI pipes shall be carried out all as specified in clause 18.2.4 to 18.2.4.6 and 18.95 to 18.95.5.4 of SSR Part I

58.0 DETECTION OF CRACKS OF PIPES/TUBES: - The pipes/tubes and fittings shall be inspected for defects and rung with a light hammer preferably while suspended to detect cracks. If doubt persists further confirmation shall be obtained by pouring little paraffin on the pipe at the suspected spot.

59.0 Sluice Valves/Reflux Or Non Return Valves: -

59.1 Sluice valve shall comply with the requirements of IS 14846-2000 and shall be class PN-1.6. The make of sluice valve shall be as mentioned in appendix ‘A’.

59.2 Non return valves (Reflux Valves) :- These shall be flanged, swing check type valves, single door pattern conforming to IS- 5312 (Pt I). The valve shall be with or without by- pass arrangement and of the makes as mentioned in Appendix ‘A’

59.3The valves shall be fixed as specified in clause 18.57 of MES Schedule Part I.

60.0 TESTING OF PIPE LINES: -

60.1 Testing of pipes and pipe lines: - All pipes and fittings shall be inspected carefully before being laid. Broken or defective pipes shall not be used or removed from the site of works. Pipes shall be rung with light hammer preferably while suspended to be defect cracks. If doubt persists, confirmation may be obtained by powering a little paraffin on the inside of the pipe at the suspected spot, if crack is present the paraffin seeps through and shows on the outer surface.

PARTICULAR SPECIFICATIONS

60.2 Testing distribution pipeline: -

(a) Pressure and leakage test: - After a new pipe line has been laid, jointed, the test shall be carried out as directed at in double the working pressure for period of two hours.

(i)A record of the above tests shall be maintained and separate register duly signed by the contractor and Engineer-in-Charge.

(ii)All facilities and equipments for testing will be arranged by the contractor at the own costt.

(iii)Any cracked or defective pipes, fittings valves and joints discovered as a result of the above test shall be removed and replaced by the contractor at his own cost and the test shall be repeated till the results are obtained to the satisfaction of the Engineer-in-Charge.

(iv)During the leakage test should any pipe of joint fitting disclose leakage greater than that specified the defective item should be replaced un-till the leakage is removed to the satisfaction on Engineer-in-Charge as specified.

60.3 Testing of pressure pipe rising the pressure pipe rising main only will be subjected to testing in accordance with Para 18-48.7 of SSR Part I.

61.0 VALVE CHAMBER

61.1 The unit rate for valve chamber in Sch 'A' and as shown on drawings shall include for:-

(a) Excavation and earth work in any type of soil and surplus spoil removed to distance n.exc 50 meters.

(b) PCC in foundation shall be (1:4:8) type D-2 using 40mm graded stone aggregate and top exposed surface finished fair without using extra cement.

(a) Brick work in cement mortar (1:4)

(d) Finishing: - 15mm thick cement plaster in cement mortar (1:4) on brick wall internally and externally to the extent shown on drgs. Cement plaster shall be finished smooth without using extra cement.

(e) MS cover 3mm thick with frame 40mm x40mmx 6mm fixing lugs and locking arrangements with two coats of grey paints over a coat of red oxide primer.

62.0 STOP COCKS: - Brass stop cocks shall conform to IS 781 high pressure quality, screw down pattern. The crutch handles, spindles glands etc, shall be cast brass (extruded, rolled and forged) in lieu of brass as specified in IS 781 without any price adjustment.

63.0 APPENDIX OF PARTICULAR SPECIFICATION: -

63.1 The make of all items as per Appx 'A' to PS attached here in after and any difference in between Sch 'A'/BOQ and Appx 'A' , the Sch 'A' take precedence in overall.

63.2 To ascertain the quality of any material to be incorporated in the CA. The GE/AGE may order for independent testing from any approved Lab and testing charges shall be borne by the Contractor.

63.3 All item should be ISI Marked as available in the market, otherwise conforming to IS Specification.

(Signature of Contractor)

AGE (Contracts)
For Accepting Officer

Appx 'A'

LIST OF BRAND/APPROVED MAKE

Sl No	Name of item	List of makes/brands/manufacturers
1	2	3
1.	XLPE Cables 1100V Grade	(a) Ekta Cables (b) Havells (c) Polycab (d) NICCO (e) Plaza (f) Rallison (g) Finolex (h) Krishna/MPCAB (j) INCAB
2.	PVC Cables 1100 Grade	(a) National Cables (b) Finolex (c) CCI (Cable Corporation of India Ltd.) (d) Havells (e) Ekta Cables (f) Plaza (g) Rallison
3.	Cold Shrinkables/cables end termination and straight through joints 33 KC & 11 KV Grade	(a) Birla - 3 M Ltd. (b) M-Seal
4.	1100 Volt Grade Cables end termination and straight through joints (Cash Resin Type)	(a) M-Seal (b) Birla 3 M Ltd (c) Denson (d) Raychem
5.	LT Switch Gear Panels (Lt Panels)	(a) Essar Universal Pvt. Ltd Kanpur (b) Asian Switch gear Kanpur (c) Control And Switch Gear Co. Ltd. (d) Havells
6.	Air Insulated Trunk Busbas	(a) L&T (Larsen & Turbo Ltd) (b) Essar Universal (Pvt) Ltd Kanpur (c) Control & Switchgears Co Ltd.
7.	Moulded case circuit breakers (ACBS)	(a) L&T (Larsen & Tourbo) (b) Schnider (c) Havells (d) Siemens (e) ABB (f) Legrand
8.	Fuse Switch & Switch Units	(a) L&T (Larsen & Turbo) (b) Havells (c) Crompton Greaves
9.	On load change over switches	(a) L&T (Larsen & Turbo) (b) Havells (c) Standard
10	Distribution Boards (SPN/TPN/RCCBS)	(a) L&T (Larsen & Turbo) (b) Havells (c) Standard (d) Legrand

Appx 'A'

Ser No	Name of Item	List of makes/Brands/Manufacture
11.	Miniature circuit brekers (MCBS) & isolator switches	(a) Havells (b) L&T (c) Lexic of Legrand (d) Siemens (e) Merlin Gerin (f) Hegar of L&t
12.	Plug and socket DBs (SPN/TPN/FP)	(a) Havells (b) Standard (c) L&T
13.	Insulator HT/LT	(a) Modern Insulators (b) WS Insulators (c) Mysore Porcelain (d) Jaipuria Brothers (e) Jayshree Insulators
14.	ACSR Conductors	(a) ALIND (b) Jaipuria Brothers (c) Bharat conductors
15.	Panel meters (ammetes, voltmeters, PP meters, frequency meter and kvar meters)	(a) Electro Mechanical Type (i) Rishabh Industries Pvt. Ltd (Marketed by L&T) (ii) AE (iii) DIP (iv) MECO (v) IMP (vi) Simco (b) Digital Type (i) Meco (ii) Enerco
16.	Wiring Cables	(a) National (b) Finolex (c) Nicco Corporation Ltd. (d) Plaza (e) Universal Cables (f) Grandlay
17.	PVC Insulated Copper Conductor armored power cables and multi straned flat cables/control	(a) National (b) Finolex (c) Ekta Cables (d) Havells (e) Plaza (f) Universal Cables (g) Grandlay

Ser No	Name of Item	List of makes/Brands/Manufacture
18.	Conduit Steel	(a) Jindal (b) AKG (c) Asian (d) Bharat Steel tubes Kanpur
19.	Conduit Rigid PVC and accessories	(a) Jindal (b) AKG (c) AG (d) Finolex (e) Srinath Pipes Ltd (f) Seiko (g) RK Electricals
20.	Wiring Accessories	(a) Anchor (b) Kinjal (c) Cona (d) Plaza
21.	ELCB/ROCB/A&D/DBs	(a) Control and switch gears (b) Standard (c) Havells (d) Legrand (e) Siemens (f) Eleger (L&T) (g) Merlin Gerln
22.	MS GI Pipes ISI 239 Latest	(a) TATA (b) Jindal (c) Swastik (d) Prakash

23.	Stop Valves/Gate valves	(a) Leader (b) Bo mbay metal & alloy Co (b) BIR (c) SAINT (d) ZOLOTO (e) PRATAP valves, Jallandar (f) NMC
24.	CI Soil and Soil Waste Pipes	(a) Jayaswals Neco ltd Nagpur (b) Corporate Ispat allogs, Ltd Durgapur (713012) (c) Indoswedish products Agra (d) Ashutosh iron factory Nagpur
25.	PVC Pipes	Supreme, Finolex, Prince, Kissan Mouldings Pvt Ltd
26.	SGSW Pipes	Gupta Refractories Gwalior, Devraj Anand Gaziabad, Perfect Jabalpur.
27.	Barbed wire	M/S Swastika Polysteel Ltd, M/S Amar Promotors Pvt Ltd
28.	DI PIPE & FITTINGS	(a) ELECTRO STEEL CASTING LTD – KOLKATA (b) TATA (c) Jindal
29.	SLUICE VALVES	(a) Leader (b) Kirlosker (c) Zoloto
30.	GI Pipes/ MS pipe	(a) TATA (b) Jindal (c) Swastik (d) Prakash (e) Zenith
31.	STOP VALVE/GATE VALVE	(a) ZOLOTOV (b) LEADER (c) KIRLOSKER
32.	CI PIPE & FITTINGS	(a) ELECTRO STEEL CASTING LTD – KOLKATA (b) KESORAM INDUSTRIES (c) KAPILANSH (M/S KALILANSH DHATU UDYOG (P) LTD, NAGPUR

Note:- The MAKEs of materials mentioned above shall be followed only when the same are not described in BOQ. In that case the makes for a particular item(s) given in approved list of makes by command chief Engineer and E-in-C Branch for A/1st cat shall also be applicable.

MILITARY ENGINEER SERVICES
NOTICE INVITING TENDER (NIT)

1. A Tender is invited to the work as mentioned in Appendix 'A' to this NOTICE INVITING TENDER (NIT).

2. The work is estimated to cost as indicated in aforesaid Appendix 'A'. This estimate, however, is not a guarantee and is merely given as a rough guide and if the work cost more or less, a tenderer / bidder will have no claim on that account. The tender shall be based on as mentioned in aforesaid Appendix 'A".

3. The work is to be completed within the period as indicated in aforesaid Appendix 'A' in accordance with the phasing, if any, indicated in the tender from the date of handing over site, which will be on or about two weeks after the date of Acceptance of tender..

4. Normally contractors whose names are on the MES approved list for the area in which the work lies, and within whose financial category the estimated amount would fall, may tender / bid but in case of term contracts, contractors of category SS to E may tender / bid. In case where the tender amount is in excess of the financial limit of the contractor and the Accepting officer decides to accept the tender. Bid, in which event the tenderer / bidder would be required to lodge additional security deposit as notified by the Accepting officer in term of conditions of contract. Contractors whose names are on the MES approved list of any MES formation and who have deposited standing security and have executed standing security bond may also tender / bid submitted without depositing earnest money along with the tender / bid and if the tender / bid submitted by such a tenderer / bidder is accepted, the contractor will be required to lodge with the Controller of Defence Accounts concerned the amount of "Individual security deposit" within thirty days of the receipt by him of notification of acceptance of his tender / bid, failing which this sum will be recovered from Fist RAR payment or from the first final bill> In case of Term / Running contracts, remaining sum shall be recovered from subsequent bill(s) of the contractor. Not more than one tender / bid shall be submitted / uploaded by one contractor or one firm of contractors. Under no circumstances will a father and his son(s) or other close relations who have business dealing with one another be allowed to tender / bid for the same contract as separate competitors. A breach of this condition will render the Tenders / bids of both the parties liable for rejection.

5. The Garrison Engineer (AF) Bakshi Ka Talab, Lucknow, C/O 56 APO will be the Accepting Officer here in after referred to as such for the purpose of the contract

6. The Technical Bid and Financial Bid (Cover-1 and Cover-2) shall be uploaded by the tenderer / bidder on or before the date & time mentioned in NIT. A scanned copy of DD with enlistment details / documents shall be uploaded as packet -1 / cover- 1 ('T' bid) of the tender / bid on e-tendering portal. DD is refundable in case 'T' bid is not accepted resulting in non-opening of 'Q' bid. The applicant contractor shall bear the cost of bank charges for procuring and encashing the DD and shall not have any claim from Government whatsoever on this account.

6.1 Tender form and conditions of contract and other necessary documents shall be available on eprocuremes.gov.in / eprocure.gov.in site for download and shall form part of contract agreement in case the tender / bid is accepted.

6.2 In case of contractor who has not executed the Standing Security Bond, the Cover-1 shall be accompanied with by Earnest money of amount as mentioned in Appendix 'A' in the form of deposit at call receipt in favour of concerned CCE / GE / GE(I) / AGE(I) (see Appendix 'A') by a schedule Bank or in receipted treasury Challan the amount being credited to the revenue deposit of the concerned CCE / GE / GE(I) / AGE(I) (see Appendix 'A').

6.3 Blank

6.4 Blank

6.5 The CCE / GE / GE(I) / AGE(I) will return the Earnest Money wherever applicable to all unsuccessful tenderers / bidders by endorsing an authority on the deposit-at-call receipt for its refund, on production by the tenderer / bidder a certificate of the Accepting Officer that a bonafide tender / bid was received and all documents were returned.

6.6 The CCE / GE / GE(I) / AGE(I) will either return the Earnest Money to the successful tenderer / bidder by endorsing an authority on the deposit-at-call Receipt for its refund on receipt of an appropriate amount of Performance/security deposit or will retain the same in part or full on account of Performance/ security deposit if such a transaction is feasible.

6.7 Copies of the drawings and other document pertaining to the work signed for the purpose of identification by the Accepting Officer or his accredited representative, sample of materials and stores to be supplied by the contractor will also be available for inspection by the tenderer / bidder at the office of Accepting Officer and concerned GE / GE(I) / AGE(I) during working hours.

7. The tenderers / bidders are advised to visit site of work by making prior appointment with GE / GE(I) / AGE(I) / CCE / Project Manager who is also the Executing AGENCY OF THE WORK (SE Appendix 'A'). The tenderers / bidders are deemed to have full knowledge of all relevant documents, samples, site etc, whether they have inspected them or not.

8. Any tender / bid which proposes any alteration to any of the conditions laid down or which proposes any other condition or prescription whatsoever, is liable to be rejected.

9. The uploading of bid implies that bidder has read this notice and conditions of contracts and has made himself aware of the scope and specifications of the work to be done and of conditions and rates on which stores, tools and plants etc will be issued to him and local conditions and other factors bearing on the execution of work.

10. Tenderers / bidders must be in possession of a copy of the MES Schedule of Rates (see Appendix 'A') including errata and amendments thereto.

11. Invitation for e-tender does not constitute any guarantee for validation of 'T' bid and subsequent opening of finance bid of any applicant / bidder, even of enlisted contractors of appropriate class, merely by virtue of enclosing DD. Accepting Officer reserves the right to reject the 'T' bid and not open the finance bid of any applicant / bidder. 'T' bid validation shall be decided by the Accepting Officer based on, interalia, and capability of the firm as per criteria given in Appendix 'A' to this NIT. The applicant contractor / bidder will be informed regarding non-validation of his 'T' bid assigning reasons thereof through the eprocuremes website. The applicant contractor / bidder if he so desires may appeal to the next higher Engineer authority viz CWE (AF) Izatnagar, Bareilly on email ID afbrlylz3- mes@nic.in with copy to the Accepting Officer on email before the scheduled date of opening of Finance bid. The decision of the next Higher Engineer Authority (NHEA) shall be final and binding. The contractor / bidder shall not be entitled for any compensation whatsoever for rejection of his bid.

12. The Accepting Officer reserves the right to accept a tender submitted by Public Undertaking giving a price preference over other tender(s) / bids which may be lower, as are admissible under the Government policy. No claim for any compensation or otherwise be admissible from such tenderer / bidder whose tender / bid is rejected.

13. Accepting Officer does not bind himself to accept the lowest or any tender / bid or to give any reason for not doing so.

14. This Notice Inviting Tender (NIT) including Appendix 'A' shall form part of the contract.

AGE (Contract)
For Accepting Officer

Signature of the contractor
Dated : _____

APPENDIX 'A" TO NOTICE INVITING TENDER (NIT)

1.	Name of work	**REPAIR / MAINT OF LT DISTRIBUTION SYSTEM AND REPAIR MAINT OF PIPE LINE AT AF STN BKT**
2.	Estimated cost	**Rs. 23.00 lakhs (At Par market)**
3.	Period of completion	**180 Days**
4.	Cost of tender documents	**Rs 500.00** in the shape of DD/Bankers cheque from any schedule Bank in favour of GE(AF) Bakshi-Ka-Talab and payable at Lucknow
5.	Website/portal address	www.defproc.gov.in and www.mes.gov.in
6.	Type of contract	The tender shall be based on drawing and specifications IAFW 1779A and GCC (IAFW-2249) with Schedule 'A' (list of items of work) to be priced by contractor. The contractor is required to quote their rates against each items of Schedule 'A'/BOQ.
7.	Information & Details: (a) Bid submission start date (b) Bid submission end date (c) Date of bid opening	Refer Critical dates:
8.	Eligibility Criteria: -	
	(a) For MES enlisted contractors	Contractors shall be enlisted with MES in **Class 'E'** and above and category **a (ii) & b (i)** subject to satisfactory remarks wrt performance in respect of works in hand reflected in work load return (WLR) or any other report circulated by competent engineer authority.
	(b) For contractors not enlisted with MES	(i) Contractors not enlisted with MES should meet the enlistment criteria of **'E' Class and a (ii) & b (i)** category. Contractor with regard to satisfactorily completion of requisite value of works with Central/state Government /Central/state Government PSU / AWHO / AFNHB / CGEWHO / DGMAP ,annual turnover, bank solvency, working capital and other requirements given in para 1.4 and 1.5 of Section 1 of MES Manual on Contracts-2020 as available in all MES formations as well as MES website(www.mes.gov.in) (ii) Not carrying adverse remarks in Work Load Return (WLR) or any other similar report circulated by any competent authority, if already working in MES (iii) Not suspended / debarred / blacklisted (either permanently or temporarily) from participating in any bid or for business dealings by any central/state Department or any Central/state Government or any autonomous Body under Central/state Government or any local body as on the bid submission end date. (iv) Also refer Note-below for all contractors [Sl No 8(C)].

	(C) For All Contractors	(a) Contractor will not be allowed to execute the work by subletting or through power of attorney holder on his behalf to a third party/ another firm except sons/ daughters of proprietor/ partner/ Director and firm's own employees, Director, Project Manager. This shall be subject to certain conditions, which will be prescribed in the NIT forming part of the tender documents. (b) Prior to commencement of electrical work/electrical component of works and other works as mentioned in BOQ, copy of valid Electrical License in the name of the contractor or copy of agreement with agency having valid Electrical License along-with Agency's Electrical License shall be submitted by the contractor to the Accepting Officer. In case contractor does not possess valid Electrical License and he intends to get such work executed through agency having valid Electrical License and with whom he has agreement prior approval of such agency shall be got done from GE. Copy of License shall be kept on record by GE for further reference. (c) In addition, Supervisor for execution of electrical works/electrical component of works employed by the contractor shall possess, Supervisor Certificate of Competency issued by concerned State Govt/Union Territory and the worker/tradesmen for execution of electrical works/electrical component of works shall hold necessary Permit issued by concerned State Govt/Union Territory. (d) Reference of Electrical License and details of Supervisor's Certificate of Competency and permit of tradesman employed for execution of electrical work/electrical component of works shall be duly incorporated in the Works Diary and relevant site documents respectively for the whole period during which such works is executed. (e) If the contractor fail to submit the License/permit necessary action as deemed fit shall be taken against the contractor.
9.	Tender issuing and Accepting Officer	GE (AF) Bakshi – Ka – Talab Lucknow-226201 Mail Id :- afbkt4-mes@nic.in
10.	Executing agency	GE (AF) Bakshi – Ka – Talab
11.	Earnest Money	**Rs. 46,000.00** in the form of DD/Bankers cheque from any Scheduled bank in favour of GE(AF) Bakshi-Ka-Talab and payable at Bakshi-Ka-Talab Lucknow. FDR not acceptable

APPENDIX 'A' TO NOTICE INVITING TENDER (NIT)

NOTES:

1. After opening of Cover 1, if the number of MES enlisted contractors of eligible class as well as un-enlisted contractors. If any, fulfilling the other eligibility criteria given in NIT are less than 7 (seven). Applications in respect of contractors one class or two classes (in case of remote and difficult areas to be decided as per list circulated by CE command/ADG) below the eligible class shall also be considered subject to fulfillment of other eligibility criteria given in the NIT. Therefore, MES contractors one class below (two classes below in case of remote and difficult areas) may also bid for this tender. However, contractors of one/two classes below the eligible class shall not be considered in case their present residual work in hand is more than twice their present tendering limit. Such bidders shall upload in their Cover –I bid details of works in hand showing names of work, names of Accepting Officers, contract amounts, dates of commencement and completion (stipulated) and progress as on bid submission date. These details shall be verified by the Tender Issuing Authority from concerned formations in case bids of such contractors are considered for evaluation.

2. In case after opening of Cover I, the number of MES enlisted contractors of eligible class as well as un-enlisted contractors, if any, fulfilling the other eligibility criteria given in NIT, are 7 (seven) or more, applications of only those one class below the eligible class bidders shall be considered, who have previously completed similar works satisfactorily and are meeting the criteria of up gradation in respect of past experience of completed works (individual work experience and/or average annual turnover as applicable) and financial soundness (solvency/financial soundness and working capital) as per details given in Manual on contracts. Therefore, such contractors shall upload the requisite information/documents in the Cover-I.

3. Unlisted contractor shall be considered provided he meets the criteria. Foreign firms shall not be eligible for this tender. However Indian Firms having foreign national /Indian nationals staying abroad /Indian national having taken foreign citizenship, as director(s) shall be considered subject to clearance from the concerned authorities.

4. Contractors enlisted with MES will upload following documents in Cover-I for taking eligibility :-

(a) Application for tender on Firm's letterhead.

(b) Enlistment letter issued by the Registering Authority duly renewed for the cycle period in vogue.

(c) Scanned copy of DD/Bankers Cheque toward cost of tender and EMD instrument in case SSD bond is not signed at the time of registration.

(d) Any other document required as described in this Appendix.

5. Contractors not enlisted with MES will be required to upload following documents in Cover I for checking eligibility.

(a) Application for tender on Firm's letterhead.

(b) Scanned copy of DD/Bankers cheque toward cost of tender and Earnest Money Deposit (EMD) instrument.

(c) Copy of Police Verification report/Police Clearance Certificate/ Character Certificate from the Police Authority of the area where the registered office of the firm is located/notarized copy of valid passport of Proprietor/each Partner/each Director.

(d) All documents required for enlistment in MES for the class mentioned in Para 8(b) above as per Para 1.5 of Section 1 of MES Manual on Contracts 2020.

APPENDIX 'A' TO NOTICE INVITING TENDER (NIT)

(e) Details of works being executed in MES, if any.

(f) Any other documents required as described in this Appendix.

6. Tenders not accompanied by scanned copies of requisite DD/Bankers Cheque towards cost of tender and earnest money (as applicable) in Cover I shall not be considered for validation of 'T' bid and their Financial Bids will not be opened.

7. Contractor should ensure that their original physical DDs and Earnest Money Deposit (EMD) instruments (as applicable) reach the office of Accepting Officer within 5 days of bid submission end date failing which following action shall be taken: -

(a) In case of tenders from an enlisted contractor of MES, where scanned copies of requisite DD/Bankers Cheque towards cost of tender have been uploaded in Cover I but physical copies are not received within the stipulated period, their financial bids (Cover 2) will be opened. However non-submission of physical copies of cost of tender shall be considered as willful negligence of the tender with ulterior motives and such tenders shall be banned from bidding for a period of six months commencing from the date of opening of Financial Bid (Cover 2).

(b) In case of tenders from unenlisted contractor, where scanned copies of requisite DD/Bankers Cheque towards cost of tender have been uploaded in Cover I but physical copies are not received within the stipulated period, their financial bids (Cover 2) will not be opened. Name of such contractors along with complete address shall be circulated for not opening of their bids for a period of six months commencing from the date of opening of Financial bid (Cover 2).

(c) In case of tenders from enlisted and un enlisted contractor, where scanned copies of instruments for Earnest Money Deposit (as applicable) have been uploaded in Cover I but the same are not received in physical form within stipulated period, such tenders shall not qualify for opening of financial bid (Cover 2).

8. Contractor will not be allowed to execute the work by subletting or through power of attorney to a third party/another firm on his behalf, However a contractor can execute the work through power of attorney to sons/daughters/spouse of Proprietor/Partner/Director and firm's own employees, director, project manager **Provided they are not having a separate enlisted firm in MES in their name as Proprietor/Partner /Director**.

9. After opening of Cover I and during its technical evaluation, in case any deficiency is noticed in the documents required to be uploaded by the tenderers as per NIT, a communication in the form of e-mail / SMS/Speed Post etc shall be sent to the contractor to rectify the deficiency within a period of seven days from date of communication, failing which their financial bid (Cover 2) shall not be opened and contractor shall not have any claim on the same.

10. Invitation for e-tender does not constitute any guarantee for validation of Technical bid and subsequent opening of financial bid of any applicant/bidder merely by virtue of enclosing DD. Accepting Officer reserves the right to reject the Technical bid and not to open the financial bid of any applicant/bidder. Technical bid validation shall be decided by the Accepting Officer based on eligibility of the firm as per criteria given in this Appendix. Tenderer/ bidder will be informed regarding non-validation of his Technical bid assigning reasons therefore through tender evaluation report which shall be uploaded on the website. Such tenderer, if desires, may appeal to the next higher Engineer Authority (NHEA) viz HQ CWE (AF) Bareilly on email id afbrlylz3- mes@nic.in with copy to Accepting Officer on email before the scheduled date of opening of Cover 2 . NHEA shall decide the matter within a period of seven working days from the date of receipt of appeal. The decision of the NHEA shall be final and binding. The tenderer /bidder shall not be entitled for any compensation whatsoever for rejection of his bid.

APPENDIX 'A' TO NOTICE INVITING TENDER (NIT)

11. In case an unenlisted contractor is already executing works in MES, he shall not be considered eligible for the subject tender if the total value of such work is more than twice the tendering limit of the MES Class of contractor for which it is eligible. For this purpose, details of the works being executed by such a contractor shall be uploaded in cover-1 of the bid and shall be checked/verified by the Accepting Officer.

12. In case the BOQ is revised through the corrigendum and the bidder has failed to quote on revised BOQ (ie he has quoted on pre revised BOQ), such bid shall be treated as willful negligence by the bidder and his quotation shall be considered non-bonafide. In such cases the lowest tender shall be determined from amongst the valid/ bonafide bids only. Accepting Officer may decide whether to re-tender or consider the lowest bonafide tender for acceptance.

13. Revoking the offer or revising the rates upward or offering voluntary reduction by the lowest tenderer after opening of Cover 2 shall be considered as a willful default. For this default a penalty of an amount equal to Earnest Money shall be levied. In case of an unenlisted tenderer, Earnest Money deposited by him shall be forfeited. In case of MES enlisted tenderer having deposited the Standing Security Bond, an amount equal to the earnest money stipulated in the NIT shall be notified to the tenderer for depositing through MRO and consideration of such tenderer in tender evaluation for future works shall remain suspended till the afore mentioned amount is deposited in the Government Treasury. No other disciplinary/administrative action shall be taken against such tenderers. In such a situation, the next lowest offer shall not be considered for acceptance. Instead, retendering shall be resorted to in a transparent and fair manner and the defaulting tenderer and his related firm if any, shall not be eligible for this tender in second call or subsequent calls.

14. Tender to related firms shall not be issued simultaneously. Firms shall be termed as related if Proprietor/one or more Partners/Directors are common. Decision of Accepting Officer on issue/deny the tender to any one of the related firms shall be final and binding.

Signature of contractor

AGE (Contract)
For Accepting Officer

File No: - 8769/BKT/E8
GE (Air Force) Bakshi-ka-Talab
PIN 901109