CA No. CECG/GOA/ /OF 2025-26

Serial Page No. 145
In lieu of IAFW-2159 (Revised 1947)

NAME OF WORK: DEMOLITION AND RECONSTRUCTION OF JCOS/SOS IN-LIVING ACCOMODATION (BLDG NO P-17) AT ICGAS DAMAN

SCHEDULE 'A' PART - I
(BUILDINGS/ STRUCTURES)

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	**2**	**3**	**4**	**5**	**6**	**7**	**8**
1	Construction of Building (G+2) for single living accommodation for JCO's/SOs including mess & club, scooter & car parking with Permanent Specification with RCC framed structure using M-30 Grade Design Mix concrete etc all as shown on drawing, as specified and as directed.		15698600.00 Each Block	1.00	15698600.00		

Total of Sch 'A' Part -I C/O to BOQ **Rs** **15698600.00**

Signature of Contractor
Date : _____

AAD (Contracts)
For Accepting Officer

SCHEDULE 'A' PART - II

(EXCAVATION, EARTHWORK, SITE CLEARANCE & SITE DEVELOPMENT)

NOTES : All excavation & earth work required for items of works covered under Schedule `A' Parts III to XII shall be measured and paid under relevant items of this Schedule, unless otherwise specifically mentioned in the description of the items of Schedule `A' Part III to XII.

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
1	Surface excavation not exceeding 30 cm deep and average 15 cm deep and getting out in soft and loose soil complete all as specified and directed		53.10 SQM	200.00	10620.00		
2	Rough excavation not exceeding 1.5 m deep and getting out Soft/ loose soil complete all as specified and directed		179.10 SQM	150.00	26865.00		
3	Surface dressing of berms manually, improvement of berms not exc 15cm deep in soft/loose soil including removal not exc 1000 mtr distance complete all as specified and directed		26.90 CUM	30.00	807.00		
4	Excavation in trenches n. exc 1.5 m wide and not exceeding 1.5 m in depth for foundation etc, or for shafts, wells, cess pits, manholes, pier holes, laying of cables, RCC poles/stays and struts etc. and getting out in soft/loose soil complete all as specified and as directed		383.70 CUM	34.20	13122.54		
5	Returning, filling in, including spreading, levelling, watering and well ramming in layers not exc 25 cm complete all as specified and as directed.		139.10 CUM	10.00	1391.00		
6	Removing excavated surplus soil obtained from excavation to a distance not exceeding 50m and depositing where directed at a level not exceeding 1.5 m above the starting point all as specified and directed.		320.40 CUM	170.00	54468.00		

C/O to next page **Rs** **107273.54**

SCHEDULE 'A' PART - II
(EXCAVATION, EARTHWORK, SITE CLEARANCE & SITE DEVELOPMENT) (CONTINUED..)

NOTES : All excavation & earth work required for items of works covered under Schedule `A' Parts III to XII shall be measured and paid under relevant items of this Schedule, unless otherwise specifically mentioned in the description of the items of Schedule `A' Part III to XII.

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
	B/F from previous page			**Rs.**	**107273.54**		
7	Removing excavated/ surplus soil exc 250 m but not exc 500 m and depositing where directed at a level n.exc 1.5 m above the starting point complete all as specified and a directed.		582.60 CUM	5.20	3029.52		
8	Removing of surplus excavated material exceeding 1.50Km but n. exc 5.00Km complete all as specified and as directed		684.60 CUM	30.00	20538.00		

Total of Sch 'A' Part -II C/O to BOQ **Rs** **130841.06**

Signature of Contractor
Date : _____

AAD (Contracts)
For Accepting Officer

SCHEDULE 'A' PART - III
(DEMOLITION AND DISMANTLING)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
1	Taking down chowkat & frames exc 1.5 Sqm but not exc 4 Sqm each (w/o taking off shutter from frame)		357.30 EACH	36.00	12862.80		
2	Taking down chowkat & frames not exc 1.5 Sqm each (w/o taking off shutter from frame)		282.90 EACH	72.00	20368.80		
3	Demolition of RCC, Roofs, floors (other than ground floors), beams, staircases, landing, chajjas and similar suspended work including embedded portions and removal of debries i.e portion of demolished/dismantled RCC/PCC in any size and any shape to out side of MoD land at the description of contractor's risk & cost.		2634.40 CUM	170.00	447848.00		
4	Demolition of Brickwork or stone / boulder masonary built up in cement mortar complete all as specified and directed		1641.94 CUM	209.00	343165.46		
5	Demolition of cement concrete of any description and in any position not otherwise specifically provided for complete all as specified and directed		1631.30 CUM	39.00	63620.70		
6	Dismantaling of wrought iron or mild steel work of any description not otherwise provided for structural steel work complete all as specified and directed		574.90 Quintal	2.00	1149.80		

C/O to next page **Rs** **889015.56**

SCHEDULE 'A' PART - III
(DEMOLITION AND DISMANTLING) (CONTINUED..)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
	B/F from previous page			**Rs.**	**889015.56**		
7	Taking down soil waste and vent pipe (RWP) of 75/80mmdia any description and any position joint/Lead joint and removing from site complete all as specified and directed		48.50 RM	31.50	1527.75		
8	Taking up or down steel tubing 15mm dia & connection including cleaning for reuse or removal from site complete all as specified and directed		30.25 RM	180.00	5445.00		
9	Taking up or down steel tubing 20mm dia & connection including cleaning for reuse or removal from site complete all as specified and directed		36.62 RM	40.00	1464.80		
10	Taking down or dismantling of sanitary fittings and water connections and taps like WHB, WC, Pillar tap, bib tap, stop cock, angle cock, shower rose, connection pipes, like etc		20.00 RM	64.00	1280.00		
11	Dismantling water tanks 500 lts capacity all as directed		752.24 EACH	8.00	6017.92		
12	Taking down carefully copper/aluminium point wiring (light,fan socket or power) point complete,including fixtures and fittings such as switches, ceiling rose, pendents, regulators, sockets, tube light fitting,main switch, MCB and DB's etc complete all as specified and directed		152.00 POINT	182.00	27664.00		
	C/O to next page			**Rs**	**932415.03**		

SCHEDULE 'A' PART - III
(DEMOLITION AND DISMANTLING) (CONTINUED..)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
	B/F from previous page			**Rs.**	**932415.03**		
13	Taking down existing tube light fitting, ceiling light fitting of any type/make complete and replacing of bipin holder,starter, connector etc and fixing back in existing or other place by providing PVC square box-02 Nos, tube rod and adequate length of three core flexible copper cable 0.75 sqmm from ceiling rose to fitting etc complete		34.94 EACH	90.00	3144.60		
14	Taking down ceiling/Exhaust fan/wall fans, from its position and keeping aside in safe custody for servicing and unserviceable fan shall be deposited in MES store yard		205.90 EACH	42.00	8647.80		
15	Taking down existing GI pipe of dia 50mm from floor/ ceiling /wall with disconnecting of water supply connection complete all as specified and complete		39.40 EACH	35.00	1379.00		
	Total of Sch 'A' Part -III C/O to BOQ			**Rs**	**945586.43**		

Signature of Contractor
Date : _____

AAD (Contracts)
For Accepting Officer

SCHEDULE 'A' PART - IV
(INTERNAL WATER SUPPLY)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
1	Supplying and laying of CPVC pipes of SDR 11 & Plain CPVC SDR 11 fittings on walls/ceiling or laying in floors of following size complete all as specified and directed.						
	(a) 20mm outer dia pipes		244.60 RM	90.00	22014.00		
	(b) 25mm outer dia pipes		353.40 RM	25.00	8835.00		
	(c) 32mm outer dia pipes		464.90 RM	50.00	23245.00		
2	S & F Gun-metal or gate valves, 32 mm dia, with iron wheel head, screwed both ends for iron pipes/ fitting including necessary fittings like CPVC Tee, nipple etc. complete all as specified and directed.		604.51 Each	6.00	3627.06		
3	S & F Gun-metal or gate valves, 32 mm dia, with iron wheel head, screwed both ends for iron pipes/ fitting including necessary fittings like CPVC Tee, nipple etc. complete all as specified and directed.		545.30 Each	5.00	2726.50		
4	S & F 15mm dia Bib taps, long body, fancy type chromium plated, cast copper alloy with crutch or butterfly handle, screwed down, screwed for iron pipe or CPVC pipes etc. complete all as specified and directed		607.57 Each	15.00	9113.55		
5	S & F 15mm dia angular stop valve, fancy type chromium plated, cast copper alloy screwed down, high pressure with crutch or butterfly handle, complete all as specified and directed		682.03 Each	18.00	12276.54		

C/O to next page **Rs** **81837.65**

SCHEDULE 'A' PART - IV
(INTERNAL WATER SUPPLY) (CONTD…..)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
	B/F from previous page			**Rs.**	**81837.65**		
6	S & F Pillar tap, 15 mm dia cast copper alloy with capstain head, chromium plated fancy type screwed down, high pressure with crutch or butterfly handle, complete all as specified and directed.		676.44 Each	9.00	6087.96		
7	S & F of PVC connection 15 mm dia, 600mm long complete all as specified and directed.		200.00 Each	18.00	3600.00		
8	S & F in chromium plated shower roses 125mm size with or without swivel joints, any size, including fixing to steel pipe or union 15mm bore complete all as specified and directed.		409.25 Each	6.00	2455.50		
	Total of Sch 'A' Part -IV C/O to BOQ			**Rs**	**93981.11**		

Signature of Contractor
Date : _____

AAD (Contracts)
For Accepting Officer

SCHEDULE 'A' PART - V
(INTERNAL ELECTRIC SUPPLY)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
1	M & L for point wiring using ISI marked 1.1 kV grade single core FR-LSH flexible cable, conforming to IS: 694- 1990, having multi-drawn thin strands of electrolytic copper conductors, conforming to IS: 8130- 1984 and insulation conforming to IS: 5831- 1984, for phase, neutral and earth continuity conductor (same size of phase conductor) connecting to earth dolly, drawn in not less than 25 mm NB PVC medium grade concealed conduits, conforming to IS: 9537 (Part 3)- 1983, colour-coded as specified in IS: 11353- 1985, including factory made sunken, galvanized, not less than 1.00 mm thick modular flush sheet metal enclosure having top, bottom, side and back-wall knockout for conduit entry from any direction, conforming to IS: 14772- 2000 and including modular cover-plates complete all as specified in IS: 732- 1989 and directed. (Note : Circuit wire from DB to switch boards shall be included in quoted rate).						
	(a) One light point controlled by one switch with cables 1.5 mm² size		992.75 Per Point	101.00	100267.75		
	(b) One light point controlled by two, 2 way switches with cables 1.5 mm² size		1397.96 Per Point	3.00	4193.88		
	(c) One fan or exhaust fan / Fresh Air Fan point controlled by one switch with cables 1.5 mm² size		992.75 Per Point	36.00	35739.00		
	(d) One 6 A socket outlet, on the same board with other switches, with cables 1.5 mm² size		284.10 Per Point	27.00	7670.70		
	(e) One 6 A socket outlet, independent, with cables 1.5 mm² size		1070.40 Per Point	21.00	22478.40		
	C/O to next page			**Rs**	**170349.73**		

SCHEDULE 'A' PART - V
(INTERNAL ELECTRIC SUPPLY) (CONTD…..)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
	B/F from previous page			**Rs.**	**170349.73**		
2	S & F modular type 6 A one-way SP switch, conforming to IS: 3854- 1997 with finger proof terminal complete as specified and directed		260.50 Each	185.00	48192.50		
3	S & F modular type 6 A two-way SP switch, conforming to IS: 3854- 1997 with finger proof terminal complete as specified and directed.		307.30 Each	6.00	1843.80		
4	M & L for point wiring using ISI marked 1.1 kV grade single core FR-LSH flexible cable, conforming to IS: 694-1990, having multi-drawn thin strands of electrolytic copper conductors, conforming to IS: 8130- 1984 and insulation conforming to IS: 5831- 1984, for phase, neutral and earth continuity conductor connecting to earth dolly, drawn in not less than 25 mm NB PVC medium grade concealed conduits, conforming to IS: 9537 (Part 3)- 1983, colour-coded as specified in IS: 11353- 1985, including factory made sunken, galvanized, not less than 1.00 mm thick modular flush sheet metal enclosure having top, bottom, side and back-wall knockout for conduit entry from any direction, conforming to IS: 14772- 2000 and including modular cover-plates complete all as specified in IS: 732- 1989 and directed. NOTE:- Circuit wire 4 sqmm from DB to switch boards shall be included in quoted rate.							
	(a) One 16 A socket outlet, independent, with cables 2.5 mm² size		1131.39 Point	16.00	18102.24		
5	S & F modular type 16 A one-way SP switch, conforming to IS: 3854- 1997 with finger proof terminal complete as specified and directed.		343.70 Each	16.00	5499.20		
6	S & F modular type 2/3 pin combined shuttered type 6 A socket conforming to IS: 1293- 2005 complete as specified and directed.		340.54 Each	48.00	16345.92		
7	S & F modular type 2/3 pin combined shuttered type 6/16 A socket conforming to IS: 1293-2005 complete as specified and directed		528.40 Each	16.00	8454.40		
	C/O to next page			**Rs**	**268787.79**		

SCHEDULE 'A' PART - V
(INTERNAL ELECTRIC SUPPLY) (CONTD…..)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
	B/F from previous page			**Rs.**	**268787.79**		
8	S & F modular type 120 W step fan regulator of 2 module size, conforming to IS: 11037-1984 complete as specified and directed		1017.95 Each	25.00	25448.75		
9	S & F 6 A, 250 V high quality robust surface/flush type polycarbonate/PVC ceiling rose, conforming to IS: 371- 1979, having 3 terminals and outside diameter not less than 63.5 mm complete all as specified and directed		65.70 Each	137.00	9000.90		
10	Supply and Fixing surface mounted LED batten 10W with extruded aluminum housing heavy duty integrated electronic driver, surge protection more than 2 KA and THD<10% Make: Havells Cat Part No: ENDURA LINEAR 0BS10WLED865SPCSS/ WIPRO/PHILLIPS/BAJAJ		693.75 Each	34.00	23587.50		
11	Supply and Fixing surface mounted LED batten 20W with extruded aluminum housing heavy duty integrated electronic driver, surge protection more than 2 KA and THD<10% Make: Havells Cat Part No: ENDURALINEAR0BS20W LED865SPCSS /WIPRO/PHILLIPS/BAJAJ		693.75 Each	47.00	32606.25		
12	Supply and fixing LED security light fitting 25/35 watt 230V AC outdoor type with pressure die cast aluminium housing and heat resistant complete with driver, lamp bracket with impact and corrosion resistant including thermal management in multiple optics complete with IP65/66 protected complete as specified and directed.		2966.25 Each	11.00	32628.75		
13	Supply and Fixing LED light fitting 1x5W mirror light, 220V, AC decorative box type with driver including LED connecting up with three core flexible copper conductor of suitable size from ceiling rose complete all as specifed and directed.		1745.46 Each	9.00	15709.14		
	C/O to next page			**Rs**	**407769.08**		

SCHEDULE 'A' PART - V
(INTERNAL ELECTRIC SUPPLY) (CONTD…..)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
	B/F from previous page			**Rs.**	**407769.08**		
14	S & F RCBO conforming to IS 12640 (Part 2): 2016, assembled for AC applications having front face indication for earth leakage fault, sliding shutters, IP 20 protected 35mm² terminals, colour coded on/off indication on dolly, integrated label holder, etc complete all as specified and directed. (a) 63 A, 30 mA, FP 415V, 50 Hz RCBO		3111.87 Each	2.00	6223.74		
15	S & F MCB for AC applications conforming to IS/IEC 60898-1-2002, 'C' curve having breaking capacity Icon = 10 kA, sliding bottom clamp, colour coded on/off indication on dolly, biconvex IP 20 protected lower terminals and sliding shutters, etc. complete all as specified and directed by engineer-in-charge. (a) 63A, FP 415V, 50Hz MCB		2360.74 Each	2.00	4721.48		
	(b) 6 to 20A, SP 415V, 50Hz MCB		294.00 Each	40.00	11760.00		
	(c) 10 to 40A, SPN 415V, 50Hz MCB		851.20 Each	16.00	13619.20		
16	M & L for sub main wiring using ISI marked 1.1KV grade single core flexible cable conforming to IS694-1990 having multi drawn thin strands of electrolytic copper conductors and insulation conforming to IS 5831-1984, type C, HR 85oC + FR for phase, neutral and earth continuity conductor connecting to earth dolly drawn in not less than 25mm NB UPVC medium grade concealed conduits conforming to IS 9537, Part-3, colour coded as specified in IS 732-1989 including making good of disturbed surfaces of wall/ ceiling/ floor all as directed by Engineer in Charge. Notes:- 01 run of phase, 01 run of neutral, 01 run of earth continuity and 01 run of concealed conduit shall be measured as one length (a) 4 x 4.0mm2+1 x 4.0mm2 earth wire		215.00 RM	150.00	32250.00		
	C/O to next page			**Rs**	**476343.50**		

SCHEDULE 'A' PART - V
(INTERNAL ELECTRIC SUPPLY) (CONTD…..)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
	B/F from previous page			**Rs.**	**476343.50**		
17	S & F single pole & neutral DB (double door), conforming to IEC 61439- 3, suitable for flush mounting with 100 A insulated & shrouded copper busbar for each phase, fully insulated & shrouded neutral bar, earth bar, wire set and cable ties for cable management, IP 43 & IK 09 protection with provision for FP RCBO as incomer and SP MCBs as outgoing, all complete as specified and directed. Note: MCBs shall be measured and paid in relevant items						
	(a) Triple Pole & Neutral DB, 6 Way 415 V		3186.20 Each	1.00	3186.20		
	(b) Triple Pole & Neutral DB, 8 Way 415 V		3588.70 Each	1.00	3588.70		
18	M & L for earthing complete with galvanized steel earth plate electrode of 60 cm X 60 cm X 6 mm size, buried directly in ground (earth pit not less than 2.25 m deep below ground level) with top edge of the plate not less than 1.5 mtr below normal ground level, connected to galvanized earth led wire 4 mm dia as earth lead by means of bolts, nuts, check nuts and washers of galvanized iron or steel, galvanized iron pipe light grade 15 mm diameter for protection of earthing wire, (To be concealed in wall/floor) connected to earthing test point, all as shown in electrical plate No. 3, connected to earthing test point including testing on completion, excavation, earthwork, PCC earth pit of dimensions 550 mm X 550 mm (outer) and 300 mm X 300 mm (inner) and 250 mm deep with a 10 mm deep CI cover hinged to CI frame on ground level, 20 mm dia GI watering pipe, funnel, etc. all as specified and directed by engineer- in - charge.		6688.40 Each	4.00	26753.60		
	Total of Sch 'A' Part -V C/O to BOQ			**Rs**	**509872.00**		

Signature of Contractor
Date : _____

AAD (Contracts)
For Accepting Officer

SCHEDULE 'A' PART - VI
(SEWAGE DISPOSAL)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
1	M & L PCC (1:4:8) type D-2 using 40mm graded stone aggregate in foundation of manhole all as directed		5483.10 CUM	1.05	5757.26		
2	M & L for cement concrete 1:3:6 type C-1 using 20mm graded aggregate in copings, band plinth courses lacing courses parapets and railings upto 60 cm in height, copings, kneelers, apex stones, bed plates, kerbs, water troughs and the like including weathering, slightly rounded or chamfered angles and throating, as directed		8629.40 CUM	1.20	10355.28		
3	M & L PCC (1:2:4) type B-0 using 20mm graded aggregate in surface channel and drains including necessary formwork finished required shape all as specified and directed		6638.10 CUM	2.00	13276.20		
4	Extra for forming fair finished drain or channel 30 cm inner girth in cement concrete, using extra cement, including forms, moulds, mitred/ stopped ends etc. in manholes (inner girth only measures)		43.35 RM	2.00	86.70		
5	M & L for precast RCC (1:2:4) type B-1 using 20mm graded aggregate as in cover slabs of manholes, open drains including of formwork set in cement mortar 1:4 (reinforcement measured and paid separately) complete all as specified and directed. (Reinforcement shall be measured and paid separately)		11036.80 CUM	0.20	2207.36		
6	M & L for Mild steel bars 10mm dia and over, cut to length, bent to shape required, including cranking, bending spirally for hooping for columns, hooking ends and binding with and including mild steel wire (annealed) not less than 0.9mm dia or securing with clips		82.60 KGS	24.00	1982.40		
	C/O to next page			**Rs**	**33665.20**		

SCHEDULE 'A' PART - VI
(SEWAGE DISPOSAL) (CONTD..)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
	B/F from previous page			**Rs.**	**33665.20**		
7	M & L for rendering 15mm thick CM (1:4) on fair faces of brickwork or concrete surface, finished even and smooth using extra cement including mixing of water proofing compound @ 3% by wt of cement or as per manufacturer's instructions (supply only WPC shall be measured & paid separately) for internal surfaces of manholes		304.24 SQM	7.00	2129.68		
8	Supply only water proofing compound		46.10 KG	2.00	92.20		
9	M & L PCC (1:3:6) type C-2 using 40m graded aggregate for Concrete bed to 150/200mm dia drain pipes including packing under and haunching against the sides of pipes after they are laid and tested complete all as specified and directed.		466.89 RM	29.00	13539.81		
10	M&L for Cutting into existing manholes for connecting new drains, making good to pipe and rendering, cutting out existing benching for and forming branch channel (1/2 round or 3/4 section) in cement concrete 1:2:4 type B-1 smooth finished and reforming benching internal dia of pipe 150mm etc complete all as specified and directed.		1120.00 EACH	1.00	1120.00		
11	M & L for brick work with sub class 'B' bricks old sized straight or curved on plan exc 6.0M mean radius and built in CM1:4 etc complete all as specified and directed		5370.50 CUM	2.00	10741.00		
	Total of Sch 'A' Part -VI C/O to BOQ			**Rs**	**61287.89**		

Signature of Contractor
Date : _____

AAD (Contracts)
For Accepting Officer

SCHEDULE 'A' PART - VII
(ROAD/PATH/CULVERTS/HARDSTANDING)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
1	M&L hard core of guage n.exc 63mm thick depositing, spread and levelled in layers n.exc 15 cm thick watering and ramming to true surface with broken stone boulders complete all as specified and directed.		2070.80 CUM	40.00	82832.00		
2	M&L Cement concrete Type C-2 1:3:6 (40mm graded aggregate) in foundations, filling and mass concrete complete all as specified and directed.		5862.00 CUM	30.00	175860.00		
3	M&L Sand filling under floors or in foundations including watering and consolidation complete all as specified.		1974.30 CUM	10.00	19743.00		
4	M&L Machine pressed precast concrete interlocking paver block any shape and size confirming to IS 15658-2006 of 60 mm thickness, M-35 Grade with grey cement and no pigment complete all as specified and as directed.		741.60 SQM	200.00	148320.00		
5	M & L for PCC 1;2;4 type B-1 using 20 mm graded stone aggregate as in kerb stones of size 450mm x 450mm and the like including use of necessary form work complete all as specified and as directed.		8369.30 CUM	2.00	16738.60		
	Total of Sch 'A' Part -VII C/O to BOQ			**Rs**	**443493.60**		

Signature of Contractor
Date : _____

AAD (Contracts)
For Accepting Officer

SCHEDULE 'A' PART - VIII
(EXTERNAL WATER SUPPLY)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
1	Supply and lay pipe galvanised, "Medium grade" including fittings 40mm (1.5") dia complete all as specified and directed.		396.50 RM	30.00	11895.00		
2	Supply and lay pipe galvanised, "Medium grade" including fittings 25 mm (1") dia complete all as specified and directed		184.60 RM	24.00	4430.40		
3	Supply and fixing Gun metal globe or gate valve with iron wheel head screws both ends for iron pipe 40 mm dia complete all as specified and directed.		784.97 EACH	2.00	1569.94		
4	Supply and fixing Gun metal globe or gate valve with iron wheel head screws both ends for iron pipe 25 mm dia complete all as specified and directed.		587.24 EACH	2.00	1174.48		
	Total of Sch 'A' Part -VIII C/O to BOQ			**Rs**	**19069.82**		

Signature of Contractor
Date : _____

AAD (Contracts)
For Accepting Officer

SCHEDULE 'A' PART - IX
(EXTERNAL ELECTRIFICATION)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
1	Supply, laying and testing cable XLPE Insulated, screened, PVC bedded, galvanized steel strip or wire armoured, electric power cables (heavy duty) 1100 Volts grade with stranded aluminium conductor of size 50 sq mm 3.5 core complete all as specified and directed.		337.52 RM	50.00	16876.00		
2	Cutting of existing road, concrete/ bituminous surface by using of mechanical method of any type complete all as specified and directed Note:-PCC for making good road surfaces shall be measured and paid separately)		1077.00 CUM	0.50	538.50		
3	Material and labour for PCC (1:3:6) type C2 using (40mm graded stone aggregate) for making good disturbed road surfaces including necessary use and waste of form work complete all as specified and directed		5862.00 CUM	0.50	2931.00		
4	Supply and laying GI tube light grade Galvanised, laid in trenches Bore of Pipe 80 mm Complete all as specified and directed.		705.00 RM	12.00	8460.00		
5	M&L for sand cushioning in trenches for cable protection as per clause No.19.75 of SSR Part I complete all as specified and as directed.		1974.30 CUM	2.50	4935.75		
6	Supplying and laying un-reinforced precast concrete cable cover, class HVP, type 1 with peak, size 250mm x 150mm x 40mm complete all as specified and directed		44.20 EACH	200.00	8840.00		
7	Supply and fixing LED street light fitting 70 Watt 230 V AC outdoor type with high pressure die cast aluminium housing and heat resistant complete with driver, lamp bracket with impact and corrosion resistant including thermal management in multiple optics complete with IP 65/66 protection complete including wall mounted GI bracket with accessories complete all specified as directed.		5942.10 JOB	8.00	47536.80		
	C/O to next page			**Rs**	**90118.05**		

SCHEDULE 'A' PART - IX
(EXTERNAL ELECTRIFICATION) (CONTD….)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
	B/F from previous page			**Rs.**	**90118.05**		
8	Material and labour for Earthing complete with galvanised steel earth plate electrode 600mm x 600mm x 6.3 mm thick buried directely in ground vertically (earth pit not less than 2.25 metres deep below ground level) with top edge of the plate not less than 1.5 metres below ground level, connected to and including galvanised iron strip 25 x 4 mm as earthing lead by means of galvanised iron bolts, nuts, check nuts and washers etc and galvanised iron all as shown in electrical plate No 3 connected to earthing test point all as specified or indicated including testing on completion.		7164.70 / EACH	2.00	14329.40		
	Total of Sch 'A' Part -IX C/O to BOQ			**Rs**	**104447.45**		

Signature of Contractor
Date : _____

AAD (Contracts)
For Accepting Officer

SCHEDULE 'A' PART - X
(ARBORICULTURE)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
1	Supply and lay in trenches GI pipe pipe medium grade with all fittings and accessories ISI marked of following size						
	(a) 15mm size		130.00 RM	20.00	2600.00		
	(b) 25 mm dia		184.60 RM	15.00	2769.00		
2	S&F gun metal valve with iron wheel head threded both ends for iron pipe and fixed complete of following size.						
	(a) 15mm size		505.45 EACH	2.00	1010.90		
	(b) 25 mm dia		587.24 EACH	2.00	1174.48		
3	M&L continuous brick edging with burnt clay bricks of sub class 'B' bricks with width equal to the width of the brick, laid dry, on edge complete all specified as directed.		110.40 RM	200.00	22080.00		
	Total of Sch 'A' Part -X C/O to BOQ			**Rs**	**29634.38**		

Signature of Contractor
Date : _____

AAD (Contracts)
For Accepting Officer

SCHEDULE 'A' PART - XI
(RAIN WATER HARVESTING)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
1	S & F 150mm dia PVC (SWR) pipes single socketed in any length with rubber ring joints fixed with wall etc complete all as specified & directed.		736.26 RM	100.00	73626.00		
2	S & F 150mm dia PVC (SWR) bends in any shape all as specified & directed		142.20 EACH	30.00	4266.00		
3	M & L for composite rainwater harvesting system including under ground water storage tank of capacity 6000 ltr as a collection chamber, first flush system - 01nos, set of gravity filter – 01nos, delivery pipes of 25mm dia of 15mtr length, down take pipes of 100mm dia of 15mtr length complete all as specified & directed		140876.0 EACH	1.00	140876.00		
4	S & F loose filling with aggregates/ broken stone boulders of gauge 80 to 150 mm spread and leveled in layers in filter units		1178.00 CUM	1.60	1884.80		
5	S & F loose filling with aggregates/ broken stone boulders of gauge 40mm spread and leveled in layers in filter units		1603.90 CUM	1.40	2245.46		
6	S & F loose filling with aggregates/ broken stone boulders of gauge 20mm spread and leveled in layers in filter units		1692.00 CUM	0.80	1353.60		
7	M&L Sand filling under floors or in foundations or in filter bed including watering and consolidation complete all as specified.		1974.30 CUM	0.80	1579.44		
	C/O to next page			**Rs**	**225831.30**		

SCHEDULE 'A' PART - XI
(RAIN WATER HARVESTING) (CONTD…)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
	B/F from previous page			**Rs.**	**225831.30**		
8	M & L for brick work with sub class 'B' bricks old sized straight or curved on plan exc 6.0M mean radius and built in CM1:4 etc complete all as specified and directed.		5370.50 CUM	0.50	2685.25		
9	M & L PCC (1:4:8) type D-2 using 40mm garded stone aggregate in foundation of manhole all as directed		5483.10 CUM	0.30	1644.93		
10	M & L for rendering 15mm thick CM (1:4) on fair faces of brickwork or concrete surface, finished even and smooth using extra cement etc complete all as specified and directed		304.24 SQM	4.00	1216.96		
11	M & L for precast RCC (1:2:4) type B-1 using 20mm graded aggregate as in cover slabs of manholes, open drains incl of formwork set in cement mortar 1:6 (reinforcement measured and paid separately) complete all as specified and directed.		11036.80 CUM	0.40	4414.72		
12	M & L for Mild steel bars 10mm dia and over, cut to length, bent to shape required, including cranking, bending spirally for hooping for columns, hooking ends and binding with and including mild steel wire (annealed) not less than 0.9mm dia or securing with clips		82.60 KG	40.00	3304.00		
	Total of Sch 'A' Part -XI C/O to BOQ			**Rs**	**239097.16**		

Signature of Contractor
Date : _____

AAD (Contracts)
For Accepting Officer

SCHEDULE 'A' PART - XII
(REFRIGERATION/AC & WATER COOLER)

Note :- All excavation under this Schedule shall be measured and paid under Sch 'A' Part -II

Sl No.	Brief Description of items	Drg Nos No	Unit Rate (in figures) Rs Ps	No of units Required.	Amount Rs Ps	Period of completion	Remarks
1	2	3	4	5	6	7	8
1	Supply and fix Deep freezer hard top more than 425 Litre capacity having double door complete all as specified and directed.		33340.27 Each	1.00	33340.27		
2	Supply and fix water cooler electric driven (single phase), having approx storage capacity of 40 litre and nominal cooling capacity of 40 Litres per hour		33884.60 Each	1.00	33884.60		
3	Supply and fix electric water heater, storage type steel body with copper inner tank and heating element upto 2 KW capacity 25 litre, BEE 5 Star rated complete with all accessories such as safety valve, thermostate, NRV, connection piece etc. complete all as specified and directed		10029.54 Each	9.00	90265.86		
	Total of Sch 'A' Part -XII C/O to BOQ			**Rs**	**157490.73**		

Signature of Contractor
Date : _____

AAD (Contracts)
For Accepting Officer