TENDER SCHEDULE

Sub: - Work Contract for Condenser tube replacement in unit No. 1 & 2 of PH-I, SGTPS, MPPGCL, Birsinghpur

Sl. No.	Description of work	Qty (Nos.)		
		UNIT-1	UNIT-2	TOTAL
	Condenser tube replacement in unit No. 1 & 2, SGTPS, MPPGCL, Birsinghpur as per scope of work. ***Tube details:-*** ***1. OD of tube: 25.4 mm*** ***2. Thickness: 1 mm*** ***3. Length : 7450 mm*** 4. ***Tube material :Cu-Ni (90/10)***	5000	5000	10000

1. Contractor shall provide safety belts, shoes, helmets etc to all its workers as per requirement of the work at its own expenditure. In case of non compliance of safety rules by the contractor the requisite safety appliance shall be provided by MPPGCL and the cost of the same including supervision charges @ 24% shall be recovered from the contractor's bill

2. All the existing and future legal/financial/other liabilities of the contract shall be in the scope of the contractor
3. Evaluation: The contract shall generally be awarded on total package basis.
4. Payment shall be made on actual work basis.
5. Extension of Contract: The contract period and/or quantity may be extended by 25% on same rate, terms & condition. Contractor shall be bound to accept the same. Any further extension in contract shall be done after obtaining consent of the contractor.
6. The bidders at their own discretion and cost may visit the site before quoting their rates.
7. Biometric attendance of the labour engaged for the work shall be maintained by the contractor.

SUPERINTENDING ENGINEER (Works)
O/o C.E. (Gen.)
SGTPS, MPPGCL, BIRSINGHPUR

SCOPE OF WORK

01. Before opening of condenser water box cutting of beam, removal of platform and other pipes, which are essential for the opening of water box, which is nearby, fitted at top of water box.
02. Opening of condenser water box door, manholes and removal of sludge and dust from water boxes.
03. Make appropriate platform (Bhada) for proper replacement and inserting the condenser tubes.
04. Shifting of new tubes from stores to the work place and return of old damaged tubes back to the stores.
05. Removal of the plugs from the leaky tubes scattered on RHS (Top & Bottom) Zones of condenser prior to cutting all tubes.
06. Cleaning of the tubes support plates including end plates before insertion of new tubes for proper alignment of tubes. Repair of damaged tubes holes if any.
07. Water filling in condenser on shell side up to the level of vacuum breaker valve after Jacking the condenser and release of Jack bolts after satisfactory completion of hydraulic test.
08. Replacement of leaky tubes, if found during hydraulic test of condenser.
09. Closing of condenser water box and manholes after work completion.
10. All the associated works involved for the complete replacement of condenser tubes are in Contractors scope of work.
11. The work shall be carried out in three shift per day (i.e. 8 hours in each shift).
12. The tube replacement work are must be completed within 20 days in each unit.

GENERAL TERMS & CONDITIONS

01. Watch and ward of new condenser tubes and old condenser tubes are in Contractors scope.
02. Expansion of tubes ends to the desired limit under controlled torque (as per Standard value) for leak proof performance of condenser tubes.
03. All the necessary T & P, consumables and manpower are in Contractors scope of work to complete the work satisfactorily.
04. The contractor has to engage sufficient skilled manpower and pay them as per rules of Government and strictly adhere to all the statutory obligations under factories Act, Contract Labour Act, Minimum Wages Act, Payment of Wages Act, and EPF Act etc.
05. Any damage/loss to Board property will be recovered by the contractor.
06. The Contractor will be responsible safely of Board's equipment. The contractor and his workers should strictly follow all the safely rules and abide by safely precautions.
07. The contractor has to complete the work within stipulated period. In case of delay in work penalty will be imposed @ 2% of delayed work on per day basis subject to a maximum of 20% order value.
08. The Contractor and his workers have to follow Power House security rules.
09. The contractor has to issue safety appliances to his workers and abide safety precautions as per factory act.
10. The contractor should get their worker insured and obtain valid labour license.
11. The Contractor has to follow all the terms and conditions as per tender documents.
12. The Contractor has to arrange accommodation at his own cost. Accommodation shall be provided by MPPGCL on chargeable basis, if available.
13. Payment for this work will be made on actual work executed (Actual no. of tubes replaced).
14. After completion of tube replacement and box up of condenser, painting work of front and rear water box will be carried out by contractor's scope of work.

SUPERINTENDING ENGINEER (Works)
O/o C.E. (Gen.)
SGTPS, MPPGCL, BIRSINGHPUR