Project Estimate

Project Details

ject Number: PW1-212-23-221

B: Neemuch Nagar Palika

partment: Public Work Departme

Work : CON. OF CROSSING W.NO.19 NEAR PUBLIC TOI

G/L Code : 4124011012 ROADS & BRIDGES-FOOT

PAC 218,645.77

Total Submitted PAC(ULb):0.00

Activity / SOR / NON SOR and WBS Details

SN NO	Activity Number	Description	Count	L	B	H	Quantity	Unit	Price / Unit	Amount	Remarks
	NII-2.6.1	exvation work with 05KM Extra lead	1	8	1.70	1.75	23.800	M3	151.00	3593.80	
			1	10	1.60	1.75	28.000	M3	151.00	4228.00	
	NII-4.1.6	CEMENT CONCRETE GRADE M-10 (NOMINAL MIX) WITH 40 MM MAXIMUM SIZE OF STONE AGGREGATE: PROVIDING AND LAYING IN POSITION CEMENT CONCRETE OF SPECIFIED GRADE EXCLUDING THE COST OF CENTERING AND SHUTTERING ALL WORK UP TO PLINTH LEVEL:	1	8	1.70	0.10	1.360	M3	4112.00	5592.32	
			1	10	1.60	0.10	1.600	M3	4112.00	6579.20	
3.1	NII-5.1.1	CEMENT CONCRETE GRADE M-20 (NOMINAL MIX) WITH 20 MM MAXIMUM SIZE OF STONE AGGREGATE :-"PROVIDING AND LAYING IN POSITION SPECIFIED GRADE OF REINFORCED CEMENT CONCRETE EXCLUDING THE COST OF CENTERING, SHUTTERING, FINISHING AND REINFORCEMENT : ALL WORK UP TO PLINTH LE VEL :"	1	10	1.50	0.15	2.250	M3	5435.00	12228.75	
			1	8	1.60	0.15	1.920	M3	5435.00	10435.20	
			2	8	0.20	1.50	4.800	M3	5435.00	26088.00	
			1	8	1.60	0.25	3.200	M3	5435.00	17392.00	
			2	10	0.15	1.50	4.500	M3	5435.00	24457.50	
			1	10	1.50	0.20	3.000	M3	5435.00	16305.00	

Scanned with OKEN Scanner

Project Estimate

Project Details

Project Number: PW1-2122-2342221

ULB: Neemuch Nagar Palika

Department: Public Work Department

Work : CON. OF CROSSING W.NO.19 NEAR PUBLIC TOI

G/L Code : 4124011012 ROADS & BRIDGES-FOOT

PAC 218,645.77

Total Submitted PAC(ULb):0.00

Activity / SOR / NON SOR and WBS Details

BSN (SNO)	Activity Number	Description	Count	L	B	H	Quantity	Unit	Price / Unit	Amount	Remarks
5.1	NII-5.11.2	HOT ROLLED DEFORMED BARS REINFORCEMENT FOR R.C.C. WORK INCLUDING STRAIGHTENING, CUTTING, BENDING, PLACING IN POSITION AND BINDING UPTO FLOOR LEVEL INCLUDING COST OF BINDING WIRE, WASTAGE AND OVER LAPS UPTO 12MM HORIZONTAL/ INCLINED POSITION OF REINFORCEMENT BARS IN SLAB AND BEAMS PLINTH, CHAJJAS, LINTELS UPTO 4.5M VERTICAL LENGTH OF REINFORCEMENT IN WALL COLUMNS, OVER LAPS SHALL BE PROVIDED AS PER REQUIREMENT OF IS : 13920, IS:456 & SP : 34) ETC. COMPLETE."	11				1140.000	KG	58.00	66120.00	
6.2	NII-19.1.1	"FOUNDATIONS, FOOTINGS, BASES OF COLUMNS, ETC. FOR MASS CONCRETE" AGAINTERING AND SHUTTERING INCLUDING STRUTTING, PROPPING, STREETCHING ETC. COMPLETE FOR AND REMOVAL OF FORM WORK BY SHEET PLATE OR PLY WOOD SHUTTERING FOR"	22	10	1.50		30.000	M2	160.00	4800.00	
			22	8	1.50		24.000	M2	160.00	3840.00	
			22	8	1.65		26.400	M2	160.00	4224.00	
			22	8	0.25		4.000	M2	160.00	640.00	
			22	1.60	0.25		0.800	M2	160.00	128.00	
			22	10	1.65		33.000	M2	160.00	5280.00	
			22	10	0.20		4.000	M2	160.00	640.00	
			22	1.50	0.20		0.600	M2	160.00	96.00	

Scanned with OKEN Scanner

Project Estimate

Project Details

roject Number: PW1-2112-233-2221

LB: Neemuch Nagar Palika

epartment: Public Work Departme

Work : CON. OF CROSSING W.NO.19 NEAR PUBLIC TOI

G/L Code : 4124011012 ROADS & BRIDGES-FOOT

PAC 218,645.77

Total Submitted PAC(ULb):0.00

Activity / SOR / NON SOR and WBS Details

BSN SNO	Activity Number	Description	Count	L	B	H	Quantity	Unit	Price / Unit	Amount	Remarks
8.1	NH-19.1.3	SUSPENDED FLOORS, ROOFS LANDINGS, BALCONIES AND ACCESS PLATFORM CENTERING AND SHUTTERING INCLUDING STRUTTING, PROPPING STRETCHING ETC COMPLETE FOR AND REMOVAL OF FORM WORK BY SHEET PLATE OR PLY WOOD SHUTTERING FOR	11	8	1.20		9.600	M2	305.00	2928.00	
			11	10	1.0		10.000	M2	305.00	3050.00	

Scanned with OKEN Scanner

Project Estimate

Project Details

roject Number: PW1-212-23-221

LB: Neemuch Nagar Palika

Department: Public Work Departme

Work : CON. OF CROSSING W.NO.19 NEAR PUBLIC TOI

G/L Code : 4124011012 ROADS & BRIDGES-FOOT

PAC 218,645.77

Total Submitted PAC(ULb):0.00

Activity / SOR / NON SOR and WBS Details

SNO	WBS NO	WBS Text	Amount
	PW1-212-23-221.001	CON. OF CROSSING W.NO.19 NEAR PUBLIC TOI	218645.77
		Total PAC	218645.77

reated by (Sub eng / A.E) digitally signed by: Om Prakash Parmar SUB ENGG. IST : Jul 18, 2023 5:40:09 PM

orwarded by (CMO / omm) and digitally igned by: Mahendra Vashishtha CMO IST: Jul 18, 2023 5:44:21 PM Neemuch Nagar Palika

GST 39,356.24

Gross 258,002.01

TECHNICAL SANCTION AS PER CONDITIONS,VIDE, Notification - 100000211265

Dated : 2023-09-14

For Construction of : CON. OF CROSSING W.NO.19 NEAR PUBLIC TOI

At ward No : 1 **Gross Granted for RS** : 258002.01

In Words : TWO LAKH FIFTY EIGHT THOUSAND TWO Rupees ONE Paise

GST 18% applicable on this Project,GST = 39356.24

Checked by :Sub.Eng. / A.E(optional)

Checked by (Sub eng and digitally signed	IST:-12:00:00 AM	Checked by A.E and digitally signed	IST: - 12:00:00 AM

Note: नोटशीट पर स्वीकृति अनुसार नाली निर्माण किया जाना है जबकि प्रस्ताव तथा प्राक्कलन अनुसार क्रासिंग निर्माण किया जाना है प्राक्कलन पर तकनीकी स्वीकृति जारी की जाती है

Assistant / Executive / Superintendent Engineer
Urban Administration & Development, Ujjain Division

A.E/ E.E/ S.E MANOJ KUMAR GHOSH Digitally signed by MANOJ KUMAR GHOSH Date: 2023.09.14 17:21:57 +05'30'

S.E

Scan to Verify TS

Important Note: Valid only after digital signature of CMO/Commissioner and EE

Scanned with OKEN Scanner