OFFICE OF THE MUNICIPAL COUNCIL,Shivpuri (M.P.)

ıtimate for the construction of .C.C. Road
.O.R.Based on UADD Bhopal 02 Aug 2021)
ce :- W.33 manku ram master to amjad khan

Description of work	NO	length	width	depth	Qut	unit	Rate	Amount
Excavation for roadwork in soil with hydraulic excavator including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location with all lifts and lead upto 1000m as per relevent clauses of section-300 of specification..	1	130	4.5	0.3	175.5	cum	65	11407.50
	Total				175.5			
ransportation By Mechanical means including ading, unloading and stacking					131.625	cum	85.88	11303.96
onstructionof granularsub-base providingCoarsegradedmaterial BR>30),spreadinginuniformlayerswithmotorgr deronprepared rface,mixingbymixinplacemethodatOMCandc npactingwith ratoryrollerof80-10KNStaticweighttoachievethedesireddensity, mplete in all respect as per relevant clauses section-400.	1	130	4.5	0.1	58.5	cum	689	40306.50
onstruction of Dry lean cement concrete Sub-se over a prepared subgrade with coarse and e aggregate conforming to IS: 383, the size of arse aggregate not exceeding 26.5mm, gregate cement ratio not to ceed 15:1, aggregate gradation after blending be as per MORTH ecifications Table 600-1, cement content not be less than 150 /cum, optimum moisture content to be termined during trial length nstruction, concrete strength not to be less an 10 Mpa at 7 days, xed in a batching plant, transported to site, d with paver with ectronic sensor/mechanical paver, compacting th 8-10 tonnes ratory roller, finishing and curing and as per levant clauses of section601.	1	130	4.5	0.1	58.5	cum	3017	176494.50
	Total				58.5			

Scanned with OKEN Scanner

duct from Item No.6.1 above if paver with tronic sensor/ hanical paver, is not used and laying is e by any other method. te :- The acceptance criteria regarding level, kness, surface larity, texture finish, strength of concrete all other quality trol measures shall be the same as in case achine laid work.) s item is to be executed with Prior written mission of Engineerin-charge					58.5	cum	211	12343.50
								164151.00
nstruction of dowel jointed, plain cement ncrete pavement in M-30 de concrete over a prepared sub base with or higher grade cement, arse and fine aggregate conforming to IS:383 ximum size of coarse regate not exceeding 25 mm, mixed in a ching and mixing plant as approved mix design, transported to site, with a fixed form or slip n paver with spreading the concrete by vels, rakes compacted ng needle, screed and plate vibrator and shed in a continuous eration including provision of contraction, ansion, and longitudinal ts, joint filler, separation membrane, sealant ner, joint sealant, onding strip, placing of dowel bar,tie rod nixtures as approved,	1	130	4.5	0.2	117	Cum	5583	653211.00
	Total				117			
duct from Item No.6.2, 6.3 and 6.6 above if er with electronic sensor ot used and laying, compaction is done by other method te :- The acceptance criteria regarding level, kness, surface ularity, texture finish, strength of concrete d all other quality ntrol measures shall be the same as in case machine laid work.)					117	Cum	391	45747.00
								607464.00

Scanned with OKEN Scanner

idingandlayingnon-sureNP2class(lightduty)R.C.C. swithcollarsjointedwithstiffmixtureofcement arintheproportionof1:2(1cement:2finesand)i dingtestingofjoints complete :: 250 mm dia. R.C.C. pipe	3	5			15	RM	499	7485.00
	Total				15			
							Total	842117.96
							GST 18%	151581.23
							Say Rs.	993699.19

ngineer
al Council
ri (M.P.)

Asst Engineer
Municipal Council
Shivpuri (M.P.)

Chief Municipal Officer
Municipal Council
Shivpuri (M.P.)

Scanned with OKEN Scanner